

PRICE BID

AUDIO SYSTEM WORKS FOR AUDITORIUM AT LOCAL HEAD OFFICE BUILDING, BHOPAL.

SR.N O.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	AUDIO SYSTEM				
	NOTE:- ALL ITEMS PROVIDING AND INSTALLATION WORK COMPLETE IN ALL RESPECT. THE SYSTEM HAS COMPLETE ONE YEAR WARRANTY AND INCLUSIVE OF OPERATOR COST OF AUDIO SYSTEM OPERATION, WHENEVER REQUIRED UNDER DEFECT LIABILITY PERIOD.				
1	Line Array :Providing at site Line Array speaker, make:- Ahuja and model no. ALX-6000 or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	8		
2	Amplifier :Providing at site Amplifier, make:- Ahuja and model no. LXA-4500 or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	2		
3	Monitor Speakers: Providing at site Monitor Speakers, make:- Ahuja and model no. SMS-450P or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	2		
4	Amplifier :Providing at site Amplifier, make:- Ahuja and model no. LXA-2000 or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	1		

5	Sub Woofer :Providing at site Sub Woofer, make:- Ahuja and model no. SWX-1010 or equivalent (Pulz /JBL/British Acoustics/Bose)	No	2		
6	Mixer :Providing at site Mixer, make:- Ahuja and model no. Promix-1442 or equivalent (Pulz /JBL/British Acoustics/Bose)	No	1		
7	Graphic Equalizer :Providing at site Graphic Equalizer, make:- Ahuja and model no. AGE-31X2 or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	1		
8	PA Audio Splitter :Providing at site PA Audio Splitter, make:- Ahuja and model no. DA-88 or equivalent (Pulz /JBL/British Acoustics/Bose)	No	1		
9	Providing at site Podium make:- Ahuja and model no. ASL-3000R. Including one stand mic and two cordless mic..or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	1		
10	Providing at site Cordless Microphone, make:- Ahuja and model no. AWM-700U2.or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	1		
11	Providing at site Cordless Microphone, make:- Ahuja and model no. AWM-700UHL. or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	1		

12	Providing and fixing Chain pully for Line array speaker hanging as per line-array speaker load bear and approved by bank engineer. Including manpower, supporting equipment's, required chain system etc. All work complete in all respect.	Nos	2		
13	Providing at site Speaker cable 2 Core 2.5 Sqmm, make:- Mapson or equivalent	Roll	2		
14	Providing Rack for Line - Array speakers, make:- Wallrack or equivalent	Nos	2		
15	Providing at site Flybar frame, make:- Ahuja and model no. ALF-06. or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	2		
16	Providing at site Microphone Stand , make:- Ahuja and model no. DGT. or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	1		
17	Providing at site Microphone Stand , make:- Ahuja and model no. DGN. or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	1		
18	Providing at site Wired Microphone including connecting cable upto 20.0m length with required connectors etc. , make:- Ahuja and model no. Pro-2200SC.or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	2		

19	Providing at site Servo Stabilizer - 20KVA including required connection, power cables, socket, Plug connections etc. , make:- Dachi or equivalent	Nos	1		
20	Providing at Boundary Layer Microphone. , make:- Ahuja, Model No. ABM-301M / 301 H. , or equivalent (Pulz /JBL/British Acoustics/Bose)	Nos	4		
21	Installation, commissioning & training of above mentioned work including Technical team, manpower, tools & tackles etc. All works completed in all respect up to satisfactory of end user.	Job	1		
22	Providing and Fixing M.S.Bracket, base plate, Purlin other frame work etc. made out of MS (square pipes, Round Pipes, Rectangle Pipes, Plates, round pipes, square bars, channels, ISMB etc.) as per the design and details, supported on existing R.C.C. frame . The structure shall be Welded by Arc Welding of superior quality using best quality Electrodes and Standard Welding Equipment, Chisel cutting, bending, grinding, drilling etc. hammering excess deposits and then finishing with surface grinders including erection. The Rates includes Cost of Anchor Bolts, Anchor fasteners(Dia. up to 16mm) with thread, Washers, Nuts etc. All work complete in all respect. Including 2 or more coat Primer & Painting with Superior Quality Steel Primer (Asian ,Narolac, Deluxe). Note:- Including Anchor fasteners make Hilti with chemical 12 to 12mm Dia. required as per site or directed by Engg. Incharge.	KG	1500		

23	<p>Existing false cutting, removing and providing and fixing New Fully Perforated Gypsum Plaster Board having approx. 15 % perforated area with perforation size and pattern as approved by the Engineer-in-charge and as per manufacturer's specification, with all 4 side tapered and backed by acoustical tissue with NRC value not less than 0.60. Including USG BORAL Concealed Ceiling Frame Work. as per the designs & specifications. As per drawing & as per instruction of site incharge. Section Size.</p> <p>1) 51x26x26x3660x0.50mm - USG Boral ST-50 Ceiling Section</p> <p>2) 45x15x15x3660x0.90mm - USG Boral ST-50 Intermediate Channel</p> <p>3) 25mm X 6mm -USG Boral Drywall Screws</p> <p>4) USG Boral ST-50 Wire connecting clip</p> <p>5) Pentagon Nylon Sleeve and steel Screws 6).Including plastic emulsion paint on wall/ceiling for first quality sheen finish of approved shade and quality in 2 coats with required putty, including labour, safety equipment's, wastage etc. All work complete in satisfactory upto architects. Make:- Asian, Berger or equivalent. Note:- Including Trap Door provide for Line Array maintenance work with hinges, Tower Bolt, required G.I. channel or M.S. Pipe framing etc, size of trap door as per site condition or as per directed by Engg. In charge.</p>	SQM	25		

24	Providing, assembling and after work finish removing at site. Required M.S. Pipe scaffolding including working platform, safety belt, transportation etc. all safety parameter in contractor scope. Working area is approx. 8.0 SQM and scaffolding at site up to work finish level and as per directed by Engg. In-Charge.	Nos	2		
25	Working area cleaning in all respect and as per directed by Engg. In-Charge. Including manpower approx. 6 person and required tools and tackles plus all waste material removing at site.	Job	1		
	TOTAL AMOUNT OF SUPPLY, LAYING, INSTALLATION, CALIBRATION AND TRAINING				

GST will be paid additionally

	FULLY COMPREHENSIVE ANNUAL MAINTENANCE CONTRACT (AMC) :- Rates to be quoted by the Agency/contractor for fully comprehensive AMC inclusive of all (Amplifiers, Speakers, Microphone, Mixer, Sub-Woofer, Cables, stabilizer etc. and all electrical, mechanical equipment's associated with above works etc) including operator for audio operation for complete system for next five years after the defect liability period of one year. The operator cost is inclusive under defect liability period also.				
	DESCRIPTION OF ITEMS	Yearly)		Yearly AMC Amount	
	For 1st Year @% of Part-'A'. without GST , fully comprehensive AMC of above Audio System Works after the Defect liability period of One year				
	For 2nd Year @				
	For 3rd Year @				
	For 4th Year @				
	For 5th Year @				
	Note:- The above AMC rates are indicative and for reference only and Bank's has discretion to consider or not consider, the AMC rate				

GST will be paid additionally