

BOQ FOR INTERIOR DECORATION OF E-LOBBY AT HAZARIBAGH BRANCH

Sr.No.	Description of Item	Unit	Quantity	Rate (Rs)	Amount(Rs)
1	Supply and fixing 4 mm thick ACP panels for paneling to walls with 25mmx38mmx1.5mm thick aluminum pipe sections for framing at 600mm intervals horizontally and vertically as per manufactures specification. The rate shall include cost of all material and labor etc. The panels should be pre-fabricated panel made out of light weight concrete core composed of Portland cement, binder's siliceous and micaceous materials aggregate with tongue and groove arrangement with two 4mm thick fiber reinforced cement facing sheets. The grooves and joints in the panels should be filled with suitable fillers. The rate shall include cost of necessary fixing material like cleats etc.	Sqm.	100.00		
2	<u>12 MM THICK TOUGHENED GLASS/ PARTITION DOOR ETC</u> Providing and fixing / fitting 12 mm thick toughened glass of approved make with all necessary hardware accessories etc including cost of labours and materials etc as per Corporate Centre, Mumbai approved materials Colour etc and specifications and the direction of E / I.	Sqm.	60.00		
a	Floor Spring	Nos	2.00		
3	Providing and fixing self adhesive Sparkle series Frosted Film and/or one way vision film of 3 M make as per design. The film are to be pasted on main glass door & other glasses as directed, cut & fixed as per design including the Bank's logo. Supporting cash memo/bills are to be produced for payment of this item including certificate from the dealer certifying use of the product. Executed area of the film pasted on glasses shall be measured for finished work.	Sqm.	180.00		

4	<p>Providing and fixing of Armstrong's Mineral Fiber Acoustical False ceiling tiles of type Prima Fine Fissured RH-99% or equivalent of approx size 600 mm x 600 mm x 15 mm with square / tegular edge at all heights. The tiles shall be laid on Armstrong's / Manufacturer's prescribed standard shape, size, thickness etc. made. Main frames /Runners (24mm x 38mm x 3600mm), T-Section, Cross tees (minimum 22mm x 22mm) or equivalent standard quality approved by the bank. Prelude XL Hot dipped galvanized exposed grid with 15 m with T-section exposed flanges which shall be powder coated white / off-white. The frame work will compromise of main runner made from 0.33 mm thick GS Sheet and of size 24 mm x 38 mm x 3600mm and spaced at 1200 center securely fixed to the structural soffit by approved hangers at 1200 mm maximum center. Hangers (GI wire of 4.0 mm dia) at the interval of 1200mm to be fixed by approved rawal plug, with all taxes, materials, labor etc. as per the prevailing standard, design, specification and direction of the bank. The last hanger at the end of each main runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be interlocked</p>	Sqm.	35.00		
---	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------	-------	--	--

5	<p>Providing and fixing in position Seamless Gypsum Board Plain False Ceiling in one or more levels as directed including vertical surfaces between different levels.</p> <p>The Ceiling including vertical surfaces is to be done with 12.5 mm thick plain Gypsum boards of approved make, duly finished with recommended filters, tapes, etc. to have a seamless flush look.</p> <p>The ceiling system is to be fixed to a concealed GI framework (Gypsteel Ultra make or approved equivalent) by 25 mm long GI drywall screws at 250 mm intervals along both ways.</p> <p>The framework shall be suspended securely from MS angle hangers fixed to true ceiling surface by dash fasteners.</p> <p>The whole system is to be fitted with all necessary arrangements like perimeter channels, intermediate channels, ceiling sections, ceiling suspension angles, rawl plug, soffit cleat etc.</p> <p>The work includes applying two coats of approved putty & primer suitable for Gypsum boards after necessary surface preparation and final painting with approved acrylic emulsion paint on the surface.</p> <p>Provisions for openable type lids for facilitating arrangements for rolling shutters are to be made as required.</p>	Sqm.	30.00		
# GST EXTRA AS APPLICABLE				TOTAL	