

**Project Name:- Construction of Residential Twin Towers at Plot No 41, Gift City, Gandhinagar**

**BOQ of Proposed Site Barricades & Gates**

Sr. No	Item of Work	Unit	Qty	Rate	Amount
1	Providing & Erecting Barricades as per given design and drawing, item includes taking pits of 600 mm X 600 mm X 600 mm size in Soil by mechanical means (Hydraulic excavator)/manual means over areas including getting out and disposal of excavated earth off the site as per approval from the local governing Authority, including necessary permission at site, Concreting in pits with M20 grade /1:1.5:3 concrete, embedding Structural Steel vertical member with MS Plate of 250 X 250 X 5 mm thk at the base of Vertical Member of Barricades. Providing Horizontal Steel Tube 50 X 50 X 4 mm Structural members for Barricades, 50 X 50 X 4 mm Thk Tube for framing of gate, 40 X 40 X 5 mm Angle bracing, ISMC 150 mm Side posts for Gates, 100 mm ISMC Vertical members for Barricades as per given drawings, Item also includes red oxide zinc chromate primer one coat and 2 coats of Oil Painting of approved brand and manufacture on steel steel works. Item also includes All necessary harware, hinges, , locking arrangement for Gates etc. Complete.	Sq m	900.00		
	Item include providing and fixing 0.8 mm thk. pre-coated galvalume corrugated /plane sheet of approved make				
	<b>Only Exposed Pre-coated Sheet Area shall be measured for the Payment</b>				
	Approved Steel Make:- SAIL, RINL, Tata, Jindal, Surya, Appolo				
	Approved GI Precoated Sheet Make:- Swastik, Jindal, Tata, Surya,				
	Approved Paint:- Asian, Nerolac, Dulux				

