

BOQ FOR TILING WORKS & DRAIN GRATING WORKS AT STATE BANK OF INDIA, ADMINISTRATIVE OFFICE, URBAN STATE PHASE-II BATHINDA.

SI. No.	Description of Item	Qty.	Unit	Rates	Amount
	TILING & DRAIN GRATING WORKS				
	Note: It is the responsibility of the vendor to co-ordinate with other vendors/ bank officials and state/ central departments etc as required. Vendor to arrange its own electricity supply/ water arrangement etc required for its working & operations. However, if available at site, vendor could use the same. The rates mentioned in the items to include all lead and transportation and no additional payment will be paid on account of lead and transportation charges. The vendor is required to dispose of all the rubbish/ unserviceable material to the nearest dumping ground & no additional payment will be made in this regard. The vendors are advised to visit the site and understand the requirements first, thereafter quote their rates and in case of any query regarding the technical aspect or item/ requirement, he may contact the Project Architect/ Engineer – In – Charge.				
1	FLOOR TILES INCLUDING SKIRTING & DADO	1625	Sqft		
	Providing and laying Doubly charged/ Full body charged (as approved by the Engineer – In – Charge/ Bank Officials) Vitrified tiles of size 800 mm x 800 mm or as approved by the Engineer – In – Charge/ Bank Officials in floor in different sizes and approved groove pattern (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colors and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @ 3 kg/ sqm including grouting the joints with epoxy and matching pigments etc. The tiles must be cut with the zero chipping diamond cutters only. Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily. The item to include the cost of brick ballast/ PCC/ mortar etc required below the tile surface to either raises the level/ makes the base strong/ hard. The item to include tiling on walls/ dado and it will be measured separately.				
2	DRAIN GRATING WORKS	1475	kg		
	Providing and fixing drain grating works of Mild Steel at the approved location of approved size & shape as per the directions of Project Architect/ Bank Officials. The M.S flats to be used should be of 5 mm thick with 50 mm wide. The vendor to check the shape/ size of the M.S Flats at site & get the same approved from the Engineer – In - Charge before supplying the same. The M.S flat sections to be welded at each joint as required so as to provide a complete strong joint. The spacing between M.S flats to be 50 mm each. The fabricated section should be fixed in the angle sections which are already in place at the site. The item to also include cleaning of drains before fixing the sections on the existing angle sections.				
3	ENAMEL PAINT	1	LS		
	Providing & applying Enamel Paint on the new supplied MS drain gratings as well as the existing/ already fixed MS drain gratings at site. The item to also include the scrapping of rust of the existing/ already fixed drain gratings before painting the same. The item to also include the painting of existing/ already fixed all the angle sections at site by first scrapping the rust & thereafter painting the same. All other works which are required to be done in order to paint the existing angle sections, existing MS flats of drain gratins & newly supplied MS flats of drain gratings are included in this item.				
	Total value of works				

GST will be paid extra as applicable