

SCHEDULE OF QUANTITIES FOR TERRACE WATER PROOFING WORKS AT JUBILEE BHAVAN, ERANHIPALAM

Civil Works:-					
Sr. No.	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Dismantling the worn out plaster, unsound RCC work, loose surface, etc. and plastering the surface in cement mortar 1:4 complete, including fixing of chicken mesh, wherever applicable, curing, disposal of waste material, repairs to cracks including cutting the patch in proper shape and applying approved quality chemical water proofing treatment to surface at all height including scaffolding, etc. at all lead and lift as directed by Engineer-In-Charge.	100	Sqm		
2	Waterproofing Treatment on Terrace : Providing and applying one coat of mortar and screed modifier cum bonding aid, Fosroc Nitobond SBR (or equivalent approved material of CERA/DR.FIXIT etc.) over prepared concrete surface strictly maintaining the coverage specified by the manufacturer. Then applying two coats of polymer modified cementitious water proof coating Fosroc Brush bond cover (or equivalent approved material) on the prepared concrete surface strictly maintaining the coverage specified by the manufacturer, consist of a liquid polymer compound (4 Ltr) and a cementitious powder component (23 Kg), which shall be mixed as per instructions. Before coating, the surface is to be prepared to remove all loose mortar and laitance, dust dirt, oil, grease etc and cleaning with pressure water gun/jet etc.	550	Sqm		
Total amount (Excluding GST)					
* GST as applicable will be paid extra					