

**PRICE BID FOR AIR CONDITIONING WORK OF DRT-2 AT 3TH FLOOR, BHIKHUBHAI CHAMBER,  
AHMEDABAD**

Sr.No.	Description	Quantity	Unit	Rate	Amount
<b>[A]</b>	<b>AIR CONDITIONING WORK</b>				
<b>[I]</b>	<b>MACHINE PART</b>				
2	Supplying & providing of <b>Hi-wall Inverter Split Type AC</b> with high wall mounted indoor and out door unit. having <b>eco friendly</b> refrigerant. Including indoor unit outdoor unit and cordless remote Machine shall have <b>copper condensor</b> Unit, Make: Carrier / Hitachi / Daikin / Mitsubishi Heavy Industries / Toshiba / Trane / Voltas / Panasonic. <b>[Mini 5 Star rating Inverter]</b>				
2[a]	Inverter Hi-wall Split AC of 2.00 TR	2	NO		
2[b]	Inverter Hi-wall Split AC of 1.50 TR	2	NO		
	<b>TOTAL FOR PART- I</b>	4			
<b>[II]</b>	<b>LOW SIDE WORK</b>				
2	Installation charges for above 2.0TR/1.50TR/ 1.00 TR Split A/C including <b>3.0 Rmt copper</b> tubing and electrical wiring connection etc. complete.	4	NO		
2[b]	Removing and Reinstallation charges for existing <b>1/1.5/2 TR High wall mounted split A/C</b> at new premisses location on 3rd Floor including connection servicing & gas filling complete as directed. [Entire new copper piping and drain shall be paid as per item No 3[a] & 4] <b>Rate Also includes Shifting from Existing Premises 2nd Floor to New Premisses on 3th Floor including indoor and outdoor with MS stand etc complete as directed.</b>	12	NO		
3[a]	Referigerant piping - insulated 0.80 mm wall thicknees copper tube of Mandav / Totalline make between indoor to out door unit beyond 5 Rmt dist. Of 1.0 TR/1.50TR/2.00 TR Hiwall split unit with 2.5 Sqmm 3 Core copper flexible cable of Finolex/R R Kable/Havells/CEI make. The copper piping shall be insulated with 9 mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make (copper pipe concealed in inside wall)	35	RMT		
4	25/32 mm Dia UPVC drain pipe with insulation of Dutron/Supreme/Astral make - schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealed in inside wall)	60	RMT		
5	Providing, pre Fabricate and Fixing M.S stand for keeping outdoor unit of Cassette /Split A/C	16	Nos		
	<b>TOTAL FOR PART- II</b>				
	<b>TOTAL ( I + II ) A</b>				
	+ GST AS APPLICABLE				