

BILL OF QUANTITIES FOR RETILING AT STATE BANK OF INDIA ANKOLA BRANCH

No.	Description	Unit	Qty	Rate	Amount
1	REMOVAL OF EXISTING VITRIFIED TILES : Remove the existing vitrified tiles and the skirting along with the adhesive and also the existing mosaic skirting and carting away the Debris from the site	sft	5700		
2	Providing & laying flooring with Vitrified tiles of approved make, shade and colour of 600mm x 600mm size of minimum 10mm thickness laid over the existing mosaic flooring using tile adhesive (Laticrete-290 or equivalent) with spacer not less than 4.00 mm after removal of the existing vitrified tiles,scarifying the adhesive/ mortar if any and levelling the surface. Grooved trowels to be used for applicaton of adhesive maintaining apt water adhesive ratio to ensure proper bonding of the vitrified tile with the existing mosaic tile. The gap between tiles to be grouted and cured as per instructions of the manufacturer with joint filling compound of epoxy type (Laticrete or equivalent) of approved shade & colour including cost of jointing material and conveyance of all materials viz., vitrified tiles, white or coloured cement etc., to site, as directed, curing etc., complete for finished item of work. The rate should include cleaning the surface on completion of work. Basic rate of vitrified tiles at Rs. 538 per Sq.m (excluding GST). Transportation, loading & unloading etc., at site should be assumed to arrive at the tender rate. No extra claim towards the wastages shall be allowed. Quantity is including of 4" high skirting (in Sft).	Sft	5700		
TOTAL RETILING WORKS (Excluding GST).					-
GST EXTRA					
Note:					
1. The area may be inspected and the nature of work known before quoting					
					Signature of contractor