

BOQ FOR INTERIOR FURNITURE WORK AT					
SBI, ADMINISTRATIVE OFFICE JORHAT					
Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
<b>A. NEW WORK:</b>					
1	<b>Plain gypsum ceiling:</b> Providing and fixing suspended 12mm thick Gypsum board false ceiling with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design, pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank. Rate shall include dismantling of existing false ceiling if any. Make: Gyproc/ amrstrong or equivalent	sqm	190.00		
2	<b>Grid ceiling:</b> Providing and fixing suspended false ceiling with <b>600x600 mm size &amp; 15/16mm thick acoustical suspended ceiling system dune max micro look edge tiles with armstrong silhouette exposed grid.</b> The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank. Make: Amrstrong	sqm	130.00		
3	<b>Full Ht. Solid partitions with both side 0.8 mm thick Laminate finish:</b> Fabricating and fixing full ht. solid partition made of 9 mm ply of approved brand in both side and to be finished with 0.8 mm thick laminate of approved brand, colour and shade over 50mm X 50mm aluminium section framework at spacing not exceeding 600mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall include dismantling of existing partition and etching of glasses as per Banks requirements. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	sqm	66.00		
4	<b>Full Ht. semi-glazed partitions with both side 0.8 mm thick Laminate finish:</b> Fabricating and fixing full ht. semi glazed partition made of 9mm ply of approved brand in both side and to be finished with 0.8 mm thick laminate of approved brand, colour and shade over 50mm X 50mm aluminium section framework at spacing not exceeding 600mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900mm to 2100mm height shall have 6mm thick plain float glass fixed with 10mm thick teak wood moulding duly polished. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rates shall include dismantling of existing partitions and etching of glasses as required at site. Rate shall include dismantling of existing partition and etching of glasses as per Banks requirements. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	sqm	26.00		
5	<b>Low ht. semi-glazed partitions with both side 0.8 mm thick Laminate:</b> Providing and fixing low ht. semi glazed partitions made of 9 mm ply of approved brand in both side to be finished with 0.8 mm thick laminate of approved brand, colour, shade over 50mm X 50mm aluminium section framework of approved brand spacing not exceeding 600mm both ways. Top portion at 900mm to 1500mm height shall have 12 mm thick plain float glass fixed with 10mm thick teak wood moulding duly polished. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. All exposed edge shall be covered with teakwood lipping of required size with polishing complete in all respect. Rate shall include making provision for fixing of countertop 12 mm glass with on its edges with necessary fixing arrangement as directed. Rates shall include dismantling of existing partitions and etching of glasses as required at site. Rate shall include dismantling of existing partition and etching of glasses as per Banks requirements. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	sqm	65.00		
6	<b>Wall &amp; Column panelling with 12 mm thk ply with laminate finish:</b> Fabricating and fixing wall/column paneling, with 12 mm thick ply finished with not less than 0.8 mm thick laminate of approved shade & brand over 25 mm x 35 mm (thickness not less than 1.5 mm) aluminium section framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout & elevation policy. Rate shall include dismantling of existing paneling if any.  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	sqm	20.00		
7	<b>Semi Glazed Door (both side 0.8 mm thick laminate):</b> Providing and fixing Semi glazed doors shutter made up of 38 mm thick block board of approved brand and quality, finished both side with not less than 0.8 mm thick laminate on one side and 4 mm thick veneer on other side of approved brand, colour and shade. Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make Saintgobin/Modigurd) fixed with 10 mm thick teak wood bidding duly polished N C lacquer as per design and direction by bank. Door shall include Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall include etching of glass area as required by Bank.  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	Sq.m.	8.00		

8	<p><b>Low ht storage unit (Laminate finish):</b> Providing and fixing storage units of size 450 mm x 750 mm, made up of 19 mm thick block board of approved brand on top &amp; vertical support and finished with 0.8 mm thick laminate of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19mm thick plywood and finished in 1 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approved brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, locks, handles etc. of Godrej or equivalent.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	RM	18.00		
9	<p><b>Full ht storage unit (Laminate finish):</b> Providing and fixing storage units of size 2400 mm x 450 mm, made up of 19 mm thick block board of approved brand on top &amp; vertical support and finished with 0.8 mm thick laminate of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19 mm thick plywood and finished in 1 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approved brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, locks, handles etc. of Godrej or equivalent.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	RM	7.00		
10	<p><b>Officers Table:</b> Supplying and installing Officers &amp; Staff Tables of Overall size - 1680 mm X 1830 mm x 750 mm including cost of side credenza (1230 mm x 450 mm x 750 mm) made up of 19 mm thick block board of approved brand all around and finished with 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include (pedestal) three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide with CPU stand and foot rest as per design and direction by Bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approved brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish &amp; 8mm thick glass duly finished to be placed on top of table &amp; credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout &amp; elevation policy.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	Each	7.00		
11	<p>Providing &amp; fixing in place 100 mm. Vertical blinds with scotch guard of approved make, quality and colour shade &amp; pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform &amp; adequate.</p>	Sq.m.	65.00		
<b>B. REPAIRING OF EXISTING FURNITURE WORK:</b>					
<b>FALSE CEILING WORK</b>					
12	<p><b>Plain gypsum ceiling:</b> Repairing of existing false ceiling with putty and lustre paint and making necessary design, pattern &amp; cut outs for light fittings, cove light etc. complete as per design direction by bank. Rate shall include dismantling of existing false ceiling if any.</p>	sqm	70.00		
13	<p><b>Grid ceiling:</b> Providing and fixing suspended false ceiling with <b>600x600 mm size &amp; 15/16mm thick acoustical suspended ceiling system dune max micro look edge tiles on existing silhouette exposed grid.</b> The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank. Make: Amrstrong</p>	sqm	60.00		
14	<p><b>Repairing of Full Ht. Solid partitions:</b> Removing, repairing and refixing of existing full ht solid partition 4mm/6mm ply in both side and to be finished with 0.8 mm thick laminate of approved brand, colour over existing frameork. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall include removing and refixing of the unit as required at site Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	sqm	32.00		
15	<p><b>Repairing of Full Ht. semi-glazed partitions:</b> Removing, repairing and refixing of existing full ht solid partition 4mm/6mm ply in both side and to be finished with 0.8 mm thick laminate of approved brand, colour over existing frameork. Middle portion at 900mm to 2100mm height shall have existing plain float glass fixed with 10mm thick teak wood moulding duly polished. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall include etching of glasses as per Banks requirements. Rate shall include removing and refixing of the unit as required at site Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	sqm	37.00		

16	<p><b>Repairing of Low ht. semi-glazed partitions with both side Laminate:</b>  Removing, repairing and refixing of existing low ht. semi glazed partitions with 4mm/ 6 mm thick ply of approved brand in both side to be finished with 0.8 mm thick laminate of approved brand, colour, shade over existing framework. Top portion at 900mm to 1500mm height shall have existing plain float glass fixed with 10mm thick teak wood moulding duly polished. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. All exposed edge shall be covered with teakwood lipping of required size with polishing complete in all respect. Rate shall includes deismantling of existing partition and etching of glasses as per Banks requierments. Rate shall includes removing and refixing of the unit as requierd at site  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent.  Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	sqm	15.00		
17	<p><b>Repairing of existing Wall &amp; Column panelling with with laminate finish:</b>  Removing, repairing and refixing of existing wall/column paneling, with 4/6mm thick ply finshed with not less than 0.8 mm thick laminate of approved shade &amp; brand over existing framework. Panelling framework to be secured to wall surface / column surface Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout &amp; elevation policy. Rate shall includes dismantling of existing paneling if any. Rate shall includes removing and refixing of the unit as requierd at site  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent.  Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	sqm	54.00		
18	<p><b>Repairing of existng Semi Glazed Door (both side laminate):</b>  Removing, repairing and refixing of existing Semi glazed doors shutter with 4/6mm ply over existing block board, finshed both side with not less than 0.8 mm thick laminate of approved brand, colour and shade. Middile portion at 900 mm to 2100 mm height shall have existing glass. Door shall includes new Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass area as requierd by Bank. Rate shall includes removing and refixing of the unit as requierd at site  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent.  Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	Sq.m.	20.00		
19	<p><b>Repairing of Low ht storage unit (Laminate finish):</b>  Removing, repairing and refixing of existing storage units of size 450 mm x 750 mm, with 4 mm thick ply on top, side and front and 6 mm ply on back and finished with with 0.8 mm thick laminate of approved brand on top, side and front. The storage units shall have existing intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of requierd size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, ,locks , handles etc. of Godrej or equivalent. Rate shall includes removing and refixing of the unit as requierd at site.  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent.  Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	RM	35.00		
20	<p><b>Repairing of existing Officers Table:</b>  Removing, repairing and refixing of existing Officers &amp; Staff Tables of Overall size - 1680 mm X 1830 mm x 750 mm including side credenza (1230 mm x 450 mm x 750 mm) with 4mm thick ply over existing ply of approved brand all around and finished with 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include repairinmg of existing one drawer and one openable shutter with 4mm ply and 0.8 mm thick laminate as requierd on right hand side with CPU stand and foot rest as per design and direction by Bank. rate shall include replacement of of telescopic slider, a keyboard tray as requierd at site. The teak wood bidding on all exposed edges to be removed and refixed after repairing of the table and polished to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, lock, handles etc. of Godrej or approved make as requierd at site. Design and detail of the table shall be as per direction of EIC. Necessary cut-out to accommodate wires, wire manager complete as per Bank's new uniform colour, layout &amp; elevation policy.  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent.  Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	Each	22.00		

21	<p><b>Repairing of existing Staff Table:</b>  Removing, repairing and refixing of existing Staff Tables of Overall size - 1450 mm X 600 mm with 4mm thick ply over existing ply of approved brand all around and finished with 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include repairinmg of existing one drawer and one openable shutter with 4mm ply and 0.8 mm thick laminate as required on right hand side with CPU stand and foot rest as per design and direction by Bank. rate shall include replacement of of telescopic slider, a keyboard tray as requierd at site. The teak wood bidding on all exposed edges to be removed and refixed after repairing of the table and polished to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, lock, handles etc. of Godrej or approved make as requierd at site. Design and detail of the table shall be as per direction of EIC. Necessary cut-out to accommodate wires, wire manager complete as per Bank's new uniform colour, layout &amp; elevation policy.  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent.  Laminate/vener Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	Each	6.00		
22	<p><b>Repairing of existing Reception table:</b> Removing, repairing and refixing of existing Staff Tables of Overall size - 1560 mm X 600 mm with 4mm thick ply over existing ply of approved brand all around and finished with 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include repairinmg of existing one drawer and one openable shutter with 4mm ply and 0.8 mm thick laminate as required on right hand side with CPU stand and foot rest as per design and direction by Bank. rate shall include replacement of of telescopic slider, a keyboard tray as requierd at site. The teak wood bidding on all exposed edges to be removed and refixed after repairing of the table and polished to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, lock, handles etc. of Godrej or approved make as requierd at site. Design and detail of the table shall be as per direction of EIC. Necessary cut-out to accommodate wires, wire manager complete as per Bank's new uniform colour, layout &amp; elevation policy.  Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent.  Laminate/vener Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	Each	1.00		
<b>Grand Total</b>					
<b>NOTE :The estimated cost is exclusive of statutory taxes (GST)on work contract</b>					