

Tender & Specifications for Proposed Interior & Furnishing, Works at Budhwaria road Branch Ujjain

Tender & Specifications for Proposed Interior & Furnishing, Works at Budhwaria road Branch Ujjain					
S.No.	Description of Item	Unit	Qty	Rate	Amount
	Interior Works :				
	Mode of Measurements : Area of exposed and finished surfaces will be measured.				
	False Ceilings :				
1	Gypsum Board False Ceiling :				
	Providing, making and fixing Gypsum Board False Ceiling :- 12.5 mm thick G.I. Perimeter Channels of size 0.55mm thick. G.I. intermediate channels of size 45mm from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick intermediate channel at 450-600 mm c/c Two coats of primer + two or more coats of plastic emulsion paint Note -Including all fittings,material, labour,cut outs required for light fixtures, Speakers, screws and joint paper/fibre tape etc. complete.	Sqm	285		
2	Cove in ceiling :				
	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.	Rmt	100		
3	Mineral Fibre Grid Tile Ceiling :				
	Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong, Gyproc or equivalent make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanised Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc or equivalent stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T - section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include all fittings and materials complete including proper installation and provisioning etc. The work is to be completed as per manufacturer's specification .	Sqm	290		
	Partitions :				
	Rate to be included of all kinds of planes/levels, profiles and cut outs, etc. required for light fixtures, trap doors and ACs, boards, provision for light fittings and diffusers have to be made at no extra cost supported with metallic section etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC Works for cabling, AC pipe works, etc.				
4	12.0 mm TOUGHENED GLASS partition with bottom 8" solid partition /Boxing with Framing.				
	Providing and fixing at site wooden boxing/partition over toughened glass Botton and Top portion to be made up of 18.0mm MR board to be hanged from the existing RCC ceiling with help of metallic anchor fasteners to be placed at 450mm c/c as per the space available, the exposed portion of the solid partition shall have approved shade of textured finished 1.0mm thick laminate of approved shade to be fixed in combination of two colors, the solid boxing is to be fixed such that to align the same with the fixed toughened glass below, the cost shall include all materials, labour, ne cessary staging work contingencies etc complete.	Sqm	24		
5	Full Height Partly Glazed/ Solid Wooden Partitions :				
	Providing and fixing full height partly wooden, partly glazed/ Solid partitions- specifications (Measurement shall be taken up to finished partition level & not of frame work and sal wood member shall go up to slab/beam soffit) Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways 8 mm thk. MR plywood Termite & Borer proof from both the sides 1.0mm thick approved shades of laminate 5 mm thick float glass (for Partly Glazed Partitions) Etching as per approved design Note -Including all fittings,material, screw, labour etc. Complete.	Sqm	195		

Tender & Specifications for Proposed Interior & Furnishing, Works at Budhwaria road Branch Ujjain

S.No.	Description of Item	Unit	Qty	Rate	Amount
6	Low Height partitions With / Without Glass :				
	Providing and fixing Half Height (approx-1200 mm ht.) partitions. Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways(Horizontal/Vertical) 8 mm thk. MR plywood Termite & Borer Proof from both the sides 1.0mm thick approved shades of laminate, 12.00 mm thick float glass Etching as per approved design wicket gate wherever required with Godrej Night latch Note -Including all fittings,material, SS hinges, SS tower bolts screw, labour etc. Complete. (Making provision for items like softboards, white boards,etc. as & where required.	Sqm	75		
	Panelling Works (Walls , Columns, etc):				
	Rate to be included of all kinds of levels/planes, profiles and cut outs required for elevation and fixing of light fixtures, trap doors and ACs, provision for light fittings, boards and diffusers have to be made at no extra cost supported metallic sections, etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC contractor for cabling, AC pipe works, etc.				
7	Wall/Column Panelling				
	Providing, making and fixing single skin paneling (Using 8 mm thick MR plywood), plain and/or curved in profile, on walls, front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises, upto 3 mt height and boxing of 0.10 – 0.45 mt. ht., as required, made out of 50 x 25 x 1.0 mm thk weighing 0.467 kg/rmt aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 6 mm thick MR plywood shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling edges / is to be provided with laminate or teak wood decorative beeding of 35mm x 20 mm finished with polish/painting as directed.	Sqm	90		
8	Cabinet for Electric Panel :				
	Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thk MR grade plywood. All visible surfaces shall be laminated with 1 mm thick Laminate on external surfaces of approved made and shades & painting the internal surfaces with 2 or more coats of synthetic enamel paint, including providing teakwood lipping of size 20 x 6 mm on edges. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet).	Sqm	3		
	Furnishing Works :				
	Providing multidrawer Godrej or Ebco single lock and approved brass handle for each drawer. Providing circular holes in table top for cables with PVC cable managers of 65 mm dia and cap. On the left side platform at bottom for CPU.The bottom compartment made up of 18mm thick. MR plywood. The exposed edges of the plywood to be provided with TW lipping of size 20x6 mm duly polished. One M S powder coated keyboard tray with mouse tray as manufactured by ebco (KBTM 45) or EGL (KBT-M-001) including sliding channel as per manufacturers specification to be provided below the working platform.				
	Tables :-				
	Providing and supplying table detailed below : 1.-18 mm thick MR Plywood 2.- 1 mm thick laminate on external surfaces and 0.8 mm thick lamination on internal surfaces of approved made 3.- TW half round beading of sect 20 x 12 mm duly polished 4.- Drawer unit of width 350mm (clear internal), consisting of set of 3 nos. of drawer. 5.-Drawer made of 18 mm thk. MR Ply wood for the front and rear 12 mm MR Plywood for sides and 6mm thk MR ply for the bottom sliding & teak wood beading of sect. 20 x 6 mm 6- EBCO Sliding Telescopic Rail +M S powder coated keyboard tray with mouse tray. Note all fittings, fixtures, locking arrangement, handles, etc. Complete.				

Tender & Specifications for Proposed Interior & Furnishing, Works at Budhwaria road Branch Ujjain

S.No.	Description of Item	Unit	Qty	Rate	Amount
9	CM & cabin Table : same as above but providing and supplying Executives Branch Manager of size -1.80 m x 0.90 m x 0.75 m ht.	Nos.	2		
10	Officer / Relationship Manager/ Auditor Tables : same as item above but providing and supplying Officer / Relationship Manager/ Auditor Tables of size 1.65 - 1.50 m x 0.75 m x 0.75 m ht.	Nos.	17		
11	GRAHAK MITRA same as item above but providing and supplying Grahak Mitra table- Size 1650mm x 800mm - 900mm x 750mm	No.	1		
12	Single Window Operator Counters : Single Window Operator Counters : same as above item & Following specifications and per dimensions specified:- a. Size- 1500mm - 1350mm x 900mm - 800mm x 750mm height. The top drawer to have cash separation arrangement. b. 18 mm thick MR Plywood c. 1 mm thick laminate d. The table edges shall be double thick, outside surface shall be curved using 3 layers of 6mm flexible plywood e. Finished with 1 mm thick Plain or Textured Laminate Hidden areas like inside of drawers, cabinets, finished with 0.8 mm white laminate.including all fitting labour, material etc complete.	Rmt	11		
13	CASH COUNTING COUNTER Cash Counting Counter : same as above item & Following specifications and per dimensions specified:- a. Size- 900mm x 750mm x 750mm height. The one top drawer to have cash separation arrangement. b. 18 mm thick MR Plywood c. 1 mm thick laminate d. The table edges shall be double thick e side support every 3 ft, e. Finished with 1 mm thick Plain or Textured Laminate Hidden areas like inside of drawers, cabinets, finished with 0.8 mm white laminate.including all fitting labour, material etc complete.	Rmt	7.2		
14	Wall Mounted Writing desk : Providing and fixing half round / rectangular customer voucher holders writing counter of width 900 mm and maximum depth 450 mm fixed to be wall or partition at a height of 1050mm made of 18 mm thk. MR plywood and 12 mm thick glass top, and sides and edges shall be finished with 1 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed . The cost shall be completed with lippings, mouldings, fittings,and accessories etc as per specification. as per the drawing and instruction given by the Bank Engineer.	Nos.	1		
15	Storages / Credenza : Officer Storage/Side Credenza/Back Credenza : Providing, making and placing in position Side Credenza storage:- Size 375mm depth, height of 750 to 900 mm 18 mm MR grade plywood construction with 6mm thk. MR grade plywood backing complete. 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. 4- All drawers shall be fitted with telescopic channels and locking arrangement laminated with 1 mm thick plain external surfaces and 0.8 mm thick white lamination on internal surfaces Note- SS Hinge, SS handles, magnetic catchers Godrej or ebco lock & brass handles all approved make etc.	Sqm	55		
16	NOTICE BOARD : Providing & fixing at site notice board of size 3' x 2' to be made up of kail/pine wood frame of size 2" x1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the design & drawing etc complete.	Nos.	2		
17	Drop & Complaint Box : Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.	Nos.	2		

Tender & Specifications for Proposed Interior & Furnishing, Works at Budhwaria road Branch Ujjain

S.No.	Description of Item	Unit	Qty	Rate	Amount
18	Temprrary shifting & arrangment of counter Works :				
	Shifted & arrangement of counter temporary arrangement work same in a suitable places as per the instruction of the Branch including cleaning, shifting charges within labour etc complete in the Branch premises etc. complete.	Job	1		
19	BUY BACK ITEM				
	LESS FOR Buying back of existing counter tables, counters and other tables, including dismantling of Partitions, tables, side units, false ceiling, Alluminium /Glass/ wooden partition with transportation, and cleaning of existing premises etc complete and throwing away the waste materials, away from the existing site including transporting the same if required	Job	-1		
	TOTAL AMOUNT FOR INTERIOR WORKS				