

**CIVIL WORK AT DGM CABIN AND SECRETARIAT**

S.No	Description of Item	Unit	Qty.	Rate	Amount
1	Providing and Laying floor Vitrified glaze tiles of size 1200 mm X 600 mm (1st quality) of approved make over a cement mortar (Green Pro certified make approved by bank or CPC team as exception/ Refer make and model sheet,cement section) bedding (1:4) as per the pattern given including filling joint with colour cement in matching shade.	sqft	1100		
2	Providing and Laying of 300 mm x 300mm Ceramic floor anti-skid tiles (1st quality) of approved make over a 75 mm thk cement mortar (Green Pro certified make approved by bank or CPC team as exception/ Refer make and model sheet,cement section) bedding (1:4) as per the design including colour cement in joint to matching shade. The joints shall be kept as thin as possible should not exceeding 1 mm.	sqft	80		
3	<b>Providing and fixing in position first quality white Hindware make European WC</b> strictly upon approval with P trap, High Quality brackets as required and as integral part removing the existing pan (broken) and/or making connections of W.C. with other accessories such as flush valve inlet, outlet, anti syphonic pipe etc. (if required) complete including making chases and holes in floors and walls and repairing the same with cement mortar (1:3) plastering, tiling etc. to the architects satisfaction	Nos	1		
4	WASH BASIN : Providing and fixing white vitrous wash basin with pedastal of Hindware / Parryware make with CI brackets, 15 mm heavy pilar cock, 32mm cp brass coupling, waste pipe etc. The rate should include all fittings jointing material, labour and making connection with the existing line complete.	Nos	1		

5	Providing & laying glazed ceramic wall tiles for dado in pantry area and on walls in toilets as per specifications of size 300mm X 600mm or 300mm x 450mm of make Simpolo, Kajaria, Nitco, Bell, Johnson, Somany etc, or equivalent in first quality of design, colour and make as per approval laid and border in special/dark colours as per approval laid over fresh or existing cement plaster including surface preparation if required to the architect's satisfaction, joints to be filled and finished neat with cement grout as per specifications including cutting at traps, mitring of joints if required cleaning applying acid wash curing etc. complete at all levels.	Sqft	275		
6	S.S. Soap Dish Wall Mounted single dish	Nos	1		
7	S.S. Clothes Hook with 5 hooks on one plate	Nos	1		
8	SS Finish Toilet Paper Holder as per approval	Nos	1		
9	SS Napkin Holder Oval or Hook shape as approved	Nos	1		
10	Providing and fixing 15mm dia Tap for wash basin of Jaguar make and hand jet of equivalent make	Nos	3		
11	<b>Providing and fixing Mirror of make modiguard/ saint gobain</b> etc or equivalent of height 1220 mm complete with flat polished edges, fitted on site on 12 mm ply base, base having wooden lipping border and finished with laminate if instructed. The mirror shall be either pasted on the ply with silicon adhesive or fitted with stud-head screws with air gap in between (minimum 6 nos average per location) or both as per approval complete to the Engineer's satisfaction.	Sqft	8		
	<b>Dismantling / Demolishing the following and carting away the debris from the site and unloading at a approved location as per statutory rules and regulations. Dismantling of existing brickwork, Dismantling of existing dado tiles without plaster, Dismantling of existing dado tiles without plaster</b>	sqft	100		
5	<b>Plastering:</b> Providing & laying <b>12-15 mm thick Plastering of walls</b> and ceiling with cement mortar 1:4, curing, ladder use, cleaning, etc. complete.	200	Sqf		

1	<p><b>Providing &amp; constructing Zade Black Granite platform for pantry and wash basin counters</b>  complete as per specifications with 18-24 mm kota stone stand and kota stone or MS angle/T section supports as required and as instructed, including base stone in kota stone and fixing of 15-18 mm thick mirror polished, machine cut jet black granite with simple full round edge moulding and facia for pantry counter and double thick edges with full round moulded edges and of required size. The granite full round moulding shall be fixed with araldite adhesive to the counter top. The cost shall be inclusive of cutting for sink, basin, taps etc. as and when required.</p>	25.00	sqf		
30	<p><b>Providing and laying Half Brick thick Brickwork</b> in CM 1:4 including R.C.C. Band 100mm thick @ every 1 metre layer including curing etc complete (Steel reinforcement paid separately)Providing and laying Half Brick thick Brickwork in CM 1:4 including R.C.C. Band 100mm thick @ every 1 metre layer including curing etc complete (Steel reinforcement paid separately)Providing and laying Half Brick thick Brickwork in CM 1:4 including R.C.C. Band 100mm thick @ every 1 metre layer including curing etc complete (Steel reinforcement paid separately)Providing and laying Half Brick thick Brickwork in CM 1:4 including R.C.C. Band 100mm thick @ every 1 metre layer including curing etc complete (Steel reinforcement paid separately)Providing and laying Half Brick thick Brickwork in CM 1:4 including R.C.C. Band 100mm thick @ every 1 metre layer including curing etc complete (Steel reinforcement paid separately)Providing and laying Half Brick thick Brickwork in CM 1:4 including R.C.C. Band 100mm thick @ every 1 metre layer including curing etc complete (Steel reinforcement paid separately)</p>	sqft	100		
12	<p>Providing and fixing 35mm thick flush door openable /sliding with 1mm thick laminate on bath side cost shall be inclusive all accessories like ss hinges, mortise handle/lock, latches, stopper, tower bolt etc. complete</p>	Sqft	50		
13	<p>Finishing walls with Plastic emalsion paint of Asian/ Nerolac/ Berger/ ICI to give an even shade three or more coats including putty and finishing the wall surface smooth complete work</p>	1000	sqf		

14	Preparing earlier treated surface by scraping with sand paper, cleaning, repairing cracks/knots if any with putty and applying two coats of synthetic enamel paint to doors/windows grills etc. complete. (Asian paint Apcolite, Berger paint - Luxol, Goolas, Nerolac paint – Nerolac	200	sqf		
15	Total Excluding GST				