

PRICE BID FOR ROOF TRUSS WORKS AT SBI KOTTAYAM TOWN BRANCH

SI No.	Description	Quantity	Unit	Rate	Amount
1	Dismantling the existing roof sheets (asbestose sheets) , purlin, lattice, beams, posts and necessary concrete / brick work demolishing etc. and removing the debris away from site. Rates include cost of material, labour, transportation charge , loading & unloading charges etc. complete.	704	SqM		
2	<p>Braced Truss Work : Providing, fabrication & fixing at site with coloured Aluminium corrugated sheets 0.46 mm thick (Jindal / Everlast) using necessary bolts (minimum 4 bolts to each sheet) including cost of all fixtures such as bitumin rubber washer, covering the holes with water proofing compound; Details of truss are as given below and as per drawing attached. All sections should be covered with epoxy primer and 2 coats enamel paint. The rate includes, cost of material, labour, transportation charge, loading & unloading charges etc. complete. The details of sections are given below.</p> <p>Post - 4" Square Tube Runner :- 1.5" X 1.5" Square Tube Bracing Frame work A Truss - 4" X 2" Squate Tube Slope Truss, 1.5"X 1.5" Square Bracing frame work Purlin - 1" X 1" Square Tube Sheet - Aluminium Oralium Strong 0.46 Pathi - Uroguard 6" Pathi, Pathi Clamp Painting - 2 coats epoxy , Black Measurements - Post gap - 3 meter A Truss gap - 1.5 meter Slope truss gap - 1.5 meter Purlin gap - 80cm Pathi clamp gap - 90cm</p>	775	SqM		

PRICE BID FOR ROOF TRUSS WORKS AT SBI KOTTAYAM TOWN BRANCH

SI No.	Description	Quantity	Unit	Rate	Amount
3	Providing and filling concrete 1:1.5:3 (1 cement, 1.5 sand, 3-20mm broken stone) including cost of all form work and watering , curing etc. complete for erretting GI pipe sections. The rate includes, cost of material, labour, transportation charge, loading & unloading charges etc. complete	5	CuM		
4	Providing and fixing 8"dia PVC semi-circular rain water pipe (gutter / pathy) with necessary pathy clamp to the existing roof below the sheet with necessary fixing arrangement etc. The rate includes, cost of material, labour, transportation charge, loading & unloading charges etc. complete	65	M		
5	Providing and fixing 150 mm PVC down water pipes with necessary fixing arrangements etc. The rate includes, cost of material, labour, transportation charge, loading & unloading charges etc. complete	45	M		
6	Providing and fixing Base plate for post with 200 x 200 x 5 mm thick metal plates with necessary anchor bolts	25	No.		
7	Good quality brick masonry work of desired size, in cement mortar 1:4 (1 cement :4 coarse sand)	10	CuM		
8	Plastering with CM 1:4, 12mm thick (1 cement & 4 sand) 12mm thick one coat floated hard and traveled smooth to walls including all staging work watering, curing etc complete.	200	SqM		

TOTAL

GST at applicable rates will be extra