

<b>PRICE BID FOR INTERIOR AND FURNISHING WORKS OF CONFERENCE ROOM AT RBO REWA</b>						
S No	Item Description	UoM	Quantity	Rate	Amount	
1	Providing & fixing Gypsum Board False ceiling with Saint Gobain "ULTRA" Main ceiling sections at 1200 c/c & Cross members at 450 c/c. The grid work to be suspended from ceiling with Hangers at every 1200 c/c both directions. The Frame work to be as per manufacturer's specifications. False ceiling is finished with 12.5 mm thk. Active Air for (Saint gobain make) to be screwd to the frame. The board is finished with fillign the tapered edges of the board with jointing compound and finisheing with PAPER tape of INDIA GYPSUM. The ceiling is finished with a top coat as per approved manufacturer. The item includes all neccessary cut outs for electrical / air conditioning grills and necessary frame work for them. Item includes Cove and curve designs. (Only Plan area is considered for area calculations)	SqM	48			
2	Providing and fixing false ceiling with mineral fibre acoustic ceiling tiles of Armstrong with MICROLOOK edges and having noise reduction properties laid on exposed grid system with 15mm wide type T-Section flanges colour white, main runners are spaced at 1200 mm centres securely fixed to the structure soffit with approved hangers at 1200 mm maximum centres. flush fitting 1200 mm crossed tees to be interlocked between main runners at 600 mm centres to form 1200 x 600 modules, 1200 mm cross tees shall be crimped.600 x 600 module to be formed by fixing 600 mm long flush fitting cross tees centrally between the 1200 cross tees. ceiling tiles of OPTRA in size 600 x 600 x 15 mm to be placed in the grid. Rate to include making necessary cut-outs or openings for light fixtures etc, complete.	SqM	62			
3	Providing and fixing Wooden False ceiling with 12mm Comm. ply finished with 4mm Veneer (base price of veneer ply Rs.150/ s.ft without tax) finish fixed over frame work of 25mmx50mm Marandi wood as per design and hanged from RCC ceiling with proper MS Angle hangers. The ceiling to be finished in Malamine polish complete.	SqM	6			

Sheet1

4	<p>Providing and fixing wall paneling for all heights with 50x25mm Kail wood frame at 2'-0" c/c in both directions, finished with 8-9 mm thk. Comm. ply &amp; 1.0mm laminate. Paneling to have 50x35mm Teak wood Moulding on top edge where panelling is 750 or 1220mm high. Panelling to have 100x12 Teak wood band at skirting including a moulding as detailed. All teak wood surfaces to be finished in Malamine polish Complete to the satisfaction of the Architect / Bank's Engg.</p>	SqM	120		
5	<p>Providing and fixing 6 mm Thick Plain MDF sheet in required design/pattern/ shape/size, etc. for application of texture paint/finishes. MDF shall be fitted over plywood structures, single skin panelling or double skin ply partition and cost shall be calculated for all these application. It shall be provided &amp; fixed in major areas, bands and /or geometrical patterns and edges flat/bevelled/ rounded off as per requirements upon approval from the Bank's engineer. MDF shall be of reputed makes like Century/ Greenply etc. and cost shall include all recommended adhesives, nailing, screwing, mitring, edge finishing etc. complete, as and in the manner required for proper and seamless fitting.</p>	SqM	15		
6	<p>Providing and fixing panelling with frame same as above, but finished with 6mm Comm. Ply and with 8/12 mm thk Euro coustic (Decorative Charcoal board base price approx. 350-550/ S.Ft without tax) panelling on wall fixed with headless steel screws upto all heights, Complete to the satisfaction of the Architect / Bank's Engg.</p>	SqM	23		
7	<p>Providing and fixing ISI marked 35mm BWR. flush door shutters, core of block board construction with frame of 1st class hard wood and well matched teak to be finished with 1 MM laminate from both sides complete, including ISI marked Stainless Steel butt hinges with necessary screws and Door Toilet Lock and tower bolt complete.</p>	SqM	9		
8	<p>Providing and fixing door closers (OZONE, Haffle, EBCO, Hettich) brand and manufacture, complete as per the direction of Engineer-in-charge.</p>	SqM	4		

Sheet1

9	<p>Providing and erecting in position conference Room table (rectangular/ elliptical/ curved/ curvilinear) to be made out of 25 mm thick BWR Plywood top and frame with 18 MM white SATUARIO MARBLE on table top in center and sides with 1 MM laminate, edges to be finished with 75 x 50 mm Tapered Edge Teak wood moulding all around 75 x 100 MM as per design, Table modesty and sides with approved 1 mm thick laminate, top supported on 50 x 50 teak wood frame all around including bracings at a regular interval of minimum 900 mm centres and 6 mm ply at bottom, Table to be erected on a central core support of 18mm thick BWR ply modesty box, to be finished with approved 1 mm thick laminate inclusive of necessary cut outs, provisions for video/ teleconferencing, providing and fixing in position cable &amp; wire managers as pop-up managers / cable cubby in desired number, necessary hardware, cabling arrangements for vide / tele conferencing, openings/ cut outs for speakers etc. all complete as per the drawings, specifications and directions of Architect/EIC. Note: Payment for table top to be measured in area.</p>	SqM	25		
10	<p>Providing and placing in position Console storage in meeting room with 19 mm BWP board and 1 mm laminate as per main table, item to have storage units with 12mm brown glass for storage shutters and shelves with pivot fittings. Middle portion of console to have 12 mm bevelled edged toughened glass fixed with 150mm S.S spacers on console as per Design &amp; Details. (Only front elevation is considered for area calculations)</p>	SqM	2		
11	<p>Providing and placing in position planter box of size 450mm wide &amp; 450mm high made of 18mm thick BWR board. Inside finished with 1.0mm thick laminate and outside finished with 1 mm thick laminate. Exposed edges of board finished with 6mm thick steam bech wood lipping. All complete as per approval of Architect /Client.</p>	SqM	5		

Sheet1

12	<p>P/F Signage plates of Stainless steel sheet of thickness 18 SWG &amp; grade 304 with names engraved in Hindi &amp; English as per etc. etched in colour on it, in following sizes of approved drawing &amp; specifications all complete as per directions &amp; instructions of Engineer-in-charge. (The sample of name plate should be got approved by Bank in advance before placing of order of Signage plates)</p> <p>Rectangular - 200 x 100/ 250 x 100 various sizes</p>	SqInch	450		
13	<p>Full Height Partly Glazed Partly Wooden Double Skin Plywood Partitions :</p>	SqM	10		
	<p>Providing and fixing full height partly wooden, partly glazed double skin partition with following specifications (Measurement shall be taken up to finished partition level &amp; not of frame work and sal wood member shall go up to slab/beam soffit)</p>				
	<p>Providing and fixing full height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite treatment to all wooden members wherever used. The partition to be sandwiched with 8 mm thick exterior grade MR commercial plywood (Make: Century/Archid/ Kitply) from both the sides and finished with 1.0mm thick approved shades of laminated finish (Make of laminate: &amp; match the panelling pattern. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite chemicals. The cost shall include all labor, materials, strictly as per the given design &amp; drawing etc. in complete.</p>				

Sheet1

<p>The partition will be provided with 5 mm thick float glass fixed at 900 -1200 mm above the floor level with teak wood beading fixed on both sides of the glass finished with polishing as directed. The float glass to be etched as per approved design (film etching to be paid separately). The beading for fixing glass to be fixed on both sides of the partition in such</p>				
<p>a way that it would be projected from the partition. (Glass opening wherever applied shall neither be included in measurement nor costing and shall be considered as separate item)</p>				
<p>The top panel (above glass panel) and side panels shall be provided with 8.00 thick exterior grade MR commercial plywood (Make: Century/ Archid/ Kitply) double skin partition as per specification of a) &amp; b) upto ceiling/top support. Making provision for items like softboards, white boards, electrical points, switchboards, telephone/ electrical/ data cables, etc. as &amp; where required (but excluding the cost for items). All finishes shall be done as per details and as per instructions of Bank's engineer. The rate to include all materials, labour, transport, etc. complete.</p>				
<p>Providing 75mm - 150 mm high skirting having 8.00 mm thick exterior grade MR commercial plywood fixed on both sides of the partition finished with 1.00 mm thick lamination of approved make and shade( Make: Century/Greenlam/ Archid). All wooden structures are to be painted with anti-termite/borer paint as per manufacturer's specification.</p>				
<p>Amount (in Rs.) excluding GST</p>				