

**PRICE BID OF FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA - WEALTH HUB BRANCH
AT AMBAWADI, AHMEDABAD**

Note:- Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris ,cleaning cutting wastage etc. all taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills

SN	Description	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	LINEAR TABLE SIZE: 4'-0" X 2'-0" X 2'-6" HT.	14.40	RMT			
	Providing and fixing Linear Table having width of 2'-0" using 18 mm thick Commercial plywood for Top and verticle support at 4'-0" c/c, Providing storage cabinet Two drawer and One shutter Unit at Every 4'-0" c/c, Group lock, SS handle in counter as directed complete. 1.0 mm thick Laminate finish on table Top and front side of shutter. Providing Foot rest of 3" x 1.5" in C.P. Teak wood with lacquered polish. Ready made Foot rest CPU stand trally with castor and metalic cable Manager shall be provided in table top All internal surfaces shall have 0.80 mm thick balacing laminate as directed. [FOR DETAIL REFER DRG] (For Assit.)					
2	BACK SIDE STORAGE CABINATE					
	Supplying and providing storage cabinete with 1.0mm laminate on Top, Front Shutter & 35mm x 6mm thick Burma Teak beading on Edges with polish. Laminate to be provided only on visible surfaces.	4.70	SMT			
	Size : Depth 1'-4", 3'-0" ht. having openable shutter as directed. storage Cabinet shall be made from 18mm thick commercial ply wood for Top with 1mm laminate finish and 18mm thick ply wood for verticle, shelves, shutters and 6mm commercial plywood for backing with 1mm laminate on all exposed surface. with verticle (at 3'-0" c/c) shelves at 1'-3" c/c Openable shutters in 18mm thick commercial ply wood with all S.S hinges, towers bolts, powder coated handle, ball catches, S.S approved make (group lock) multi purpose lock complate. Edges to be finished with teak wood lipping etc. including all internal surface to be polished/painted etc. complate. Laminate to be provided only on over visible surface. Front surface area shall be measured for payment purpose.					
	FINISHING DETAILS IN NUTSHELL:					
	1) Table Top : Dark Laminate & Burma Teak beading on Edges with pilished					
	2) Front Aprron & Sides: Dark Laminate					
3	SHUTTER FOR UNDER PANTRY PLATFORM	1.40	SQMT			
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" T.W members for frame, 18mm Tk plywood with 1.0mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60mm thick balancing laminate on internal shutter surface					

PRICE BID OF FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA - WEALTH HUB BRANCH AT AMBAWADI, AHMEDABAD

4	LOW HEIGHT PARTITION NEAR SALES TABLE	9.50	SQMT			
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12mm thick MDF Board exterior grade of approved brand on both side of aluminium skeleton and fixing 1.0mm thick laminate of approved shed on both sides. Fixing 1.0mm laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12mm th free clear float glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface.					
5	SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR	39.00	SQMT			
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.5mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade on both sides, 1.0mm laminate of approved make shall be fixed on plywood, Providing 8 mm thick float glass as directed in the partition. Providing door shutter using 30mm thick flush shutter with both side laminate and fixing 6mm thick glass shall be provided in door shutter providing 5" Long 3 Nos stainless steel hinges/doorstop, door closer, shall be provided as directed. Godrej Mortice lock shall be provided in door shutter Steam beach Beading shall be provided for fixing glass. All visible members if not laminated shall have lacquer polished as directed. As per drawing and instruction of Architect/Bank Complete.					
6	FULLY GLAZED PARTITION	17.60	SQMT			
	FULLY GLAZED PARTITION With C & D bracket for cabin. 12 mm thick Toughened glass with the help of top patch & bottom patch fittings. fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides.					
7	ISOLATED FLUSH DOOR SHUTTER (Partly Glazed and Partly Laminate) WITH FRAME	7.90	SQMT			
	Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 31mm thick flush door with 6mm thick clear float glass vision panel secured with 12mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, 1mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Ded Lock, S.S Handles, 150mm long Door stoppers, doorstop of approved make etc. all exposed surface /edges not laminated be provided with lacquer polish. As per drawing and instruction of Architect/Bank Complete					

**PRICE BID OF FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA - WEALTH HUB BRANCH
AT AMBAWADI, AHMEDABAD**

8	ISOLATED FLUSH DOOR SHUTTER (Partly Glazed and Partly Laminate) WITH FRAME FOR UPS ROOM	2.00	SQMT			
	Providing and fixing aluminium frame of 65mm x 38mm x 1.5 mm thick and door shutter made out of 50x25x1.5mm thick framing at maximum 1'-6" C/C both way with 8mm thick Hilux Board on both side with painting. Providing 6mm thick clear float glass vision panel secured with 12mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, aluminium stoper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Ded Lock, S.S Handles, Door stoppers, doorstop of approved make etc. complete as per drawing & instructions					
9	FULLY GLAZED DOOR WITH PATCH FITTINGS FOR MAIN ENTRANCE DOOR	5.90	SQMT			
	Providing & Fixing fully glazed door. The Item includes fixing of 12mm thick Toughened glass with the help of top patch & bottom patch fittings. The door will have patch lock, pivot, floor spring & 400 mm long handles both sides, (Approved Make), fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.					
	The patch fittings (Approved make) shall be of aluminium with S.S. matt finish coating & signage shall be of kich make. The entire door, complete in all respect should be installed in positions as req.					
10	PANELING WITH ALUMINIUM FRAMING (FINISH:	12.50	SQMT			
	Providing and laying panelling on walls & pillars having 12mm thick MDF Board exterior grade and 1.0mm th laminate fixed on wall & pillars with Aluminium framing of 25mm x 25mm x 1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed. panelling as per design and instruction of Architect. .					
11	WALL PANELING (FINISH: LAMINATE)	3.80	SQMT			
	Providing and laying panelling on walls & pillars having 12mm thick MDF Board exterior grade and 1.0mm th laminate fixed on wall & pillars on wall and pillar etc complete as directed. panelling as per design and instruction of Architect. .					
12	BACK PAINTED GLASS	3.00	SQMT			
	Back painted glass (Lacquer Glass) paneling: Providing and fixing in position wooden paneling to column / walls finished with Back painted (Lacquer Glass) comprising as under:-					
	(i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed upto 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.					

PRICE BID OF FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA - WEALTH HUB BRANCH AT AMBAWADI, AHMEDABAD

	(ii) Panel Finishing:- Providing & fixing 12 mm thick approved make BWR plywood to Aluminum framework finished with 8 mm thick approved quality and make back painted Lacquer Glass panels of required size, rigidly fixed using 3M adhesive / double side self-adhesive tape complete as directed by the Engineer-in-charge.				
	(iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards etc., including providing necessary wooden/aluminum section members support at cutouts, providing scaffolding for execution of work at all heights, complete as per drawings and as directed by the Engineer-in-charge at site.				
13	ROLLER BLINDS	32.80	SQMT		
	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shed. (Basic Price of Rs 135=00 Per Sq.Ft)				
14	FROSTED GLASS FILM	27.20	SQMT		
	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surfaces as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification.				
15	GRID FALSE CEILING	153.60	SQMT		
	Providing and Fixing of Armstrong Mineral Fibre Acoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid.				
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose.				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications.				
16	GYPSUM BOARD FALSE CEILING	71.20	SQMT		
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	After completion of work to certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification				

**PRICE BID OF FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR STATE BANK OF INDIA - WEALTH HUB BRANCH
AT AMBAWADI, AHMEDABAD**

	Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft. (3) Only finished visible surface area shall be measured for payment.				
17	Removing and refixing of old tables with side unit (approx. 7 to 8 nos.), partitions (approx. 25 SMT), storage cabinates(approx. 11 SMT), Side racks Chairs, Sofas tendom Chairs, False ceiling Grid Tiles including Grids available at our existing premises at Ambawadi without any damage and Refixing the same on Ground floor of our old zonal office premises situtaed infront (approx.200 feet) of the existing SPPB Branch Ambawadi Including all charges like transpotation, lead - Lift etc.complete. Rate also includes removal, stacking of existing furniture/set up properly required necessary for making new set up as per new layout . No extra payment shall be made for theses works	1.00	JOB		
18	Removing, repairing and refixing of existing side unit and back side storage from ground floor to first floor same premises including lead - lift. item includes changing of laminate of approve shade with removing of existing laminate by heating. including polishing where ever required. including changing of group lock. and required minor repairs. Front elevation area will be consider for payment purpose.	11.00	SQMT		
19	Removing, reconditionin existing partition and providing and fixing new partly glazed bothside laminated wooden partition including door as per given layout. Item includes changing of 1mm thick laminate on bothsides of existing 1.22 mt height partition and woen door also. Item also includes erecting new partly glazed wooden partition above 1.22 mt height and up to existing false ceiling with 1.5mm thick aluminium section of required size for matching thickness of existing partition in a maximum grid of 600mm x 600mm, 6/8 mm thick plywood and 1.00 mm thick laminate on both sides and 8mm thick glass. Item also includes providing and fixing new and reconditioning of existing partly glazed wooden door with matching laminate on both sides, providing new lock and required necessary all accessories, matching beading patties, polishing, cleaning etc. complete. (Existing partition and new partition including door, the combined furnished visible actual area as per layout plan will be considered for payment) (Note: Contractor should visit the site and check maximum existing partition area to be utilised and the rest area will be provided for new partition as per given layout)	25.00	SQMT		
20	Removing of existing laminate and refixing of new laminate as per selection for tables, partitions, Storage cabinate	10.00	SQMT		
	TOTAL COST "A"		RS.		