

PRICE BID

BOQ FOR AC WORKS FOR SHRINAND NAGAR BRANCH, SBI, AHMEDABAD					
Sr.No	Description	Quantity	Unit	RATE	AMOUNT
[A]	AIR CONDITIONING WORK				
[I]	MACHINE PART				
[a]	AC EQUIPMENT WITH - INVERTER COMPRESSOR				
1	Supply & providing of 4 way Inverter Cassette Type AC ceiling mounted cassette unit with indoor and out door having eco friendly refrigerant. Including indoor unit outdoor unit. decorative grille and cordless remote Machine shall have copper condensor Unit , Make: Daikin/ Mitsubishi Heavy Industries/Toshiba. [Mini 5 Star rating as per BEE Guide Line 2022]				
1.a	Inverter 4-way Cassette of 3.00 TR.(3 Phase Compressor Only.)	2	NO		-
2	Supplying & providing of Hi-wall Inverter Split Type AC with high wall mounted indoor and out door unit. having eco friendly refrigerant. Including indoor unit outdoor unit. and cordless remote Machine shall have copper condensor Unit , Make: Carrier/ Hitachi/ Daikin/ Mitsubishi Heavy Industries/ Toshiba/ Trane/Blue star. [Mini 5 Star rating as per BEE Guide Line 2022]				
2a	Inverter Hi-wall Split AC of 1.50 TR	1	NO		-
	TOTAL FOR PART-I				-
[II]	LOW SIDE WORK				
1	Installation of IDU & ODU of 4.00 TR/3.00/2.00 TR ceiling mounted cassatte unit with first oil & gas charge & commissioning etc. Rate including ceiling mounted suspension Kit etc complete	2	NO		-
2	Installation charges for above 2.0TR/1.50TR/ 1.00 TR Split A/C including 5.0 Rmt copper tubing and electrical wiring connection etc. complete.	1	NO		-
3	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit of 4.00/3.00/2.00 TR ceiling mounted cassette unit with 2.5 Sqmm 4 Core copper flexible cable of Finolex / R R Kable/Havells/CEI make. The copper piping shall be insulated with 13mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armafex/ Superlon Make	25	RMT		-
4	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit beyong 5 Rmt dist. Of 1.0 TR/1.50TR/2.00 TR Hiwall split unit with 2.5 Sqmm 3 Core copper flexible cable of Finolex/R R Kable/Havells/CEI make. The copper piping shall be insulated with 9 mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armafex/ Superlon Make (50	RMT		-
5	Removing and Reinstallation charges for existing 1.5/2.00 TR High wall mounted split A/C at new location including connection servicing & gas filling complete as directed.[Entire new copper piping and drain shall be paid as per item No 1[a] & 2] Shifting Existing Premises including indoor and outdoor with MS stand etc complete as directed.	5	NO		-
6	25/32 mm Dia UPVC drain pipe with insulation of Dutron/Supreme/Astral make schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealed in inside wall)	50	RMT		-
7	Providing and Fixing M.S Powder coated stand for keeping outdoor unit of cassette and split A/C. (Redy made)	4	NO		-
8	Providing ,Fabricate and Fixing M.S stand Plateform for keeping outdoor unit of Cassette /Split A/C. with M.S cage for locking of outdoor unit of Cassette/Split A/C. including painting [Drawing should be prepared by the vendor and approved by the Architects]	100	KG		-



Sr.No.	Description	Quantity	Unit	RATE	AMOUNT
9	MISC. CIVIL WORK LIKE MAKING ZARI IN WALL, WALL OPENING TO PASS DUCTS & PIPES, CORE CUTTING, PLASTERING & RE-FINISHING OF THE SAME TO THE ORIGINAL FINISH AS PER THE SITE REQUIREMENTS.	1	JOB		-
	TOTAL FOR PART- II				-
	'TOTAL (I + II)				-
[III]	Buyback Rate				
	Removing, Dismantalling & Buyback of OLD 1.0/1.50 Tr SPLIT AC	2	NO		-
	NET AMOUNT (I + II-III)				-
	+ GST AS APPLICABLE				

