

SUMMARY SHEET**NAME OF WORK- INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO**

Sr No	Description Of Work	Total Cost
1	Partitions - 76mm Thick	
2	Panelling (25mm + 1.2mm)	
3	False Ceiling and Accessories	
4	Doors	
5	Work Station Tables	
6	Tables (in Sq.Mt.)	
7	Back Runner	
8	Ready Made Tables	
9	Back Wall Unit	
10	Phone Booth	
11	Chairs	
	Total for Interior Work	

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	<p>Preamble: A) The quoted rate should include cost of necessary scaffolding, staging, centring, shuttering etc. as required for execution of the job at any height and location including removal of same. The scaffolding should be erected and anchored into the concrete members with help of expandable bolts, which are to be cut as the scaffolding is removed, no wall is to be punctured, at no extra cost to the Bank. Also, all the holes created needs to filled properly before handing over the project. B) Contractor has to make arrangements at his own cost to tie a safety net around the work so that loose material does not cause damage to the property or any human being, if necessary. C) Contractor has to make arrangements at his own cost to cover entire existing surface/ materials with Hessian cloth curtains so that does not cause any damage to the existing structures/ materials and even take care of dust control and carefully removing them complete. D) Contractor has to make arrangements at his own cost to cover entire existing flooring to avoid any damage. In case of any damage caused, contractor is liable to replace the damaged floor at their cost. E) Necessary care to be taken to avoid any damage to the existing facade, fittings, toilets etc. Any damage caused needs to be replace at Contractor's cost.</p>				
	<p>F) Rate for full height partition to include the cost of framework above false ceiling as required to fix the same to the ceiling slab for which no extra payment shall be made and the rate quoted shall be inclusive of the same. Measurement of Partition & Panelling shall be limited upto the False Ceiling level. However the cost towards frameworks to be continued upto the main ceiling shall be deemed to have been considered in the quoted rates and no separate payment shall be made for the framework or supporting elements of partitions / panelling items, above the false ceiling level unless directed by the Architect / Site Engineer to extend the partition up till the ceiling. G) The rate shall be all inclusive of the necessary hardware, fittings, fixtures & including glass & finishing for the same. The fittings needs to be got finalised by the Architect / Site Engineer before procuring the same. The rate shall be also inclusive of pattas & bands, grooves at any level, any design in veneer, textures etc including the necessary framing/ openings for Electrical, Telephone & AC outlets. Further it is important to note that the Glasses wherever specified for the items of Partitions & Panelling if any shall have bevelled edges as per the direction & thickness as indicated by the Architect or Engineer in charge. H) The Brand should use as per Approved makes given and all Rate shall include scaffolding hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p>				
1	Partitions - 76mm Thick				
1.1	Full Height (Upto Ceiling) - Unfinished and 12mm Calcium Silicate (Drawing code PVC)				
	<p>Providing & fixing in position 76 mm thick +/- 2mm full height solid/opaque wooden partitions unfinished 9 mm MR Ply on one sides and finished with Calcium Silicate and Paint on other side comprising as under:- (i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) bothways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling. (ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood IS 303 on one side of frame work only.</p>				
	<p>(iii) Finishing:- Providing and fixing one side with Calcium Silicate 12mm finished in two-Three coats of Acrylic emulsion paint of approved make and shade including making grooves etc. as per Architectural drawing or as directed by the Engineer-in-charge using approve Quality adhesive complete.</p>				
	<p>(iv) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete. (v) Provide Rock wool density 48kg/Cum with 50 mm thickness between the ply and calcium silicate for sound insulation. (vi) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p>				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	<p>Approved make:-</p> <p>(a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) Plywood:- Greenply, Century, Samrat , Duro or equivalent approved by the Bank.</p> <p>(c) Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.</p>				
	<p>Mode of measurement:- Though the partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>As per drawing and instruction of Architect/Bank.</p>	14	Sq.Mt.		
1.2	Full Height (Upto Ceiling) - Veneer Laminate				
	Full height solid wooden partition with one side laminate and one side veneer (Drawing code PVL)				
	<p>Providing & fixing in position 76 mm thick +/- 2mm full height solid/opaque wooden partitions finished with 4mm Veneer on one side and 1.0 mm laminate on other side comprising as under:-</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) bothways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling.</p> <p>(ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood IS 303 on both sides of the framework.</p> <p>(iii) Finishing:- Providing 1.00 mm thick, approved quality and shade laminate on one side and 4mm thick approved quality and shade veneer on other side of partitions in approved design & pattern including making grooves etc. as per Architectural drawing or as directed by the Engineer-in-charge using approved quality adhesive complete.</p> <p>(iv) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p> <p>(v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site.</p> <p>(vi) Applying 2 or more coats of approved matching shade and finish, melamine polish to veneer side as well as all exposed edges of partitions including those in door openings, cutouts etc. complete.</p> <p>(vii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>(viii) Provide Rock wool density 48 kg/Cum and 50 mm thickness between the ply and calcium silicate for sound insulation.</p>				
	<p>Approved make:-</p> <p>(a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Bank.</p> <p>(c) Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank.</p> <p>(d) Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank.</p> <p>(e) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.</p>				
	<p>Mode of measurement:- Though partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>As per drawing and instruction of Architect/Bank.</p> <p>Base Rate - 1. Veneer Rs-1200 / Sq.Mt. 2. Laminate - 700/ Sq.Mt.</p>	11	Sq.Mt.		
1.3	Full height solid wooden partition with laminate on both sides (Drawing code PLL)				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	Providing & fixing in position 76 mm thick +/- 2mm full height solid/opaque wooden partitions finished with 1.0 mm laminate on both sides comprising as under:- (i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) bothways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling. (ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood IS 303 on both sides of the framework.				
	(iii) Finishing:- Providing and fixing 1.0 mm thick approved quality and shade laminate on both sides of partitions in approved design & pattern including making grooves etc. as per Architectural drawing or as directed by the Engineer-in-charge using approved quality adhesive complete.				
	(iv) Making suitable cutouts/openings/channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site. (v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site.				
	(vi) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete. (viii) Provide Rock wool density 48 kg/Cum and 50 mm thickness between the plywood for sound insulation.				
	Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (c) Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.				
	Mode of measurement:- Though aluminium frame shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. As per drawing and instruction of Architect/Bank. Base Rate- Laminate RS- 700 / Sq.Mt.	50	Sq.Mt.		
	1.4 Slim line glass partition of approved make: (Drawing code SLG)				
	Providing and fixing 12mm thick straight toughened glass full height partitions comprising as under: (i) Framing:- Made using 45 x 25 mm, approved make, Black powder coated aluminium sections of SLIM LINE series or equivalent approved by the Bank. at floor and false ceiling level as per manufacturers' specifications. (ii) Door Frames/Openings: Made using 105x25mm, approved make, powder coated aluminium WIDE LINE sections for Door Frame. The two vertical sections of the frame shall be extending upto false ceiling level and horizontal section shall be provided at door top level. The rate shall be inclusive of all fittings and accessories from FFL to the bottom of false ceiling height.				
	(iii) Glazing:- Providing 12mm thick toughened clear glass panels of approved make to the frame sections fixed properly as per manufacturers' specifications including sealing glass joints using approved silicon sealant on both side. (iv) Fixing flush stop of size 20mmx15mm for door frame visible joint, grooves of size 12 mm etc complete.				
	Rate shall be inclusive of supply, transport charges, handling, loading and unloading & installation of all necessary hardware's, scaffolding, wastage, providing necessary structural supports to the framework with walls/roof ceiling etc. complete all as per manufacturers specifications as directed. As per drawing and instruction of Architect/Bank. (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Slim line Glass - Saint Gobain, Asahi Float, Modi Guard.	58	Sq.Mt.		
	1.5 Full Height (Upto Ceiling) - Partly Solid Partly Glazed - One Side Veneer One side Laminate (Drawing code G/S-LV)				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	<p>Providing & fixing in position 76 mm thick +/- 2mm full height solid/opaque wooden partitions up to 3 feet height finished with 1.0 mm laminate on one side and 4 mm thick veneer on other side. above 3 feet up to false ceiling glazed partition with 8 mm thick toughened glass framed on solid partition of minimum 150 mm thickness and fixed with 10mmx10 mm T.W. beading with fully polished (Melamine).</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) bothways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling.</p> <p>(ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood IS 303 on both sides of the framework.</p> <p>(iii) Finishing:- Providing 1.00 mm thick, approved quality 1 mm laminate and shade laminate on one side and 4mm thick approved quality and shade veneer on other side of partitions in approved design & pattern including making grooves etc. as per Architectural drawing or as directed by the Engineer-in-charge using approve quality adhesive complete.</p> <p>(iv) Making suitable cutouts/openings/channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p> <p>(v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site.</p> <p>(vi) Applying 2 or more coats of approved matching shade and finish, melamine polish to veneer side and on teak wood as well as all exposed edges of partitions including those in door openings, cutouts etc. complete.</p> <p>(vii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>(viii) Provide Rock wool density 48 kg/Cum and 50 mm thickness between the plywood for sound insulation.</p>				
	<p>Approved make:-</p> <p>(a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank.</p> <p>(c)Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank.</p> <p>(d) Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank.</p> <p>(e) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.</p> <p>(f) Glass: Saint Gobain, Asahi Float, Modi Guard.</p>				
	<p>Mode of measurement:- Though aluminium frame shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt..</p> <p>As per drawing and instruction of Architect/Bank.</p> <p>Base Rate- 1. Veneer Rs 1200/Sq.Mt. 2.Laminate - Rs 700 / Sq.Mt.</p>	6	Sq.Mt.		
1.6	Full Height (Upto Ceiling) - Laminate Calcium Silicate (Drawing code PLS)				
	<p>Providing & fixing in position 76 mm thick +/- 2mm full height solid/opaque wooden partitions finished with 1.00 mm laminate on one sides and 12 mm Calcium Silicate on other side comprising as under:-</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) bothways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling.</p> <p>(ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood IS 303 on laminate side of the framework only.</p> <p>(iii) Finishing:- Providing and fixing 1mm thick approved quality and shade laminate on one sides of partitions and other side Calcium Silicate finished in two or three coat of Acrylic emulsion paint of approved design & pattern including making grooves etc. as per Architectural drawing or as directed by the Engineer-in-charge using approve Quality adhesive complete.</p>				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	(iv) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete. (v) Provide Rock wool density 48 kg/Cum and 50 mm thickness between the ply and calcium silicate for sound insulation.				
	Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (c) Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.				
	Mode of measurement:- Though the partition shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sq.Mt.. As per drawing and instruction of Architect/Bank. Base Rate - 1. Laminate - Rs 700 / Sq.Mt.	74	Sq.Mt.		
1.7	Partition unfinished (Above false ceiling and other places) (Drawing code UP)				
	Providing & fixing in position 76 mm thick +/- 2mm full height solid/opaque wooden partitions unfinished comprising as under:- (i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) bothways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling. (ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood IS 303 on both sides of the framework.				
	(iii) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site. (iv) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete. (v) Provide Rock wool between the ply and calcium silicate for sound insulation. As per drawing and instruction of Architect/Bank.	294	Sq.Mt.		
	Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (c) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.				
1.8	Half Height (1.2 Mtr Height) both side laminates (Drawing code HPL)				
	Providing & fixing in position 70 mm +/- 2mm thick Low height wooden partitions with laminate on both sides comprising as under:- (i) Total Height of the partitions shall be as per approved drawing. (ii) Framing : Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium sections placed bothways (horizontal and vertical) not exceeding 450 mm c/c rigidly fixed to floor, wall / columns etc. (iii) Plywood skin : Providing & fixing 9mm thick MR plywood IS 303 on both sides of the framework and around vertical posts extending upto total height of LHP.				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	(iv) Providing finished section size 70/75 x 8mm thick seasoned second class rounded Teak wood moulding to all exposed edges of partition including applying 2 or more coats of melamine polish / Duco paint including necessary preparatory work for surface preparation with putty, priming coat, sealer coat etc. complete as per sample approved by the Bank. (v) Making necessary cutouts for electrical conduits / cables & switchboards etc., including providing additional supports wherever required complete as per drawings and as directed by Engineer. (vi) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete. As per drawing and instruction of Architect/Bank. Base Rate of Laminate - 700/ Sam	132	Sq.Mt.		
	Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b)Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (c) Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank. (d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank. (e) Enamel Paint/polish: Asian/Nerolac/Berger or equivalent approved by the Bank. (f) Glass: Saint Gobain, Asahi Float, Modi Guard or equivalent.				
1.9	Sliding Wooden Partition (Drawing code SWP)				
	i)Providing & fixing in position sliding solid partition made up of 100 x 20 mm extruded aluminium box section sandwiched between 9 mm MR ply from both sides over it and full height solid Sliding wooden partitions finished with one side 1.0 mm laminate and on other side Acoustic Panel comprising as under:-				
	ii)40 x 25 mm teak wood bidding on edges with melamine polish and including necessary Top hung sliding mechanism as approved by Architect/Engineer Incharge. iii)The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminium section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site and all as per Architectural Drawing. Approved makes- Laminate:- Greenlam/Century/Merino/ Roval touch or equivalent approved by the Bank.	14	Sq.Mt.		
1.10	Skins				
1.10.1	lacquered glass (Drawing code S1)				
	Panel Finishing:- Providing & fixing 8 mm thick approved quality and make Lacquer Glass panels of required size, colour, rigidly fixed using 3M adhesive / double side self-adhesive tape complete as directed by the Engineer-in-charge. Glass: Saint Gobain, Asahi Float, Modi Guard. Base Rate - 1400 / Sqm	67	Sq.Mt.		
1.10.2	Acoustic Panelling (Drawing code S2)				
	Providing & Fixing in position, 10mm thick Acoustic panel of approved make and colour with Density 2000gm/Sqm and Acoustic performance 0.6 to 0.9 NRC.as per the instructions and designs of the Architect / Engineer on wall side, including cost of required for pasting and Gripper System , Cut-Outs, decorative mouldings / finishing-items / Melamine Polish of moulding & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. Base Rate- Rs 450 / Sqm Approved Makes- Armstrong or Equivalent as approved by Bank	141	Sq.Mt.		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
1.10.3	<p>Laminate Finish (Drawing code S3) Providing & Fixing in position, 1mm thick laminate of approved make and colour as per the instructions and designs of the Architect / Engineer on wall side, including cost of required for pasting, Cut-Outs, decorative mouldings / finishing-items / Melamine Polish of moulding & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. Base rate of laminate : Rs 700 per sqm Approved Make- Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank.</p>	75	Sq.Mt.		
1.10.4	<p>Wall Paper (Drawing code S4) Providing and fixing graphics on smooth surface with adhesive of as per manufactures standard specifications and instructions by architect. Surface to be finished with putty and oil primer to apply the wall paper. Wall paper is applied using water based glue (Water mixed with CNC powder and Fevicol), and should ensure absence of bubbles, scratches ..etc. .All inclusive with complete application and protective covering until handover cost to include surface preparation (similar to base preparation for a paint) to receive the wall paper. Complete as per architect instructions. Basic cost - 200 rupees/sft Approved Make- D.Decor or equivalent approved by the Bank.</p>	8	Sq.Mt.		
1.10.5	<p>Charcoal Finish (Drawing code S5) Providing & Fixing in position, 10 mm thick charcoal finish panel of approved make and color as per the instructions and designs of the Architect / Engineer on wall side, including cost of required for pasting, Cut-Outs, decorative mouldings / finishing-items / Melamine Polish of moulding & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. Base Rate - Rs- 720 / Sqm</p>	9	Sq.Mt.		
1.10.6	<p>Column Laminate Cove-(Drawing code S6) Making laminate Cove as per drawing and instructions of architect. The rate shall be inclusive of necessary ply backing , making cutouts for light fixtures,bulkheads,internal and External vertical fascia etc. complete. Cove section includes exposed L shaped / curved/slant work and circular configurations where ever required as per detail. The rate shall inclusive of providing and fixing 2 mm PVC edge banding at exposed edges. For measurement purpose only front surface is measured for payment, no thickness or moulding will be counted. As per drawing and instruction of Architect/Bank.</p>	110	Rmt		
			Total 1		
2	Panelling (25mm + 1.2mm)				
2.1	With Veneer Finish (Drawing code PnV)				
	<p>Providing and fixing in position wooden panelling to column / walls finished with 4 mm thick veneer comprising as under 9 mm thick MR Ply: (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb. (ii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminium section members support at cutouts, Grooves inlay Patti/ doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site. (iii) Applying 2 or more coats of melamine polish to exposed edges of panelling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete. As per drawing and instruction of Architect/Bank. (iv)Wood Skin - P& F 9 mm thick MR Plv IS 303 finished with 4 mm thick Veneer Skin</p>				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (c) Veneer- Green/Century/ Merino or equivalent approved by the Bank. (d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.				
	Base rate - Veneer 1200/ Sqm	36	Sq.Mt.		
2.2	With Laminate Finish (Drawing code PnL)				
	Laminated Columns/Wall Panelling L.C				
	Providing and fixing in position wooden panelling to column / walls finished with laminate comprising as under 9 mm thick MR Ply: (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb and finished with 9 mm ply. (ii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminium section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site. (iii)Wood Skin - P& F 9 mm thick MR Ply IS 303 finished with 4 mm thick Veneer Skin				
	Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear panelling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sq.Mt.. As per drawing and instruction of Architect/Bank. (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (c) Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank. Base Rate- 1.Laminate - Rs 700 / Sq.Mt.	344	Sq.Mt.		
2.3	Wall panelling with different finishes(Drawing code PnG)				
	Providing and fixing in position wooden panelling to column / walls finished with following finishes (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed upto 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb. (ii) Panel Finishing:- Providing & fixing 9 mm thick approved make MR plywood IS 303 to Aluminium framework				
	(iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards etc., including providing necessary wooden/aluminium section members support at cutouts, providing scaffolding for execution of work at all heights, complete as per drawings and as directed by the Engineer-in-charge at site.				
2.3.1	lacquered glass				
	Providing & fixing 8 mm thick approved quality and make Lacquer Glass panels of required size, rigidly fixed using 3M adhesive / double side self-adhesive tape complete as directed by the Engineer-in-charge. Approved makes- Glass: Saint Gobain, Asahi Float, Modi Guard. Base Rate - 1400 / Sqm	39	Sq.Mt.		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
2.3.2	<p>Fluted Veneer Finish Panelling (Drawing code NV) Providing & Fixing in position, 4 mm thick fluted Veneer with melamine polish of approved make and color as per the instructions and designs of the Architect / Engineer on wall side, including cost of required for pasting, Cut-Outs, decorative mouldings / finishing-items / Melamine Polish of moulding & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. Base rate of veneer : Rs 3000 per sqm Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank.</p>	6	Sq.Mt.		
2.3.3	<p>Fluted Laminate Finish Panelling(Drawing code PnFI) Providing & Fixing in position,1.25 mm fluted laminate of approved make and color as per the instructions and designs of the Architect / Engineer on wall side, including cost of required for pasting, Cut-Outs, decorative mouldings / finishing-items / Melamine Polish of moulding & Scaffolding, as per Architectural & Acoustical Design & Instructions & Complete in all aspects. Base rate of laminate : Rs 850 per sqm Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank.</p>	6	Sq.Mt.		
2.3.4	<p>Charcoal Finish wall Panel (Drawing code PnC) Providing & Fixing in position, Charcoal finish of 10 mm thick approved make and color as per the instructions and designs of the Architect / Engineer on wall side, including cost of required for pasting, Cut-Outs, decorative mouldings / finishing-items / Melamine Polish of moulding & Scaffolding, as per Architectural & Instructions & Complete in all aspects rate inclusive of adhesive. Base rate of : 2000/Sqm</p>	328	Sq.Mt.		
2.4	<p>Reception Dummy columns(Drawing code RC3) Providing and fixing in position wooden panelling to column / walls finished with 1.00mm laminate comprising as under:- (i) Framework:- Made out of 50 mm x 50 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb. (ii) Panel Finishing:- Providing & fixing 9 mm thick approved make MR plywood to Aluminium framework finished with 1mm laminate , using approved adhesive, in approved pattern & design, including providing grooves, decorative mouldings etc. as per Architectural drawings. (iii)Cutouts for SBI Logo as per Architectural Drawing. (iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminium section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site. Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (c) Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank. Base Rate- Laminate -Rs -700 /Sqm</p>	9	Sq.Mt.		
2.5	<p>Reception Back Panel (Drawing code RC 2) Providing & fixing a wall panel behind reception counter with 50x25x1.2 mm Aluminium framework at 600 mm centre to centre, covered with 9mm thick IS 303 MR grade plywood with finishing layer of 12 mm thick Artificial grass fixed in pattern approved by Architect. The patterns will be created using wooden battens and polished using melamine polish. Unit should be complete with standard hardware fittings, hinges, locks as per the drawing Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank.</p>	15	Sq.Mt.		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
2.6	<p>Reception Console (Drawing code RC1) Manufacturing, assembling, transporting & placing / fixing in position Admin counter table, inclusive of all fixtures, finishing, wire management, outlets for connectors, Table top finished by Corian and all side finished in 1.00mm thick laminate of Approved Shade, Grade and type as shown in drawings or as per specifications or equivalent approved by the Bank. or as directed by the Architect or Engineer on site. The length of table will be approx. 2400mm with a width of 600mm and height 750mm. The writing ledge will have an height of 1050mm from flooring and length 1200mm finished in 1mm laminate. As per drawing and instruction of Architect/Bank. Basic rate of laminate is Rs 700 per sqm Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank.</p>	5	Sq.Mt.		
			Total 2		
3	False Ceiling and Accessories				
3.1	<p>Plain Gypsum Ceiling (12mm Thick) (Drawing code FCG) GYPSUM CEILING: Providing & Fixing 12 mm thk Gypsum board false ceiling to G.I./AL ultra studs in perfect level. Necessary offsets and grooves to be provided at the junction of ceiling & walls/columns/partitions etc., Cut out for light fittings A/C grills etc. Rate to include providing & fixing of necessary G.I./wooden/MS frame supports for the above fixtures & additional suspenders & the ceiling in AC duct area as per architects instructions. G.I.frame to consist of proprietary supplied frames & as per manufacturers recommendations suspended from dash fasteners anchored to structural slab by means of G.I.angles. Gypsum board fixed with proprietary supplied fixing devices & finished. The joint between the sheets of plasterboard are to be covered with jointing paper tape and flushed with UB 888 (all purposes jointing compound) to provide a smooth durable and professional finish. Suspension points and clips shall be able to take a minimum safe load of 50 kgs. including making grooves at the junction of ceiling & walls/columns/partitions etc.</p>				
	<p>The rate shall inclusive of 2coats of Birla white putty, 1 coat of primer & 2 coats of royal emulsion. The putty shall be applied with blades and the surface to be kept rest for minimum of 24 hrs. The surface lups shall be racked out with putty blade and the second coat of putty shall be applied and to be left for minimum of 24 hrs. The surface shall be done with sand paper to get neat and plain surface. One coat of primer shall be applied to the final coat of putty and to be left to dry. After drying the engineer has to check for any undulation. If any undulations found the surface shall be sand papered, levelled with putty and to be left to dry & primer to be applied to the surface. The process has to be done until the wall surface is even and with out any undulations. The first coat of paint shall be applied and to be dried for minimum of 24 hrs. At the time of handing over the final coat of paint shall be laid. Care shall be taken by engineer that there will be no rectification works to be done after first coat and second coat of paint. Rate to be included with the cost of material, labour, transportation, leads, lifts, scaffolding, rectification works etc include all upto completion and handing over of the works upto the satisfaction of engineer in charge. Works has to be done as per specifications, drawings and as directed by engineer in charge.</p>				
	<p>Cutouts for light fittings, A/C grills etc. to be left wherever necessary. the ceiling profile shall be as per Architects instructions. All complete including return air slits etc. & A/C boxing wherever indicated. Note : Marking of Electrical , Fire Alarm & Air-conditioning & co-ordination with marking of fixtures to be considered. Gypsum ceiling to be installed as per IGL specifications. Rate to include additional channel supports at the junction of Grid & Gypsum Ceiling. Rate to include Acrylic sheets as per design. Note : Marking of Electrical , Fire Alarm & Air-conditioning & co-ordination with marking of fixtures to be considered.</p>				
	12 mm thick gypsum plain board with paint conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks)	1368	Sq.Mt.		
3.2	Grid Tile Ceiling (600mm x 600mm) - (Drawing code FCG)				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	P & F of modular grid type false ceilings at all heights of 600 x 600 x 15mm Armstrong mineral fiber ceiling tiles of type dune supreme ml edge rh – 99 % laid on armstrong silhouette 15mm black reveal grid systems or eq.the frame work comprise of main runner of size 15 x 42 x 3000 mm spaced at 600 mm centers securely fixed to the structural soffit by approved hangers at 1200 mm maximum centers. hangers (BUTTER FYLY CLIP) to be fixed by approved roof plug, level adjusters, screws etc. the last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees of size 15 x 42 x 600mm centrally between the main runners. Perimeter wall angle of size 19 x 19 x 3000mm secured to walls at 450mm maximum centers. finally dune supreme ml edge rh – 99 % 15 mm thick (nrc=0.50, light reflectance > 85 %, cac – 34 db, k value = 0.052 to 0.057 w / m k) micro look edge has to be laid on the 600 mm x 600 mm module. (the same ceiling shall be fixed by using full size tiles only & shall be fixed to the gypsum false ceiling) Tiles: mineral fibre acoustical tiles shall be of Armstrong Adria micro look edges with sanded backing & finished with a reinforced scratch resistance coating on the face side suitable for grids of nominal sizes 600mm x 600mm as per the specification below:	1170	Sq.Mt.		
	Type: Tiles having ml edge rh – 99 % tile thickness: 15 mm, humidity resistance: rh 99 %, fire performance: class 0/class1 (bs – 476), noise reduction co-efficient (nrc): 0.50 (average), sound attenuation: 34 db, light reflectance: > 85 %, thermal conductivity: 0.052 – 0.057 w / m k Suspension system: suspension system shall be silhouette 15 mm white reveal suspension system (hot dipped galvanized steel) section consisting of the following members: Main runner: main runner shall be t-shaped section with rotary stitch of size 15 x 42 x 3000 mm long, cross runners: size 15 x 42 x 600 mm long, wall angle of size 19 x 19 x 3000 mm long colour white The area of the ceiling where full tile size light fixtures are installed, will be NOT deducted from the total quantity executed. However the cost of tiles will be deducted from the bill amount. The work shall be executed under the supervision authorized applicator of . The contractor has to submit the certificate from the company for the use of company sections & boards along with the final bill				
3.3	Wall painting with acrylic emulsion paint over existing surface or Newly finish surface, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats like putty or punning of required thickness wherever required, to achieve even shade and colour (Asian Paints, Burger, Nerolac or equivalent.).	140	Sq.Mt.		
3.4	Supply & installation of Zebra roller blinds (150 GSM) Providing, supplying & fixing Zebra Blinds of approved make, shade etc as per the directions of the Bank at the predetermined locations. The fabric used should be dust, moisture resistant as approved from the Architect before supplying the items. Shade : Colours would be as approved by Architect Composition of Yarn : Glass Fibber (30% minimum) & Bulk dyed Polymer compound. Fire resistance : confirming to NFPA 701 (USA) / NF P92-503 Thickness of Fabric : minimum 0.5mm thk Durability : water proof, anti-microbial, corrosion resistant washable, flame retardant, fade resistant & stain guarded. Roller Tube of SS Thickness : minimum 0.5mm with minimum 25mm Bottom Rail Ball Chain SS coated on Brass as per manufacturer without connecting cap. Chain to be continuous & fixed while installing chain drive unit. Chain drive unit & idler end Manufactured of moulded plastic with steel support pin. It shall be driven by ball chain pulley. The shade shall be automatically locked in any position. Base Rate - 1300/Sq.Mt. Approved Makes- Vista / Wintree / D. decor or equivalent approved by the Bank.	545	Sq.Mt.		
3.5	Re-inforced Aluminium Framing(@ maximum 450 mm vertical and horizontal spacing) for receiving Bison board at Entrance Lobby. Vendor to ensure following the design details for curvature at the edges and making provision for indirect lighting by making of cove or pelmet as per drawing.	216	Rmt		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
3.6	Providing and fixing carpet tile on floor as per drawing and manufactures specifications & instructed by Architect or engineer in charge without undulation & bubbles with the help of Approved adhesive. Size of carpet tile should be 500mm X 500mm. Cost should include house keeping & cleaning for the carpet till the handover (Required material test certificate along with supporting document), material movement & shifting for all the floors. The finished flooring to be covered with the help of thick plastic & masking tape. Basic cost - Rs. 1700 / Sqm Approved Makes- Welspun / Armstrong / Interface or equivalent approved by the Bank.	250	Sq.Mt.		
			Total 3		
4	Doors				
4.1	Fully Glazed Door (Drawing code GD)				
	Providing and fixing in position frameless glass door shutter made using 12mm thick toughened glass fixed to floor and ceiling / Partition (glazed / solid / gypsum partitions) using heavy duty floor spring with pivot of approved make including necessary cutting of floor and making the surface good to its original position including all necessary Patch fittings of approved make and fixtures, Fittings like C-Shape Handle, locks/ floor spring etc. & hardware's. all fittings shall be approved by Architect / Engineer Incharge. Mode of Measurement: Door opening size shall be measured.	26	Sq.Mt.		
4.2	Providing & Fixing glass protective film of approved shade on partitions, doors, windows etc. for similar locations to provide safety and security etc. complete as per the direction of Engineer-In-Charge. Base Rate for film - Rs- 300 / Sqm Approved Makes- 3M Science or equivalent approved by the Bank.	60	Sq.Mt.		
4.3	Flush Door with viewing glass panel (Drawing code FD)				
	Flush Door with Laminate finish:- FD- Providing & fixing 35 mm Flush doors with finishes as per design. Door frame:- Providing and fixing door frames using teakwood members of size 100mm x 50mm and finished with melamine polish. Shutter:- Providing and fixing block board shutters of 35mm thick . Skin:- The shutters shall be finished with 1mm thick laminate of approved quality and make. The Doors to have all hardware such as 125mm SS hinges, 450 m long SS handles, SS tower bolts, Mortice Locks (Dorma/ Godrej). Exposed edges of shutter shall be provided with teakwood beading of 30mm width and finished with melamine polish. The item also includes SS rods 6mm x 6mm inserted in grooves and finished properly using putty and polish as per details complete to the satisfaction of Architects/ Bank's Engineer. All fitting shall be approved by the P.A / SBI before its installation. Size of Door : 1000 x2100mm including frames. Approved Makes- Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. Veneer- Green/ Jalaram/ Merino or equivalent approved by the Bank				
4.3.1	Finished with 1mm thick laminate finish on both sides	68	Sqm		
4.3.2	Finished with 4mm thick Veneer and bevel moulding patti with melamine polish on one side and laminate on other.	5	Sqm		
			Total 4		
5	Work Station Tables				
5.1	For 1 Unit				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	<p>Providing and fixing factory finished modular, curved shaped 120 degree(1 Desk system) desking system. Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The table top will be placed on MS powder coated under structure with legs total height 750 mm and fixed to partition using L clamps and allied hardware. 120 degree aluminium partition of 1200 mm (+/- 50 mm) height and maximum 50 mm Thickness connected with 1 way triangular post , finished with combination of soft board, lacquered glass and MR ply covered with Fabric of approved make and shade, above table top and MR ply with laminate below the table top. All the exposed edges of the partition to be finished with extruded aluminium trim. Frames: The frame verticals are fabricated in 1.2mm CRCA sheet. All CRCA sheets confirm to IS – 513.The horizontal members are fabricated with welded joints to the vertical which makes the frames sturdy and facilitates carriage of cables at different levels. All the frames are fitted with M10 levelling bolts to adjust to ground undulations. Can be adjusted +/- 20mm. Frames can be provided with anchoring arrangement if required. All the Frames are duly powder coated in charcoal black color or color of choice to a thickness of 50-60 microns confirming to ASTM – 117, ISO – 1520 and ISO – 1518 & ASTM – 2794. The powder coating will be done with NANO Ceramic coating to the extent possible.</p>	3	No		
	<p>The partition will be provided with adjustable leveller at the bottom. Cost to be inclusive of 2 Nos Pedestal for each desk (2 no's) LxHxD - 720x450x450 mm(front and side using 12 mm thick MR ply and back side and bottom using 8mm MR ply)-The Pedestal unit box with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. MS powder coated raceway to accommodate minimum 40 no's of CAT 6 cables to be considered for wiring. Partition to be considered using 25 mm thick MR ply finished with 1mm laminate and 2 mm PVC edge band for each end of approved make and shade as per drawing. Metal powder coated CPU trolley, telescopic keyboard tray to be considered for each desk (1 no's each) , and PVC wire manager of approved makes. Rest details and items to be followed as per drawings. (+/- 1 MM variation in thickness based on availability of raw material) Size of each seat/ table will be L x D - 1350x1350x600</p>				
	<p>Providing and Fixing 25 mm thick MR ply 1200 mm height finished with 1 mm thick laminate on both sides and all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The same shall be fixed to the table top of workstation using L clamps. The rate shall be inclusive of providing necessary cut outs , transportation, carting etc complete. The rest shall be as per drawings. Makes: Featherlite, Godrej, Geeken or equivalent</p>				
5.2	For 2 Units				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	<p>Providing and fixing factory finished modular, curved shaped 120 degree(2 Desk system) desking system. Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The table top will be placed on MS powder coated under structure with legs total height 750 mm and fixed to partition using L clamps and allied hardware. 120 degree aluminium partition of 1200 mm (+/- 50 mm) height and maximum 50 mm Thickness connected with 2 way triangular post , finished with combination of soft board, lacquered glass and MR ply covered with Fabric of approved make and shade, above table top and MR ply with laminate below the table top. All the exposed edges of the partition to be finished with extruded aluminium trim. Frames: The frame verticals are fabricated in 1.2mm CRCA sheet. All CRCA sheets confirm to IS – 513.The horizontal members are fabricated with welded joints to the vertical which makes the frames sturdy and facilitates carriage of cables at different levels. All the frames are fitted with M10 levelling bolts to adjust to ground undulations. Can be adjusted +/- 20mm. Frames can be provided with anchoring arrangement if required. All the Frames are duly powder coated in charcoal black color or color of choice to a thickness of 50-60 microns confirming to ASTM – 117, ISO – 1520 and ISO – 1518 & ASTM D - 2794. The powder coating will be done with NANO Ceramic coating to the extent possible.</p>	13	Nos		
	<p>The partition will be provided with adjustable leveller at the bottom. Cost to be inclusive of 2 Nos Pedestal for each desk (4 no's) LxHxD - 720x450x450 mm(front and side using 12 mm thick MR ply and back side and bottom using 8mm MR ply)-The Pedestal unit box with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. MS powder coated raceway to accommodate minimum 40 no's of CAT 6 cables to be considered for wiring. Partition to be considered using 25 mm thick MR ply finished with 1mm laminate and 2 mm PVC edge band for each end of approved make and shade as per drawing. Metal powder coated CPU trolley, telescopic keyboard tray to be considered for each desk (2 no's each) , and PVC wire manager of approved makes. Rest details and items to be followed as per drawings. (+/- 1 MM variation in thickness based on availability of raw material) Size of each seat/ table will be LxD - 1350x1350x600 Makes: Featherlife, Godrei, Geeken or equivalent</p>				
5.3	For 3 Units				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	<p>Providing and fixing factory finished modular, curved shaped 120 degree(3 Desk system) desking system. Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with Providing and fixing factory finished modular, curved shaped 120 degree(3 Desk system) desking system.</p> <p>Table Top - Made of 25 mm thick MR Ply finished with 1 mm thick laminate of approved make and shade, all exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The table top will be placed on MS powder coated under structure with legs total height 750 mm and fixed to partition using L clamps and allied hardware.</p> <p>120 degree aluminium partition of 1200 mm (+/- 50 mm) height and maximum 50 mm Thickness connected with triangular post , finished with combination of soft board, lacquered glass and MR ply covered with Fabric of approved make and shade, above table top and MR ply with laminate below the table top. All the exposed edges of the partition to be finished with extruded aluminium trim.</p> <p>Frames: The frame verticals are fabricated in 1.2mm CRCA sheet. All CRCA sheets confirm to IS – 513.The horizontal members are fabricated with welded joints to the vertical which makes the frames sturdy and facilitates carriage of cables at different levels. All the frames are fitted with M10 levelling bolts to adjust to ground undulations. Can be adjusted +/- 20mm. Frames can be provided with anchoring arrangement if required. All the Frames are duly powder coated in charcoal black color or color of choice to a thickness of 50-60 microns confirming to ASTM – 117, ISO – 1520 and ISO – 1518 & ASTM D - 2794. The powder coating will be done with NANO Ceramic coating to the extent possible.</p>	47	Nos		
	<p>The partition will be provided with adjustable leveller at the bottom.</p> <p>Cost to be inclusive of 2 Nos Pedestal for each desk (6 nos) LxHxD - 720x450x450 mm(front and side using 18 mm thick MR ply and back side and bottom using 8mm MR ply)-The Pedestal unit box with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame.</p> <p>MS powder coated raceway to accommodate minimum 40 no's of CAT 6 cables to be considered for wiring. Partition to be considered using 25 mm thick MR ply finished with 1mm laminate and 2 mm PVC edge band for each end of approved make and shade as per drawing.</p> <p>Metal powder coated CPU trolley, telescopic keyboard tray to be considered for each desk (3 no's each) , and PVC wire manager of approved makes</p>				
	<p>Rest details and items to be followed as per drawings. (+/- 1MM variation in thickness based on availability of raw material) Makes: Featherlite, Godrej, Geeken or equivalent</p>				
			TOTAL 5		
	6 Tables (in Sq.Mt.)				
	6.1 DGM Table				
	<p>DGM TABLE 2700 x 1050 x 750 mm with side table 1050x 450 x 750 mm Manufacturing, assembling, transporting & placing / fixing in position, with Veneer finish and lather finish side table with adjustable side top.</p> <p>Supplying and installation of Table as per the following description : Table Top: Providing and fixing 38 mm thick IS 303 MR grade plywood with 4mm thick Veneer with melamine polish with necessary intermediate support. Table top shall be supported by 50mm SS stud fasteners. Apron (Modesty Panel) made from 18mm thick IS 303 MR grade plywood finished with 4 mm thick veneer with melamine Finish & 10 mm brass strip in groove pattern and leatherette finish panels with foam backing as per drawing. Table sides, back & intermediate panels (at 50cm from each sides) made from 18 mm thick MR ply wood finished with 4 thick veneer with melamine finish for exposed surfaces (4 faces) and 0.8 mm thick laminate matching to veneer for inner surfaces shall be provided as per drawing.</p>	2	No		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	<p>Side storage unit: Side Storage cabinet: Box of 1050 x 450 x 750 mm shall be provided using 18 mm thick IS 303 MR grade plywood. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of 2 no's drawers and shutters to be made of 18 mm thick MR ply & bottom of drawers shall be of 8 mm thick IS 303 MR grade plywood. Ply to be finished with 4 mm thick veneer finished with melamine polish on top and all other exposed surfaces finished with melamine polish. The drawers and shutters to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer for each drawer. Drawer / Storage cabinet: One Box of 450 X 600 X 640 mm shall be provided using 18 mm thick IS 303 MR grade plywood on either side on which table top will be fixed. Each Drawer Fascia made out of 18 mm thick MR ply and all sides of drawers be made of 12 mm thick MR ply & bottom of drawers shall be of 8 mm thick IS 303 MR grade plywood. The drawer unit box and individual drawers to be fixed with 4mm thick Veneer finished with melamine polish on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick laminate matching to the veneer. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. Computer Key board (550 x 375 mm) of metal / PVC of approved make shall be provided. Foot rest of 38 x 76 MM T W members shall be provided. Metallic cable Manager shall be provided in table top. Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Bank. (c)Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (d) Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank. (e) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.</p>				
6.2	AGM Table				
	<p>AGM TABLE 2100 x 1050 x 750 including side unit of 900 x 450 x 750 Table Top: Providing and fixing 18 mm thick IS 303 MR grade plywood with 1mm thick laminate with necessary intermediate support. Table top shall be supported by 18 mm thick IS 303 MR grade plywood with plywood framing. Apron (Modesty Panel) made from 18mm thick IS 303 MR grade plywood finished with 1mm laminate. Table to have 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Side Storage cabinet: Box of 900 x 450 x 750 mm shall be provided using 18 mm thick IS 303 MR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of 2 no's drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick IS 303 MR grade plywood. The cabinet to have 1 no's adjustable shelf 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The Pedestal/ Drawer unit box 450 x 450 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p>	3	No		
	<p>Computer Keyboard drawer (550 x 375 mm) of metal / PVC of approved make shall be provided. Footrest (400 x 400) made of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All internal surface will have min. 0.80 mm thick balancing laminate. Table shall have stand of 18 mm MR ply finish with 1 mm thk.As per drawing and instruction of Architect/Bank. The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p>				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
	Approved make:- (a) Aluminium extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Bank. (c)Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.				
	Rest as per drawing and instruction of Architect/Bank, work to be Completed				
6.3	CM Table, SO Table				
	CM Table CM 1 A, CM1 B and SO Table 1800W X 750D X 750 Side Unit 900 x 450 x 750 Table Top: Providing and fixing 18 mm thick IS 303 MR grade plywood with 1mm thick laminate with necessary intermediate support. Table top shall be supported by 18 mm thick IS 303 MR grade plywood with plywood framing. Apron (Modesty Panel) made from 18mm thick IS 303 MR grade plywood finished with 1mm laminate. Table to have 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Side Storage cabinet: Box of 900 x 450 x 750 mm shall be provided using 18 mm thick IS 303 MR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of 2 no's drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick IS 303 MR grade plywood. The cabinet to have 1 no's adjustable shelf 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. The Pedestal/ Drawer unit box 450 x 450 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Computer Keyboard drawer (550 x 375 mm) of metal / PVC of approved make shall be provided. Footrest (400 x 400) made of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All internal surface will have min. 0.80 mm thick balancing laminate. Table shall have stand of 18 mm MR ply finish with 1 mm thk.As per drawing and instruction of Architect/Bank. The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.	27	Nos		
	Approved make:- Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Bank. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.				
6.4	MR 1A,MR2A,MR3A				
6.4.1	Meeting Room - MR1A 4500 x 17600x 750mm dimensions. Supplying and installation of Table as per the following description and as designed by the Architect: Table Top: Providing and fixing 19 mm thick IS 303 MR grade plywood. HDHMR patti's finished with DUCO. necessary intermediate support wherever required of aluminium sections. Table top shall be supported by 18 mm thick IS 303 MR grade plywood with plywood/aluminium framing. Base made from 18mm thick IS 303 MR grade plywood finished with 1 mm laminate . Table to have HDHMR square panels with bevelled edges as provided in the drawing. Cutouts for Cable Manager/Microphones/ AV sockets/ power sockets/power rails etc. shall be provided on the tabletop. All edges to be provided & fixed laminate/wooden moulding strip as per design detail. Cost to be considered for Brass inlay/Metal Strip as per design details. Cost to be inclusive of finishing by polishing of / duco finish over HDHMR. Table to have moulded skirting as per design details of the same. As per drawing and instruction of Architect/Bank.	1	Nos		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
6.4.2	Meeting Room - MR3A- 7300 x 1500x 750mm dimensions. Supplying and installation of Table as per the following description and as designed by the Architect: Table Top: Providing and fixing 19 mm thick IS 303 MR grade plywood. HDHMR patti's finished with DUCO. necessary intermediate support wherever required of aluminium sections. Table top shall be supported by 18 mm thick IS 303 MR grade ply wood with plywood/aluminium framing. Base made from 18mm thick IS 303 MR grade plywood finished with 1 mm laminate . Table to have HDHMR square panels with bevelled edges as provided in the drawing. Cutouts for Cable Manager/Microphones/ AV sockets/ power sockets/power rails etc. shall be provided on the tabletop. All edges to be provided & fixed laminate/wooden moulding strip as per design detail. Cost to be considered for Brass inlay/Metal Strip as per design details. Cost to be inclusive of finishing by polishing of / duco finish over HDHMR. Table to have moulded skirting as per design details of the same. As per drawing and instruction of Architect/Bank.	1	Nos		
6.4.3	Meeting Room - U table 2900 x 7270 x 750 less central well 6370 x1200 Supplying and installation of Table as per the following description and as designed by the Architect: Table Top: Providing and fixing 19 mm thick IS 303 MR grade plywood. HDHMR patti's finished with DUCO. necessary intermediate support wherever required of aluminium sections. Table top shall be supported by 18 mm thick IS 303 MR grade ply wood with plywood/aluminium framing. Base made from 18mm thick IS 303 MR grade plywood finished with 1 mm laminate . Table to have HDHMR square panels with bevelled edges as provided in the drawing. Cutouts for Cable Manager/Microphones/ AV sockets/ power sockets/power rails etc. shall be provided on the tabletop. All edges to be provided & fixed laminate/wooden moulding strip as per design detail. Cost to be considered for Brass inlay/Metal Strip as per design details. Cost to be inclusive of finishing by polishing of / duco finish over HDHMR. Table to have moulded skirting as per design details of the same. As per drawing and instruction of Architect/Bank.	1	Nos		
			TOTAL 6		
7	Back Runner				
7.1	DGM Back Runner				
7.1.1	DGM LOW HEIGHT STORAGE Low Height Cupboard with Veneer Finish: Providing & fixing Storage Cupboard of height 900 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm IS 303 MR grade ply. All shutters and shelves to be made with 18 mm thick MR ply. Top Facia of the unit will be made with 38 mm thick MR ply finished with 4mm thick veneer finished with melamine polish. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 4mm thick veneer with 4 mm grooves as per drawings to be finished with melamine polish. Vertical Grooves after every 50 mm on shutters as per drawings. All internal surfaces to be provided with 0.8 mm laminate. All edges of the cupboard should be finished with 4 mm thick veneer finished with melamine polish. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks (Godrej/ Hettich/Haffe), SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation As per drawing and instruction of Architect/Bank. Basic Rate of Veneer - Rs. 1200/ Sqm	6	Sq.Mt.		
	Approved make:- (a) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (b) Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank. (c) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.				
7.2	CM , SO and AGM Back Runner				

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
7.2.1	<p>AGM,CO and SO BACK STORAGE UNIT - LOW HEIGHT Low Height Cupboard with Veneer Finish: Providing & fixing Low Height Storage Cupboard of height 750 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm MR ply. All shutters to be made with 18 mm thick MR ply and finished with 1 mm thick laminate of approved shade. Shelves to be made with 18 mm thick MR ply and finished with 0.8 mm thick laminate of approved shade. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 1 mm thick laminate of approved shade. Vertical Grooves after every 50 mm. All internal surfaces to be provided with 0.8 mm laminate. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks, SS towerbolts etc. All shutters to to be made overlapping the frame. Only front elevation will be considered for area calculation As per drawing and instruction of Architect/Bank. Base rate laminate - Rs 700/ SOM Approved make:- (a) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (b)Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (c) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.</p>	65	Sq.Mt.		
7.2.2	<p>AGM FULL HEIGHT Full Height Cupboard with Laminate Finish: Providing & fixing Full Height Storage Cupboard of 2400mm height and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm IS 303 MR grade ply. All shutters to be made with 19 mm thk. block board and all shelves using 18mm MR ply All internal and external surfaces to be finished with 1mm laminate of approved shade and make. All edges of the cupboard should be edgebanded using PVC edgebanding tape of approved shade. Shutters to be provided with S.S. 200mm handles, magnetic catchers, self closing SS hinges, locks (Godrej/Hettich/Haffele), SS towerbolts etc. All shutters to to be made overlapping the frame Only front elevation will be considered for area calculation. Base Rate- Laminate - Rs. 700/ Ssm Approved make:- (a) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (b)Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. (c) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.</p>	14	Sq.Mt.		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
7.2.3	<p>DGM BACK DISPLAY UNIT - FULL HEIGHT 2 Full Height Cupboard with Veneer Finish: Providing & fixing Full Height Storage Cupboard of height 2700 mm and 450mm deep Outer exposed structure with to be made with 18mm MR ply as per IS 303 and back side using 8mm IS 303 MR grade ply. All shutters and shelves to be made with 18 mm thk. block board finished with 4mm thick veneer and finished with melamine polish. All the external exposed surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 4mm thick VENEER with 4 mm grooves as per drawings to be finished with melamine polish. Veneer Shutters to have 12 mm wide veins coating (moulding patti) made out of solid wood finished with melamine polish all around as per drawings. All internal surfaces to be provided with 0.8 mm laminate. All edges of the cupboard should be finished with 4 mm thick veneer finished with melamine polish. Shutters to be provided with 38 mm finger pull groove handle, magnetic catchers, self closing SS hinges, locks (Godrej/ Hettich/Haffele), SS towerbolts etc. All shutters to be made overlapping the frame. Only front elevation will be considered for area calculation As per drawing and instruction of Architect/Bank. Basic Cost of Veneer - Rs. 1200/ Sqm</p>	13	Sq.Mt.		
	<p>Approved make:- (a) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (b) Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank. (c) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.</p>				
			TOTAL 7		
8	Ready Made Tables				
8.1	<p>Providing and Fixing table of following description (Drawing code DR1) Work Surface-Made of 36mm thick MR one side prelaminate board conforming to IS14587: Discussion round table of Size 900 mm Dia. and Height 750 mm. Glass table top.12 mm thick clear glass with cristle edge polish supported with 15 mm dia SS pipe supports with necessary fixtures and hardware. All as per the Architectural Drawing</p>	4	Nos		
8.2	<p>Display Cabinet (Drawing code MR 1 B) Full Height Cabinet with Veneer Finish: Providing & fixing Full Height Storage Cupboard of height 2100mm and 450mm deep Outer exposed structure with to be made with 18mm MR Ply's per IS 303 and back side using 8mm IS 303 MR grade ply. All shelves to be made with 19 mm thk with Veneer finish and melamine polish. Front shutter to have Anodised Aluminium profile shutter with clear glass. All internal surfaces to be provided with 1mm. All edges of the cupboard should be edgebanded using veneer with melamine polish. Shutters to be provided with S.S. 200mm handles, magnetic catchers, self closing SS hinges, locks , SS towerbolts etc. All shutters to to be made overlapping the frame. Only front elevation will be considered for area calculation As per drawing and instruction of Architect/Bank. Basic Rate of Veneer Rs. 1200/ Sqm</p>	2	Sq.Mt		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
8.3	<p>PA Table - 1500W X 750D X 750 Side Unit 900 x 450 x 750</p> <p>Table Top: Providing and fixing 18 mm thick IS 303 MR grade plywood with 1mm thick laminate with necessary intermediate support. Table top shall be supported by 18 mm thick IS 303 MR grade ply wood with plywood framing. Apron (Modesty Panel) made from 18mm thick IS 303 MR grade plywood finished with 1mm laminate. Table to have 0.8 mm thick laminate for inner surfaces shall be provided as per drawing. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>Side Storage cabinet: Box of 900 x 450 x 750 mm shall be provided using 18 mm thick IS 303 MR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of 2 no's drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick IS 303 MR grade plywood. The cabinet to have 1 no's adjustable shelf 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>The Pedestal/ Drawer unit box 450 x 450 x 720 mm with 3 individual drawers to be made in MR ply finished with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick white laminate. The drawers to be fitted with Telescopic sliding channel (of approved makes) with SS Group locks of approved make and provided with 38 mm finger groove handle for each drawer. The front ply of the drawers to be overlapping the frame. All exposed edges finished with machine pressed 2mm PVC edge banding glued with hot melt EVA glue.</p> <p>Computer Keyboard drawer (550 x 375 mm) of metal / PVC of approved make shall be provided. Footrest (400 x 400) made of 18 mm thick MR ply finished with 1 mm laminate of approved shade and make. All internal surface will have min. 0.80 mm thick balancing laminate. Table shall have stand of 18 mm MR ply finish with 1 mm thk.As per drawing and instruction of Architect/Bank.</p> <p>The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>As per drawing and instruction of Architect/Bank.</p> <p>Basic Rate of laminate - Rs. 700 / Sqm</p>	5	Nos		
8.4	<p>Pantry Trolleys (Drawing code PTY-TR) Size-2.5mx 0.70m x 0.70m as per Architectural drawing / Engineer Incharge</p> <p>Providing & fixing Structural frames and door frames in MR Ply carcass.</p> <p>Tandem drawers with cutlery insert, Bottom pull outs,HDHMR based for Tandem dwr. Antiskid matt 1 mm thick. Novo pro Drawer with telescopic soft close sliders.</p> <p>Pull grip Handles High Glass Laminate front Panels</p>	3	Nos		
8.5	<p>Pantry Overhead unit (Drawing code PTY -OH)</p> <p>Providing and fixing pantry overhead unit of size 2.5mx 0.6m x 0.3 m as per Architectural drawing / Engineer Incharge and having following specification</p> <p>HDHMR Boxes visible sides MR tough glass laminate</p> <p>soft close Door openings.</p>	3	Nos		
8.6	<p>Coffee Table</p> <p>Manufacturing, assembling, transporting & placing / fixing in position coffee table, inclusive of all fixtures, finishing, having dimentions1100 x400x600 mm sixes finished with 8 mm thick Tempered glass with maximum load capacity of 40 kg. net weight 23.3 kg. and having UV cured stainless steel disc holding the top and under structure together. As selected by Architect Incharge.</p>	9	Nos		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
8.7	<p>Conference Table 11 MEETING ROOM TABLE - 3900(L) X 1200 (W) X 750(H):</p> <ul style="list-style-type: none"> • WORKTOP to be made of with 28mm thk. MR ply finished with 4 mm thick veneer finished with melamine polish, Work surface HT shall be 750mm • STRUCTURAL SUPPORT SYSTEM:- 2 nos. 600 x 900 mm box made out of 18 mm IS 303 MR ply and finished with veneer. Both boxes to be connected using Horizontal modesty panel of size 400 mm for best stability. Modesty panel to be made out of 18 mm ply finished with veneer. <p>All Veneer finished with melamine polish.</p> <ul style="list-style-type: none"> • WIRE MANAGEMENT:- The Vertical (Vertical Duct) & Horizontal (1 tier cable tray) wire carriers are placed below worktop, made up of CRCA with Powder Coating & Fixed to the under structure with specially designed brackets. A Metal Separator within the wire carrier is provided to separate electrical & data cables. Switch plates to be in the cable tray, easily accessible through a ACCESS FLAP. <p>Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards etc including providing necessary wooden supports wherever required and directed at site.</p> <p>As per drawing and instruction of Architect/Bank.</p>	3	Nos		
			TOTAL 8		
9	Back Wall Unit				
9.1	<p>Back Wall Unit (Drawing code DGM BWU) Providing & fixing a wall unit with 18mm MR plywood for main structure, back with 8mm ply , overall unit to be finished with 4mm thick quality veneer approved by Architect & coated with 2 coats of Melamine polish. Free edges of shelves with T inlay pattis as per the drawing & details as shown in the drawing.Grooves & edges of all vertcals,horizontals of shelves, to be finished with melamine polish. Unit should be complete with standard hardware fittings, hinges,locks As per drawing and instruction of Architect/Bank.</p>	16	Sq.Mt.		
	<p>Approved make:- Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Bank. Veneer- Green/Jalaram/ Merino or equivalent approved by the Bank. Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank. Base Rate - Veneer- Rs 1200 /Sqm</p>				
9.2	<p>Back Wall unit AGM (Drawing code AGM BWU) Providing & fixing a wall unit with 18mm MR plywood for main structure, back with 8mm ply , overall unit to be finished with 1mm thick quality laminate approved by Architect. Free edges of shelves with T inlay pattis as per the drawing & details with standard adhesives as shown in the drawing.Grooves & edges of all vertcals,horizontals of shelves, to be finished with melamine polished. Unit should be complete with standard hardware fittings, hinges,locks As per drawing and instruction of Architect/Bank.</p>	12	Sq.Mt.		
	<p>Approved make:- Plywood:- Greenply, Century, Samrat, Duro or equivalent approved by the Bank. Laminate:- Greenlam/Century/Merino/ Royal touch or equivalent approved by the Bank. Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank. Base Rate - Laminate- Rs700 /Sqm</p>				
			TOTAL 9		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
10	<p>PHONE BOOTH</p> <p>This MAX L Pod is designed for comfort and functionality, featuring a fabric exterior and interior wood finish for an elegant and modern look. It has the following dimensions: External Dimensions: L2200mm x D1200mm x H2250mm Internal Dimensions: L2030mm x D1140mm x H2117mm Required Room Height on Site: 2400mm</p> <p>The pod includes booth facilities such as interior/exterior fixtures, a fixed centre discussion table, Serene sofa, and Netbow power for convenience. The furniture includes both a table and sofa for a complete functional space. Ideal for collaborative environments, this pod offers privacy and a comfortable setting for discussions or meetings Approved Makes- Talkbox, Phonebooth,featherlite Silentium or equivalent as approved by Bank</p>	4	Nos.		
11	Chairs				
11.1	<p>Supplying and Installation of Chairs for Meeting room, Discussion room B Manager Chairs</p> <p>Amaze Medium Back Mesh Chair: The chair features an AN 70 mesh backrest with a self-calibrating multilock mechanism for ergonomic support. It includes an adjustable lumbar support, one-way adjustable arms (height), and a durable nylon base. The seat is upholstered with fabric and cushioned for added comfort, ensuring a versatile and functional seating solution Featherlite - Amaze Medium Back Mesh Chair Wipro - Adapt Mid Back Bosq - Performance or work Chair Approved Make- Godrei/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	157	Nos.		
11.2	<p>Supplying and Installation of chairs for Reception Assistant Manager * Medium Back Mesh Chair</p> <p>The chair is designed with an AN 70 mesh backrest for breathability and durability. It features a self-calibrating multilock mechanism for customized reclining positions and an adjustable lumbar support for enhanced comfort. The one-way adjustable arms allow height adjustments, while the nylon base ensures stability. The seat is fabric upholstered and cushioned for added comfort and a premium finish Featherlite - Amaze Medium Back Mesh Chair Wipro - Adapt Mid Back Bosq - Performance or work Chair Approved Make- Godrei/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	11	Nos.		
11.3	<p>Supplying and Installation of chairs for CM main B Manager Chairs</p> <p>The chair features an AN 70 mesh backrest for superior ventilation and support. It is equipped with a self-calibrating multilock mechanism for flexible reclining and an adjustable lumbar support for optimal posture. The one-way adjustable arms enable height customization, while the sturdy metal base provides exceptional durability. The seat is fabric upholstered and cushioned for enhanced comfort and style. Featherlite - Amaze High Back Mesh Chair Wipro - Adapt High Back Bosq - Executive Chair Approved Make- Godrei/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	23	Nos.		
11.4	<p>Supplying and Installation of chairs for CM visitors Assistant Manager * Grey Medium Back Chair</p> <p>The chair is designed with an AN 75 mesh backrest for optimal breathability and durability. It features a self-calibrating multilock mechanism for versatile reclining and an adjustable lumbar support for superior comfort. The grey one-way adjustable arms offer height customization, while the robust metal base ensures long-lasting stability. The seat is fabric upholstered and cushioned for a comfortable and elegant seating experience. Featherlite - Amaze Medium Back Mesh Chair Wipro - Adapt Mid Back Bosq - Performance or work Chair Approved Make- Godrei/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	49	Nos.		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
11.5	<p>Supplying and Installation of chair Workstation, file store, PA</p> <p>The chair is equipped with an AN 70 mesh backrest for excellent ventilation and durability. It includes a self-calibrating multilock mechanism for adaptive reclining and an adjustable lumbar support for enhanced ergonomic comfort. The one-way adjustable arms allow height customization, while the sturdy nylon base ensures stability. The seat is fabric upholstered and cushioned, offering a comfortable and stylish seating solution.</p> <p>Featherlite - Amaze Medium Back Mesh Chair Wipro - Adapt Mid Back Bosq - Performance or work Chair Approved Make- Godrej/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	186	Nos.		
11.6	<p>Supplying and Installation of chair AGM Main</p> <p>The chair features a medium back design with a multilock mechanism for adjustable reclining comfort. It includes two-way adjustable arms (height and swivel) for personalized support. The sturdy chrome base ensures durability and stability. The seat and back are upholstered in leatherette material with an elegant beige color, providing a sophisticated and comfortable seating experience.</p> <p>Featherlite - Amaze High Back Mesh Chair Wipro - Adapt High Back Bosq - Executive Chair Approved Make- Godrej/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	7	Nos.		
11.7	<p>Supplying and Installation of chair DGM</p> <p>The chair is designed with a fabric upholstered cushion seat for enhanced comfort and style. It features a multi-lock synchro mechanism for adjustable reclining, an adjustable lumbar support for ergonomic posture, and a seat sliding function for personalized seating depth. The four-way (4D) adjustable arms provide flexibility in height, width, depth, and angle adjustments, while the durable nylon base ensures stability and longevity</p> <p>Featherlite - Helix High Back Mesh Chair Wipro - Absolute High Back Bosq - Executive Chair Approved Make- Godrej/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	2	Nos.		
11.8	<p>Supplying and Installation of chair AGM/DGM visitors Assistant Medium Back Chair</p> <p>The Amaze Grey Medium Back Chair features an AN 75 mesh backrest for enhanced breathability and support. It is equipped with a self-calibrating multilock mechanism for adjustable reclining and an adjustable lumbar support for optimal posture. The chair includes grey one-way adjustable arms (height) and a durable metal base for stability. The seat is fabric upholstered and cushioned, offering a comfortable and stylish seating experience.</p> <p>Featherlite - Helix Mid Back Mesh Chair Wipro - Absolute Mid Back Bosq - Performance or Work Chair Approved Make- Godrej/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	17	Nos.		
11.9	<p>sofa Executive</p> <p>3-Seater Sofa: This elegant three-seater sofa features a width of 1930mm, depth of 800mm, and a height of 820mm, providing ample seating space with a compact design. It is crafted for comfort and style, making it a perfect fit for any modern living or office space.</p> <p>Basic Rate - Rs 42000/- Approved Make- Godrej/ featherlite /Wipro/Bosq or equivalent as approved by Bank</p>	5	Nos.		

INTERIOR FURNISHING WORKS OF 1ST, 2ND & 3RD FLOORS OF CLOCK TOWER, KHARADI, PUNE FOR ESTABLISHMENT OF BANK'S AO PUNE & 3 RBO

Item No.	Description	Total Quantity	Unit	Rate	Amount
11.10	Providing and Supplying ladies room 3-Seater Sofa cum Bed & Single-Seater Sofa cum Bed: The single-seater sofa cum bed has an overall sofa size of 800L x 850D x 930H (mm) and bed dimensions of 1980L x 580W mm (580W excluding armrests, 800mm including side panels). The seat height is 430mm (17 inches). Upholstery Material: Fabric (100% polyester, 400-450 gsm, with high abrasion resistance of 50,000+ cycles). Frame: Made from treated pine wood and plywood, with high-quality 32-density foam for both seat and bed, upholstered in fabric or leatherette. Mechanism: Metal with corrosion-resistant coating for seamless sofa-to-bed conversion. Backrest: Features three locking positions adjustable for user convenience. Designed for durability, comfort, and functionality, this sofa cum bed is ideal for versatile living spaces. Basic Rate - Rs. 56,000/- Approved Make- Godrej/ featherlite /Wipro/Bosq or equivalent as approved by Bank	1	Nos.		
11.11	Coffee table chair Cushion Seat and Mesh Back Chair: This chair is designed for both comfort and style, featuring a cushion seat for added comfort and a mesh back for breathability and support. It includes a pneumatic gas lift mechanism, allowing for easy adjustment of seating height to suit different user preferences. Ideal for office or home use, this chair combines ergonomic functionality with a modern aesthetic. Basic Rate - Rs. 4,000/- Approved Make-Godrej/ featherlite /Wipro/Bosq or equivalent as approved by Bank	10	Nos.		
			TOTAL 11		