



PRICE BID

Annexure-III

BOQ for Supply and Installation of Air Conditioners at AIIMS Phulwari Sharif Branch and ATM

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
1	Supply of 1.0 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Hitachi (ATM)	Nos.	2		
2	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Hitachi (BM Chamber)	Nos.	1		
3	Supply of 2.0 TR Capacity Ceiling Mounted 4-way Copper Cassette type split air conditioners with Copper Condensor Coil and eco friendly refrigerants (R32 or R 410A) of higher star rating and inverter model available in market. AC Make, Voltas/Bluestar/Carrier/Daikin /LG/Hitachi	Nos.	7		
4	Installation charges of the 1.0TR/1.5 TR Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	3		
5	Installation charges of the 2.0 TR Copper Cassette Type Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	7		
6	For 1.0 TR/1.5 TR Copper Hi-Wall type split air conditioners: Supply and laying of copper pipes with insulations , drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	35		

7	For 2.0 TR Copper Cassette type split air conditioners: Supply and laying of copper pipes with nitrile insulations, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	145		
8	Supply and Installation of 4 KVA Stabilizer for 1.0/1.5 TR Split Acs	Nos.	2		
9	Supply and Installation of 5 KVA Stabilizer for 2.0 TR Cassette type Acs	Nos.	7		
10	Supply & Installation of 20 A , Timer switch with 2 no.s of 20A DP MCB's alongwith suitable size enclosure box for switching of AC's alongwith 2 NO 25 A 1M contactor in the same enclosure box for controlling 2 no.s of AC power circuit through timer including all necessary hardware & accessories etc complete as required.	Nos.	1		
GST will be extra as applicable			Grand Total(In Rupees)		