

| PRICE BID FOR PROPOSED ELECTRICAL AND AIR-CONDITIONING WORKS FOR SONHAT BRANCH RBO-4, BILASPUR MODULE | | | | | |
|---|--|-----|------|-----------------|--------|
| S.No. | Description of Item | Qty | Unit | L-1 TENDER COST | |
| | | | | Rate | Amount |
| A | Part A : Electrical Works : | | | | |
| | ELECTRICAL WIRING WORK | | | | |
| | Note: Use of Flexible conduits & Elbows in Circuit wiring is not allowed except in exceptional site conditions with the approval of Bank's Engineer / Architect and All wiring laying in the MS/PVC conduit strickle follow IE(Indian Electricity) rules, IS code, follow in all items of project/ work execution. Proper ferrules, lux, thimble , gland termination to be done in all cabling & wiring from both load/source end. Conduit carrying submain will not carry circuit/point wiring. Similarly conduit carrying circuit wiring will not carry submain/point wiring. Conduit carrying point wiring will not carry submain/circuit wiring. All Electrical works (Cabling/wiring/panel etc) to be carried out as per layout/General Arrangement (GA)Drawing attached only. | | | | |
| 1 | ELECTRICAL WIRING | | | | |
| | Providing, fixing, testing and commissioning of POINT WIRING of any length for light point/Wall fan point/Exhaust fan point/ Call bell point/ including call bell/ including fan box(if required), 'S' type fan hook etc with 3 X 1.5 Sq.mm(P/N/E) PVC 650V/1100V Grade FR insulated copper conductor single core multi stredned wire in 16 SWG(Medium Gauge) stove enamelled rigid steel conduit 20mm/25mm with conduit accessories like bend, junction box etc in concealed/surface manner as per site requirment with suitable Modular Switches/sockets with plate and Metal/PVC box,Scaddle, angle bracket (if required), 3 plate ceiling rose/bulb holder etc. The floor/roof/wall junction box shuold be of MS(heavy duty) box of suitable size and covered with Steel finish Steel cover sheet by screw tight and gasket to avoid water/dust insertion. The above wiring carried out surface or recess in wall/floor/roof should be cutting by cutter/chiesling, replastering, curing, painting with uniform and smooth finish by specilised workman ship and making the surface neat afterwards complete in all respect as per direction of Bank Engg. (EACH Circuit to take NOT MORE than 7-8 points) The conduit/ Flexible conduit/junction | | | | |
| | Phase- Red, Neutral- Black, Earth-Green | | | | |
| | Make of Material for items of BOQ:- | | | | |
| | (i) Modular Type Switch/socket/step electronic fan regulator, plate, box, TV/telephone, bulb holder/3 pin ceiling rose with all accessories:- Lergand/ Anchor(Roma)/MK/ Crabtree | | | | |
| | (ii) MS conduit/PVC conduit with all accessories:- BEC/AKG/NIC/Precision | | | | |
| | (iii) PVC insulated copper wire(FR) 650V/1100 V grade:- Finolex/RR cable/ Havells | | | | |
| a | Providing and fixing of point wiring with above specifications. One light point controlled by one switch. | 40 | Nos. | | |
| b | Providing and fixing of point wiring with same above specifications. Two light points to be controlled by one switch. | 15 | Nos | | |
| C | Providing and fixing of ceiling fan point controlled as under (i) one 6 amp switch (ii) one no stepped electronic regulator of two module type. | 8 | Nos. | | |
| d | providing and fixing 6 Amps Plug Points with same specs as above and install along with same light switchboard | 8 | Nos | | |
| e. | Master switch of 16 Amps(Only Grey/Golden/Wooden colour other than white colour) to install alongwith same light switch board to control all light as a master switch ON/OFF in each switch board | 8 | Nos | | |
| 2 | 6 AMP. POINTS ON SEPARATE BOARD : | | | | |
| | Supply,fixing,testing and commissioning of 1 No 6 A Multi Socket with 1No. 6 A switch (Modular type) with cover plate , sheet steel box / PVC modular box etc on surface / concealed manner l/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed. | 6 | Nos | | |
| | (Minimum two and Maximum three points are loop with one circuit as mentioned beolw) | | | | |
| 3 | Power Wring (6 / 16 AMP. POWER POINTS) | | | | |

| | | | | | |
|----------|--|----|-------|--|--|
| | Supply, fixing, testing and commissioning of 1 No 16 A switch & 1 No.six pin 6/16 Amp. Multi Socket (Modular Type) with cover plate , sheet steel box etc on surface / concealed manner i/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed. | 8 | Nos | | |
| | (Maximum two points are loop with one circuit as mentioned below) | | | | |
| 4 | SPECIAL POINTS : (For Computers) | | | | |
| | Supply, fixing, testing and commissioning of following Modular type switch socket with cover plate, PVC modular box on Surface / sheet steel box in concealed manner i/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed. | 6 | Nos | | |
| | 2 Nos. 6 A Switch + 3 Nos. 6 A, 3 pin Socket | | | | |
| | (Minimum two and Maximum three points are loop with one circuit as mentioned below) | | | | |
| 5 | AC/Geyser Point (Single Phase) | | | | |
| | Supply, Installation, Testing and commissioning of the surface / recess mounting A.C. / GEYSER power point with the followings : | | | | |
| | Metra Plug and Socket DBs with one Nos 20 Amp SP MCB, 20 Amp plug and socket with complete Enclosur plate and box.- 1 set i/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as required as per site requirement and as directed by Bank Engineer. | 2 | Nos | | |
| | OR Modular 32A DP 1 way switch with plate & box 1 set. + 25A & 10A twin socket | | | | |
| | (Only one point is connected with one circuit as mentioned below) | | | | |
| 6 | AC Point (Three Phase) | | | | |
| | Supply, Installation, Testing and commissioning of the surface / recess mounting A.C. Cassette power point with the followings : | | | | |
| a. | Metal enclose Four way with one Nos 32 Amp FP MCB with complete Enclosur plate and box.- 1 set i/c electrical connections and making good all the damages, painting, cleaning the site etc complete as required as per site requirement and as directed. (Only one point is connected with one circuit as mentioned below) | 3 | Nos | | |
| 7 | CIRCUIT WIRING : | | | | |
| | Supplying, providing circuit wiring for Power/UPS with following PVC insulated copper conductor single core multi stredned wire (HRFRR) in mentioned conduit i/c electrical connections in suitable size MS / PVC modular boxes and it laying, fixing, testing and commissioning in suitable size 20/25 mm dia,16 SWG (Medium Gauge) thickness rigid MS conduit with conduit accessories like bend/junction box/ fan box etcwith cover plate, sheet steel box/ PVC modular box etc on surface/ concealed manner i/c electrical connections and making goods all the damages, replastering, painting, cleaning the site etc complete as required as per site condition. The floor/roof/wall junction box should be of MS(heavy duty) box of suitable size and covered with Steel finish Steel cover sheet by screw tight and gasket to avoid water/dust insertion. The length of circuit upto 30 meter length or less as per site condition/requirement. Make of Material | | | | |
| | (i) MS conduit/PVC conduit with all accessories:- BEC/AKG/NIC/Precision | | | | |
| | (ii) PVC insulated copper wire(FR) 650V/1100 V grade:- Finolex/RR cable/ Havells | | | | |
| a | 3 X 2.5 sqmm (For UPS Circuit/6 amp Separate Board) in suitable size of 16 SWG (MMS) steel conduit as per IS code. | 12 | Nos | | |
| b | 3 X 4.0 sqmm (For AC/Power Circuit) in suitable size of 16 SWG (MMS) steel conduit as per IS code. | 2 | Nos | | |
| c | 5 x 4.0 sqmm (for three phase AC Indoor Circuit) in suitable size of 16 SWG(MMS) steel conduit as per IS code. | 2 | Nos | | |
| 8 | UPS OUTGOING & OTHER WIRING, As Per Requirement. | | | | |
| (a) | 3 x 10 Sqmm copper multistread wire in 25 mm 16 SGW (MMS) steel conduit. (UPS INPUT DB TO UPS) | 10 | R.Mtr | | |
| (b) | 3 X 1.5 Sqmm copper multistread wire in suitable size of 16 SWG (MMS) steel conduit. | 20 | R.Mtr | | |

| | | | | | |
|----------|--|----|-------|--|--|
| (c) | 3 X 2.5 Sqmm copper multistread wire in suitable size of 16 SWG (MMS) steel conduit. | 45 | R.Mtr | | |
| (d) | 3 X 4 Sqmm copper multistread wire in suitable size of 16 SWG (MMS) steel conduit. | 10 | R.Mtr | | |
| (e) | 5 X 4 Sqmm. Copper multistread wire in suitable size of 16 SWG (MMS) steel conduit (For Cassette AC) | 10 | R.Mtr | | |
| (f) | 3 X 6 Sqmm copper multistread wire in suitable size of 16 SWG (MMS) steel conduit. | 25 | R.Mtr | | |
| 9 | DISTRIBUTION BOARDS | | | | |
| | All MCB to be "C" series | | | | |
| | Supply, installation, Testing and commissioning of the surface/recess mounting following ways MCB DB's 230/415 Volts with tinned copper busbar, neutral bar, earth bar, din bar detachable gland plate, interconnection and making good all the damages, painting, cleaning the site etc complete as required as per site requirement. All MCCB has braking capacity is 25KA and ALL MCB/ELCB has breaking capacity has 10 KA. Make of Materials | | | | |
| | Panel- As per IS Standards/CPRI Tested. | | | | |
| | DBs/MCCB/MCBs- Legrand/Siemens/Hagger/Schneider only | | | | |
| | (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered) | | | | |
| a | <p>Supplying, installation, testing and commissioning of indoor type , sectionalised, compartmentalized, MV Panel board of suitable size fabricated from CRCA sheet of 2 mm thick for frame work,enclosure and doors, 3 mm thick for gland plates with stiffers where required, having vibration free structure chemically treated with seven tank process before painting for surface treatment and powder coated,with aluminum busbar with DMC / SMC busbar supports suitable for 3 Phase 415 V 50 Hz AC supply i/c providing and fixing the following switchgear mounted thereon complete with gaskets and interconnections, connection as per specification complete as required.</p> <p>(The board shall be dust & vermin proof with suitable degree of IP protection) NOTE : All switchgears Ics shall be equal to 100% Icu.</p> <p>Sheet 14 swg : panel sides,upper,lower,and Ft.doors Sheet 16 swg : back side and compartments. Glande plates : 3 mm thick. Cable entry : Provision at bottom and upper sides. The above panel belongs following as under: A. 4 Nos. 200 Amp. Electrolytic grade Aluminum Bus Bars insulated with colored Heat Shrinkable PVC Sleeves & duly supported on SMC/DMC molded supports with Antitracking barriers. B.INCOMING SWITCHGEARS :(RYB LED Indicators for Both Main/DG) (i) 1 No. FP.125 A , 25 KA MCCB with thermal magnetic trip unit with digital voltmeter & ammeter with suitable size of CTs, selector switch etc. C. OUTGOING SWITCHGEARS: (i) 1 Nos- 125Amp TP MCCB for main with 200amp bus bar with indicator. (ii) 160 amp onload changeover with 1 Nos 125 amp 25 KA, TP MCCB for DG supply with 200 amp bus bar with indicator (iii) 200 amp bus bar for parallel connection with DG changeover output (Note:- Before Placing the Panel order, firstly it Passed by The Bank Authority, otherwise it will not considered)</p> | 1 | Nos | | |
| b | Supply & Installation of SDP(Surge Protector Devicve) for general protection of main Distribution Board Legrad Make Cat No. 412247 (3P+N) , 40 KA, T2- I _{max} 40KA/pole with complete wiring. | 1 | Nos | | |
| c | Providing and fixing 6 way TPN double door DB for LIGHT /POWER POINTS with 63 Amp TPN , controlling 18 Nos. 10/16/32 Amps SPMCBs. & Complete. | 2 | Nos | | |
| d | Providing and fixing 4 way TPN double door DB for LIGHT /POWER POINTS with 63 Amp TPN , controlling 12 Nos. 16/32 Amps SPMCBs. & Complete. | 1 | Nos | | |
| e | Providing and fixing (12) way SPDB double door type For UPS points with 1x32 Amps DP, controlling 10 Nos, 16 AMP SPMCB | 1 | Nos. | | |
| f | Providing and fixing (8) way SPDB double door type For Light DB only for Emergency Lights like glow sign etc with 1x32 Amps DP, controlling 6 NO.10 A./16 AMP SPMCB | 1 | Nos. | | |

| | | | | | |
|-----------|--|----|------|--|--|
| | | | | | |
| g | Providing and fixing (4) way TPN double door type For UPS INPUT with 1x63 Amps TPN and 63 amp DP MCB- 3 Nos & 3 Nos, 32 amp SP MCB complete (E-lobby/UPS Output) | 1 | Nos. | | |
| h | Providing and fixing of Kit Kat Rewirable Porcelian fuse carrier & base with wooden frame of 200 amp/415 Volt near meter box | 1 | Set | | |
| 10 | CABLES | | | | |
| | Supplying, unloading, storage, laying, testing and commissioning of PVC/XLPE insulated (Heavy Duty) Al/Cu conductor armoured cable suitable for working voltage upto and including 1100 V grade, laid and tied on existing overhead cable trays, or laid and tied over MS supports in masonry trenches with copper/al cable lugs, single compression brass cable glands, tapping, crimping etc. as required and all cables run with double run(2 No.) of GI wire of 8 SWG size. The size of cables are as under:- | | | | |
| | Make of Material:- | | | | |
| | (i) PVC/XLPC Armoured cable:- Finolex, Havells, RR cable, CCI(Cable Corp. of India) | | | | |
| | (ii) Cable Termination:- Dowells, Comet | | | | |
| a | 3.5 X 70 Sq.mm XLPE. Al. armoured Cable(AC VTPN & BUS BARS)/Main cable | 40 | Mtr | | |
| b | 3.5 X35 Sq.mm XLPE.Al.armoured Cable (POWER) | 40 | Mtr | | |
| c | 4X 25 Sq.mm XLPE.Al.armoured Cable (POWER/LIGHT/UPS) | 40 | Mtr | | |
| d | 4X 16 Sq.mm XLPE.Al.armoured Cable (LIGHT/UPS) | 50 | Mtr | | |
| 11 | EARTHING | | | | |
| | COPPER PLATE EARTH STATION: | | | | |
| | Preparation of the Plate Earth Station:(As per IS:3043) | | | | |
| | Supply, Installation, Testing and Commissioning of Maintenance Free Earthing system made up of copperbondedrod of 10 feet length,23 mm dia. (Minimum copper bonding shall be 0.25mm) along with Rod-to-Conductor connectors, Earth enhancement material, Pit Cover and other accessories as required and as per specification and other applicable codes (include chamber for earthing as well as Earthing certificate showing the required values). (JEF ECO Safe / SEE / Duval Messien/ E Damen) | | | | |
| (i) | (a) Excavation of hard rocky earth, soft murrum, hard murrum etc and back filling with black cotton soil for the earth station, the earth pit size is 1000 mm X 1000 mm X 2500 mm. | 2 | Nos | | |
| | (b) Supply and fixing of Copper Plate of Size 600 mm X 600 mm X 3.0 mm thick. | | | | |
| | (c) Fixing of 50 mm X 6 mm, 3 Mtrs copper strips from Copper Plate to earth terminal including brazing/welding at plate etc. | | | | |
| | (d) Supply and laying in position 19 mm, 2 Mtrs G.I "B" Class pipe for watering with reducer/funnel with mesh. | | | | |
| | (e) Supply and Fixing of the following in the earth station. | | | | |
| | (i) 75 Kg. Charcoal. | | | | |
| | (ii) 15 Kg. Original Salt. | | | | |
| | (iii) Black Cotton soil of adequate amount. | | | | |
| | (f) Construction of earth pit chamber including necessary brick work concrete, plastering, S/F of C.I Cover of size 12" X 12" complete as per site requirement. | | | | |
| | G.I.PLATE EARTH STATION : | | | | |
| | Preparation of the Plate Earth Station: (as per IS:3043) | | | | |
| (ii) | (a) Excavation of rocky earth, soft murrum, hard murrum etc and back filling with black cotton soil for the earth station, the earth pit size is 1000 mm x 1000 mm x 2500 mm deep. | 2 | Nos | | |
| | (b) S/F of G.I. plate of size 600 x 600 x 6.0 mm thick. | | | | |
| | (c) S/F fixing 50 mm x 6 mm, 3 mtrs G.I, strips from G.I.plate to earth terminal including brazing / welding at plate etc. | | | | |
| | (d) Supplying and laying in position 19 mm, 2 mtrs G.I. 'B' class pipe for watering.with reducer/funnel with mesh. | | | | |
| | (e) S/F of the following in the earth station. | | | | |
| | 75 Kg. Charcoal, 15 Kg. Original Salt. and Black Cotton soil of adequate amount. | | | | |
| | (f) Construction of earth pit chamber including necessary brick work concrete, plastering, S/F of C.I. Cover of size 12" x 12" complete as per site req.and marking its value and identification etc. | | | | |

| | | | | | |
|-----------|--|----|------|--|--|
| | | | | | |
| (iii) | Providing and fixing Copper/GI strip as per specification complete including connection to earth electrode revetting/sweating/soldering, burying 15 cms below in all types of soil/rocks etc complete as required. | | | | |
| | (a) Copper Strip 25 X 5 mm | 10 | Mtr. | | |
| | (b) G.I.Strip 25 X 5 mm | 10 | Mtr | | |
| (iv) | Supply and laying of 10 Sq.mm 650V/1100 V PVC grade insulated copper wire in 15 mm G.I. Pipe ISI grade including all accessories complete as required.(Dedicated Earthing for UPS output DB only) | 30 | Mtr. | | |
| 12 | OCCUPANCY SENSORS:- | | | | |
| | Supply, installation , testing and commissioning of occupancy sensor surface/recess mounted as per site condition complete with all wiring/conduit/Switch etc complete in all respect as per site condition as required Honeywell Make K5015/16, Siemens/Johnson Control | 2 | Nos | | |
| | OR Equivalent as per Bank's approved. | | | | |
| 13 | TELEPHONE POINT | | | | |
| | Supplying, Installation, testing and commissioning of the telephone point with the followings | | | | |
| (i) | Two pair, 0.61 mm dia. telephone cable tinned copper conductor, P.V.C. insulated and sheathed , fire retarding, anti termite, colour coded twisted pairs and rip cord, Double outlet The length of telephone cable upto 35 meter length or less as per site condition with shutter modular type Telephone Outlets (RJ — 11) with suitable size MS / PVC modular boxes and it laying, fixing, testing and commissioning in suitable size 20/25 mm dia,16 SWG (Medium Gauge) thickness rigid PVC conduit with conduit accessories like bend/junction box/cover plate/sheet steel/PVC box on surface/ concealed manner i/c electrical connections and making goods all the damages, replastering, painting, cleaning the site etc complete as required as per site condition. The floor/roof/wall junction box should be of MS(heavy duty) box of suitable size and covered with Steel finish Steel cover sheet by screw tight and gasket to avoid water/dust insertion. | 3 | Nos | | |
| | Make of Material:- Delton/Finolex/RR cable | | | | |
| (ii) | Supplying and fixing of krone telephone tag block on surface/ recess mounted with its accessories suitable for the multi core telephone cable and shall accommodate tin-plated phosphor bronze connectors, the connectors shall splice unskinned cables up to 0.61 mm dia and shall be terminate both incoming and out going lines, the tag blocks shall be mounted inside, water proof box and locking arrangement and shall be fully accessible. (A) 20 Pair tag block | 1 | Nos | | |
| (iii) | Supply, installation, testing and commissioning of the following size jelly filled armoured telephone cable. 20 pair | 20 | Mtr | | |
| 14 | DATA CABLING FOR LAN | | | | |
| a | Providing, fixing, testing and commissioning of all nodes of four pair UTP CAT 6 LAN cables length upto 30 meter length or less as per site condition in suitable size 20/25 mm dia, 16 SWG wall thickness rigid PVC conduit with conduit accessories like bend/junction box/ fan box etc on surface/recessed manner and making good all the damages, painting, cleaning the site etc complete as required as per site condition and as directed as required. Junction box should be covered with Stainless steel plate with screw with gasket for protection of water/dust. Providing, fixing, testing and commissioning of modular type Information Outlets with suitable size of MS/PVC modular boxes complete, all accessories with insulation displacement connectors etc suitable for CAT 6 UTP cabling with RJ-45 socket with testing and commissioning of STP cabling with scanner for all the nodes/switches/jack panel complete (Each point/circuit/cable from both load and source end to be marked with ferrules.) Make of Material:- (i) Data Cable, Cat 6 cable, Switch, Jack panel, Rack, Patch cords & Other accessories:- D-Link, Legrand | 9 | Nos | | |
| b | Providing and fixing Patch Panels 24 port (100 base TX) CAT 6 patch/jack panel with connector, outlets and necessary connectivity complete as required & (D-Link make) | 1 | Nos | | |

| | | | | | |
|-----|--|----|---------|--|--|
| c | Providing, assembling, fixing, testing and commissioning Floor/Wall mounted RACKS for gig switches, patch panels etc including cooling DUAL fan trays, a 10 Point PDU, Fixed Trays as necessary complete. 9 U wall mounted RACK | 1 | Nos | | |
| d | Providing and fixing of flowing factory fabricated Patch cords. (UTP/CAT 6 complete with connector on both side.) | | | | |
| i) | for 1 Mt. long | 10 | Nos. | | |
| ii) | for 2 Mt. long | 10 | Nos | | |
| e | Providing, fixing, testing and commissioning of four pair CAT 6 LAN cable in suitable size of 20/25mm PVC medium gauge 16SWG conduit including all accessories to interconnect the switches from different location. | 30 | Mtr | | |
| f | Providing, fixing, testing and commissioning of Jack Panel of reputed brand. | 1 | Nos | | |
| 15 | TV POINT:- Supply, installation, testing and commissioning of TV point(Modular) with RG-6 cable in the Medium Gauge 1.6 mm PVC Conduit with all accessories complete in all respect | 2 | Nos | | |
| 16 | Supply and installation of Vinyl sticker for on Electrical DBs like, " Switch Off at Night" , Switch Off For Safety, etc | 10 | Nos | | |
| 17 | Making & Providing of 3 sets of Asbuilt Drawing with coloured print for entire Electrical work (Power/UPS/Light/Data/Telephone/AC etc.) as advised by the Bank's Authority. | 1 | Lum sum | | |
| | Description of light /fan fixture | | | | |
| | Supply and Installation, Testing and commissioning of the following fittings / equipments in surface/recess mounted as directed etc down rods of size upto 300 mm where ever required with ball sockets, anchor fastner etc complete as per site conditions. All fittings should be hang with suitable size of GI wire to four corner of fittings to the RCC rooftop with suitable size of anchor fastner/heavy gauge screw. The necessary arrangement is made by the contractor to install fittings in false ceiling especially 2'X2' and 4'X1' etc. as per instruction of Bank Engg. | | | | |
| 18 | LED LUMINARES:- 2' x2' (FULL GLOW TYPE) LED light fittings (600 X600mm) dimension suitable for grid/gypsum ceiling complete with its electronic driver as required per instruction of Bank's Model No are as under:- PHILIPS:- RC380B G2 LED 35S-6500 PSU OD WH LED (FULLGLOW) WIPRO:- CRCO10RO 38 HP57 HAVELLS:- LHECDIL7IL1W036 (Edge- Lit) CG:- LCTAR3-40-CDL | 14 | Nos | | |
| 19 | LED DOWNLIGHTER: 15 Watt, recessed mounted circular down lighter , 6" dimension with complete its electronic driver are as under:- PHILIPS:- GREENLED-DN193B LED-12S-6500 PSU WIPRO:- IRIS LED LD 71-121-XXX-50-XX HAVELLS:- LHEBJNP ZPZ 1W 015(ENDURA LOW DEPTH) CG:- LC DD-15-CDL, | 20 | Nos | | |
| 20 | LED Spot Light, 3 Watt, 2/3"(Inches) size as per site requirement. PHILIPS, WIPRO, HAVELLS, CG | 4 | Nos | | |
| 21 | LED COVE/ STRIP LIGHT WITH ITS ELECTRONIC DRIVER(BLUE COLOUR):- Supply, installation, testing and commissioning of bright LED strip light with its electronic driver complete as required. PHILIPS, WIPRO, HAVELLS, CG | 60 | Mtr | | |
| 22 | BOX TYPE LUMINARES: LED TUBE FITTINGS, 1200mm, 18/20 Watt PHILIPS/WIPRO/HAVELLS/CG | 15 | Nos | | |
| 23 | FAN:- (Five star rating BLDC fan) | | | | |
| a | CEILING FAN: Single phase heavy duty grease filled double ball bearing, aerodynamically designed heavy gauge aluminium blades, copper wound and impregnated silicon stamping motors etc 1200 mm sweep, brilliant white | 8 | Nos | | |

| | | | | | |
|----------|--|----|-----|--|--|
| | CG/USHA/ ORIENT/HAVELLS | | | | |
| b | WALL FAN:-(Only Metallic Body) | 2 | Nos | | |
| | Oscillating wall fan with regulator i/c connections etc complete as required as per approved make, Sweep 400/450 mm , RPM 1300 make are as under: | | | | |
| | CG/USHA/ ORIENT/HAVELLS | | | | |
| | EXHAUST FAN:- | | | | |
| 24 | Single phase, 300mm sweep, 900 rpm, metallic exhaust fan of the following single phase Exhaust fan continuously rated, capacitor start and run type, totally enclosed and ruggedly built, pre lubricated double ball bearing, copper wound, A & E class insulation, dynamically balanced, below 40 db sound level etc, front cover with grill/gravity louver for protection purpose with 12 mm plywood complete in all respect make as under: CG/USHA/ ORIENT/HAVELLS/ALMONARD/ALSTOM | 10 | Nos | | |
| | Sub Total : Part A (Electrical Works) | | | | |
| | | | | | |
| B | Part B : AIR CONDITIONING WORKS : | | | | |
| | AIR CONDITIONING WORK | | | | |
| | Supply, installation, testing and commissioning of following AIR CONDITRIONERS as under. The Rate shall be inclusive of all taxes excluding GST. GST will be paid additionally by the Bank as applicable subject to GST Number. and system has complete one year warranty & If any additional warranty provided by company/vendor in any specific part like compressor etc that is acceptable, please mentioned it. | | | | |
| | Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only | | | | |
| | | | | | |
| 25 | Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, FIVE STAR RATING OF BEE AIR CONDITIONERS 1.5 Ton Machines conforming to latest Indian Standards and suitable for operation on 230 Volts + 10 %, single Phase, 50 Hz AC supply with rotary compressor, Refrigerant and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The out door unit should be anti-rust powder coated. Indoor unit should | 3 | Nos | | |
| | Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only | | | | |
| | | | | | |
| 26 | Supply, installation, testing and commissioning of Higher Efficient models of CASSETTE TYPE AIR CONDITIONERS(Three) BEE Certified rating 2.0 Ton Machines conforming to latest Indian Standards and suitable for operation on 415 Volts + 10 %, three Phase, 50 Hz AC supply with Scroll compressor, Refrigerant (R-32) and capable to perform cooling, dehumidifying, Air Circulating, auto mode, auto swing, anti dust , anti bacteria filtering, ventilation and with remote control with Cool/Fan/Dry/Auto mode, sleep mode & on/off timer with suitable thermostat. The rate should include installation charges after making appropriate changes in existing false ceiling. Heavy ready made/fabricated M S Stand to house the out door unit as per site conditions including carpentry work, minor civil work and material including copper piping of hard & prime quality of min. 22 G upto 5 metres with class "o" Nitrile insulation 12mm , cabling from indoor to outdoor unit, heavy gauge PVC drain piping with insulation as per site requirement. The copper piping, drains piping and electrical cabling should be fixed with clamps and no loose piping/cabling is allowed. The rates inclusive of all repairs of civil and carpentry work The out door unit should be anti-rust powder coated. The cost | 2 | Nos | | |
| | Make of ACs:- Daikin/Hitachi/Voltas/Bluestar/Carrier only | | | | |
| | | | | | |
| 27 | Supply and installation of hard & prime quality of min. 22 G Copper pipe for "Cassette AC Only" with class "o" Nitrile insulation of minimum 12 mm for 3 / 4 ton cassette type air conditioner including interconnection power/ communication cable between indoor and outdoor unit as per site requirement.(If required additionally, payment will made as per actual installtion.) The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:- Superton/Aflex/Armacecl/Kflex . Make of cable:Finolex/RR | 30 | Mtr | | |
| | | | | | |

| | | | | | |
|--|--|-----|-----|--|--|
| 28 | Supply and installation of soft & prime quality of min. 22 G Copper pipe for " Split AC only" with class "o" Nitrile insulation of minimum 12mm for split air conditioner including interconnection power/ communication cable between indoor and outdoor unit as per site requirement. (If required additionally, payment will made as per actual installtion. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. Make of Insulation:- Superlon/Aflex/Armacell/Kflex Make of cable:- Finolex/RR/Havells | 45 | Mtr | | |
| 29 | Drain Pipe (If Required additional) Applicable to both ACs(Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site requirement with its all accessories like bend, solution etc as per site condition. The rate inclusive of all chisel work, plastering, finishing, painting & all civil related work pertaing to mentioned work. (If required additionally, payment will made as per actual installtion.) Make:- Kasta/supreme | 100 | Mtr | | |
| 30 | Providing & fixing of 4 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 1Tr /1.5Tr Split AC & 1.5 Tr Cassette AC) Make:-Microtek, V-Gards (Voltage Range 150- 280 Volts) | 1 | Nos | | |
| 31 | Providing & fixing of 5 KVA Voltage stabilizer with time delay option including all accessories with installation at site (For 2Tn Split AC & 2 Tn Cassette AC) Make:- Microtek, V-Gards. (Voltage Range 150- 280 Volts) | 2 | Nos | | |
| Sub Total : Part B (AIR CONDITIONING WORKS) | | | | | |

GRAND TOTAL (A+B)

Vendor's Sign