

PRICE BID FOR RBO DIBRUGARH AT NEW PREMISE					
INTERIOR & FURNITURE WORKS					
SN	DESCRIPTION OF ITEMS	UNIT	QNTY.	RATE (Rs.)	AMOUNT (Rs.)
1	FALSE CEILING WORK				
1.1	Plain Gypsum Ceiling: Providing and fixing suspended 12mm thick Gypsum board false ceiling with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design, pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank. Rate shall include dismantling of existing false ceiling if any. The ceiling material should be water proof with respect to any kind of water droplets from AC drainage pipe at 2nd and 3rd floors and rain water at 4th floor. Make: Gyproc/ Amrstrong or equivalent	SQM	377.00		
1.2	Grid Ceiling: Providing and fixing suspended false ceiling with 600x600 mm size & 12mm thick mineral fiber ceiling tiles of Amrstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank. The ceiling material should be water proof with respect to any kind of water droplets from AC drainage pipe at 2nd and 3rd floors and rain water at 4th floor. Make: Gyproc/ Amrstrong or equivalent	SQM	566.00		
2	PARTITIONS				
2.1	Full Ht. Solid Partitions with both side 0.8 mm thick Laminate finish (FHSP - BSL): Fabricating and fixing full ht. solid partition made of 9mm ply of approved brand in both side and to be finished with 0.8 mm thick laminate of approved brand, colour and shade over 50mm X 50mm aluminium section framework at spacing not exceeding 600mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall include dismantling of existing partition and etching of glasses as per Banks requirements. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	SQM	118.00		
2.2	Full Ht. Semi-Glazed Partitions with both side 0.8 mm thick Laminate finish (FHSGP - BSL): Fabricating and fixing full ht. semi glazed partition made of 9mm ply of approved brand in both side and to be finished with 0.8 mm thick laminate of approved brand, colour and shade over 50mm X 50mm aluminium section framework at spacing not exceeding 600mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900mm to 2100mm height shall have 6mm thick plain float glass fixed with 10mm thick teak wood moulding duly polished. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall include dismantling of existing partition and etching of glasses as per Banks requirements. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	SQM	77.00		
2.3	Full Ht. Semi-Glazed Partitions with one side 4 mm thick Veneer and one side 0.8 mm thick Laminate finish (FHSGP - OSV OSL): (Conference Room) Fabricating and fixing full ht. semi glazed partition made of 9mm ply of approved brand in both side and to be finished with 0.8 mm thick laminate of approved brand, colour and shade over 50mm X 50mm aluminium section framework at spacing not exceeding 600mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900mm to 2100mm height shall have 6mm thick plain float glass fixed with 10mm thick teak wood moulding duly polished. All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall include dismantling of existing partition and etching of glasses as per Banks requirements. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	SQM	37.00		
2.4	Low Ht. Semi-Glazed Partitions with both side 0.8 mm thick Laminate (LHSGP- BSL): Providing and fixing low ht. semi glazed partitions made of 9 mm ply of approved brand in both side to be finished with 0.8 mm thick laminate of approved brand, colour, shade over 50mm X 50mm aluminium section framework of approved brand spacing not exceeding 600mm both ways. Top portion at 900mm to 1200mm height shall have 12 mm thick plain float glass fixed with 10mm thick teak wood moulding duly polished (Total Height of 4.0 Feet). All expose edge shall be covered with teak wood lipping/bidding with polishing complete in all respect. All exposed edge shall be covered with teakwood lipping of required size with polishing complete in all respect. Rate shall include making provision for fixing of countertop 12 mm glass with on its edges with necessary fixing arrangement as directed. Rates shall include dismantling of existing partitions and etching of glasses as required at site. Rate shall include dismantling of existing partitions and etching of glasses as per Banks requirements. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.	SQM	140.00		
2.5	12 MM thick Toughened Glass Partition with patch fitting: (RM chamber) Providing and fixing 12mm thick toughened glass partition with polished edges on patch fittings and other accessories. Rate shall include etching of glass as per design provided by Bank.	SQM	28.00		

3	PANELLING				
3.1	<p>Wall & Column Panelling with 12 mm thk Ply with Laminate finish: Fabricating and fixing wall/column paneling, with 12 mm thick ply finished with not less than 0.8 mm thick laminate of approved shade & brand over 25 mm x 35 mm (thickness not less than 1.5 mm) aluminium section framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout & elevation policy. Rate shall includes dismantling of existing paneling if any.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	SQM	167.00		
3.2	<p>Wall and Column Panelling with 12 mm thk Ply with 4mm thk Veneer with PU polish finish: (RM Chamber & Conference Room) Fabricating and fixing wall/Column paneling of CM Chamber, with 12 mm thick ply finished with 4 mm thick veneer of approved shade & brand over 25 mm x 35 mm (thickness not less than 1.5 mm) aluminium section framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface. Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout & elevation policy. Rate shall includes dismantling of existing paneling if any.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	SQM	87.00		
4	DOORS				
4.1	<p>12 MM Toughened Glass Door: (RM Chamber) Providing and Fixing full glass door made out of 12 mm thick toughened glass, in patch fittings, and with heavy duty floor spring with SS cover plate. The doors to be provided with locking arrangement in patch fittings as well as ss 25 mm dia, and approx. 600 mm long approved model handles. Rate shall includes etching of glass area as required by Bank.</p>	SQM	2.00		
4.2	<p>Solid/ Semi Glazed Door with both side 0.8 mm thick Laminate: Providing and fixing Semi glazed doors shutter made up of 38 mm thick block board of approved brand and quality, finished both side with not less than 0.8 mm thick laminate on one side and 4 mm thick veneer on other side of approved brand, colour and shade. Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make Sainigobin/Modigurd) fixed with 10 mm thick teak wood bidding duly polished N C lacquer as per design and direction by bank. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass area as required by Bank.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	SQM	55.00		
4.3	<p>Solid/ Semi Glazed Door with one side 0.8 mm thick Laminate one side 4 mm thick Veneer): (Conference room) Providing and fixing Solid doors shutter made up of 38 mm thick block board of approved brand and quality, finished one side with 0.8 mm thick laminate and other side with 4 mm thick veneer of approved brand, colour and shade. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	SQM	5.00		
5	BUILT IN FURNITURE				
5.1	<p>Low Ht Storage unit (Laminate finish): Providing and fixing storage units of size 450 mm x 750 mm, made up of 19 mm thick block board of approved brand on top & vertical support and finished with 0.8 mm thick laminate of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19mm thick plywood and finished in 1 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, locks, handles etc. of Godrej or equivalent.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	RM	79.00		
5.2	<p>Low Ht Storage unit (Veneer finish): (RM Chamber) Providing, fabricating and fixing (600 mm deep) low height 750mm with 4mm thk. Veneer finish (on external face) storage cabinet including feature cabinet as per drawing consisting of 19mm block board- IS303/MR Grade (Gattani, Archidply, Century), at top, bottom, sides, horizontal & vertical partition, drawers and shutters and 6mm thick ply backing and with 0.7 mm thk. laminate finish on all inside faces .Rate to include cost towards PU Polish, fixing of stainless steel hinges, tower bolts, locks etc. complete in all respects .</p> <p>Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	RM	4.00		

6	TABLES				
6.1	<p>RM Table: Supply and installing Table of size - 2100 mm x 2100 mm x 900 mm including cost of side credenza (1200mm x 600mm x 750 mm) made up of 19mm thick Block board all around, finished with 4 mm thick teak Veneer of colour, shade & brand as approved. The table cost to include (pedestal), three drawers of 450 mm wide made with 6mm/12mm ply on telescopic slider and a keyboard tray 250mm wide, CPU stand, foot rest as per design and direction by bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/ bidding of required size stained to match the desk and melamine finished. All inner surface to be finished with mat finish 0.8 mm thick laminets of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved brand. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in veneer & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	EACH	1.00		
6.2	<p>Officer Tables: Supplying and installing Officers & Staff Tables of Overall size - 1650 mm X 1800 mm x 750 mm including cost of side credenza (1050 mm x 450 mm x 750 mm) made up of 19 mm thick block board of approved brand all around and finished with 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include (pedestal) three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide with CPU stand and foot rest as per design and direction by Bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks , handles etc. of Godrej or approved make. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	EACH	28.00		
6.3	<p>Staff Tables: Supplying and installing Officers & Staff Tables of Overall size - 1500 mm X 1800 mm x 750 mm including cost of side credenza (1050 mm x 450 mm x 750 mm) made up of 19 mm thick block board of approved brand all around and finished with 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include (pedestal) three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide with CPU stand and foot rest as per design and direction by Bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks , handles etc. of Godrej or approved make. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	EACH	18.00		
6.4	<p>Running Table: Supplying and installing Runing Table with Top of Width 600 mm and Height 750 mm made up of 19 mm thick block board of approved brand all around and finished with 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include a keyboard tray 250mm wide with CPU stand and foot rest as per design and direction by Bank. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks , handles etc. of Godrej or approved make. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8 mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Ply/Block Board Make: MR Grade of Century/ Green /Archidply /Gattani /kitply or equivalent. Laminate/veneer Make: Greenlam /Centurylam /Merinolam /Archidlam or equivalent.</p>	RM	6.00		
7	MISCELLNEOUS ITEMS				
7.1	Providing & fixing in place 100 mm Vertical Blinds with Scotch Guard of approved make, quality and colour shade & pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform & adequate.	SQM	52.00		
TOTAL COST (Excluding GST)					