

**PRICE BID FORM**

**CIVIL/STRUCTURAL WORKS INCLUDING PAINTING , RENOVATION OF TOILETS , CANTEEN, FLOORING ETC.) AT  
SBI BERACHAMPA BRANCH (08855) UNDER RBO-4 OF AO BIDHANNAGAR**

<b>1</b>	<b>Dsimantling of brickworks as per requirment</b>				
<b>a</b>	10 " thick brickwall	<b>CUM</b>	2		
<b>b</b>	5" thick brickwall	<b>Square Metre</b>	5		
<b>2</b>	<b>Providing and erecting Brickwork: :</b>				
	The brickwork shall be executed with 1st class bricks only, unless mentioned otherwise. All bricks are to be made saturated with surface dry by dipping into potable water for at least 24 hours before using. Also, scaffolding and staging are to be done wherever necessary. The work is to include all necessary materials, accessories, labour, tools & tackles. All materials should be approved by the Bank. Executed volume of brickwork is to be measured for finished work. The job is to be done with cement-sand mortar as below –				
<b>a</b>	<b>Providing &amp; erecting of 10 " thick brickwork (Blocking of windows)</b>	<b>CUM</b>	3.5		
<b>b</b>	<b>Providing &amp; erecting of 10 " thick brickwork (Record room wall)</b>	<b>Square Metre</b>	22.5		
<b>3</b>	<b>Providing and applying Plastering Work:</b>				
	Plastering shall be applied to walls, ceiling, columns, beams, etc. or any other surface as directed and as per design. The job is to be finished with rounding off or chamfering corners as directed.  The work includes raking out joints along with throating, nosing and drip course as required.  Also, scaffolding and staging are to be done wherever necessary. The work is to include all necessary materials, accessories, labour, tools & tackles. All materials should be approved by the Bank. Executed plastered area is to be measured for finished work. The job is to be done with cement-sand mortar as below –	<b>Square Metre</b>	68.50		
<b>b</b>	Supplying & laying true to line & level <b>Double charged Vitrified Tiles (At Branch Premises only)</b> at BM & UPS room area ( Bi-colour Patten of approved brand ( e.g. Jhonson/Kajaria/Nitco/Somany/ Equivalent) of size 600 mm x 600 mm x 10 mm min. thick) in floors, skirting, etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry using back side of tiles using cement @ 2.91 KG. /M2 or using polymerised adhesive (6 mm thick layer) applied directly over finished laid after application slurry using 1.75 KG of cement per Sqm. below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of works coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specifications and direction. (White cement, syntethic adhesive and grout materials as required , are to be supplied by the contractor.If necessary then the existing floor shall be made in line and level with PCC (1:2:4)with required thickness as per site condition to fix the tile.The rate shall include entire operations involved for this work. The MRP of the tile shall be in the range	<b>Square Metre</b>	271.00		
<b>5</b>	<b>Providing &amp; fixing of designed Ceramic wall tiles at Kitchen room over kitchen slab upto the hight of 7'-0". Tiles colour to be approved by EIC before fixing</b>	<b>Sq Mtr</b>	8.21		
<b>6</b>	<b>P &amp; F Stainless steel sink at kitchen</b>	<b>No</b>	1.00		
<b>7</b>	<b>Internal plumbing works :</b> Supplying & Fixing of PVC or CPVC pipes as per requirement for the connection of <b>Water Supply lines (CPVC) , Waste lines (UPVC)</b> of Kitchen - Canteen etc, fittings with accessories including plumbing fixture, soil pipes, fitting with accessories as per direction.	<b>P.S</b>	<b>1</b>	<b>2000</b>	<b>2000.00</b>

8	Providing and fixing Heavy grade <b>Bib cocks/ stop cocks</b> of spring loaded self closing type conforming to IS: 781 including making connections, cutting walls and making good the same etc. all complete. a) 15mm dia CP Brass Bib cock. b)15mm dia CP Brass Stop cock.	nos	3.00		
9	<b>Construction of Kitchen Slab</b> with Granite Work Counter Top Grade : Providing and fixing 18mm thick polished black/Green color and shade of granite molding at edges in kitchen plat form, vertical faces, main entrance door sills etc and other similar locations like front entrance door including raising the platform by about 100mm using cement concrete of 1:2:4 and making recess for floor spring of door. The width of the granite slab is as per site condition. This also includes preparing the base surface, applying neat cement slurry @ 2.75 kg. of cement per sq. mtr. of area to receive the mortar bed, jointing each slab with neat cement paste/ grout with white cement mixed with pigment (conforming, to IS:2114, Table-1) to match the colour of the granite to IS:2114, Table-1) to match the colour of the granite ( Black Galaxy Granite tiles with base price of Rs.200/- per Sqft. inclusive of tax ). Granite Sample has to be approved before starting of the work.	Sq mt	5.5		
10	<b>Wash Basin:</b> P/F/F in Position Vitreous White China Round/oval Counter-top Wash-basin of minimum 470mm dia. with 32mm dia. CP waste pipe with standard patten , C.P Bottle Trap and 15 mm dia 450mm long PVC Connector with C.I. Bracket including painting of fittings & brackets , cutting & making good to the walls wherever required. Rate includes all items mentioned here to compete in all respect including taking out the existing wash basin with connecting pipe line & mending the damages good. (Make: Parryware/ Hindware/ Cera Model to be approved before installing )	nos	1.00		
11	Providing and applying <b>Wall Putty</b> on old interior surfaces at any floor level as directed: Removal of loose scales, blisters, etc. from old plastered surfaces of walls, ceiling, columns, beams, etc. is to be done at first. The job includes scraping, rubbing and chipping the surface by means of appropriate tools & tackles to receive putty. The work is to be finished with White Cement-based Putty up to approximately 1.5 mm thickness, properly levelled as directed. Also, scaffolding and staging are to be done wherever necessary. The work is to include all necessary materials, accessories, labour, tools & tackles. All materials should be approved by the Bank. Executed rendered area is to be measured for finished work	<b>Square Metre</b>	410		
12	<b>Applying Synthetic enamel paint with primer</b> Area of Applying paint: Rolling Shutter of Banks Main Entrance rolling shutter & coll. Gate, Safe room Shutter & coll. Gate, Inside walls & ceiling of Kitchen room.	<b>Square Metre</b>	85		
13	<b>Applying Acrylic Emulsion Paints on plastered surface at any floor level as directed:</b> Firstly, the surface shall be scraped thoroughly and prepared to receive fresh paints by means of appropriate tools & tackles. Also, sand papering in intermediate coats for smoothening and cleaning the surface thoroughly shall be done prior to painting. White Cement-based Putty is to be applied up to approximately 1.5 mm thickness, if required. Two coats of Acrylic Primer of approved make as required are to be applied on the prepared surface. Then, two coats of best quality Acrylic Emulsion Paint of approved shade & make are to be applied over the primer coats. Protective and decorative approved grade paint is to be applied, and duly completed up to smooth finishing. The work is to be done as per manufacturer's specification. Also, scaffolding and staging are to be done wherever necessary. The work is to include all necessary materials, accessories, labour, tools & tackles.				

	All materials should be approved by the Bank. Painted area is to be measured for finished work.	<b>Square Metre</b>	512.00		
<b>26</b>	<b>Site developments</b>	<b>P.S</b>	1		
	<b>Total :</b>			<b>Rs</b>	
<b>(IN WORDS:</b>					

*Note : Above values are excluding GST*