

# PRICE BID

## BOQ OF REFURNISHING WORK FOR CSRM DEPTT. ON 10th FLOOR, SBI, LAL DARWAJA( OLD LHO BUILDING), AHMEDABAD.

ESTIMATED BILL OF QUANTITIES					
Sr. No.	Description	Quantity	Unit	Rate	Amount
<b>Note :</b> Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage & removing of all existing furniture items and relocating the same as per instruction by bank etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills					
	FURNISHING				
<b>1</b>	<b>TABLES</b>				
<b>FINISHING DETAILS IN NUTSHELL:</b>					
	<b>1) Table Top :</b> 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished				
	<b>2) Front Apron &amp; Sides:</b> 1.0 mm thick Dark Laminate				
	<b>3) Facing of Drawers:</b> 1.00 mm thick laminate finish				
	The W.S. should have Ready Made Foot Rest. High impact polysterene with crome plated metal structure of approved make.				
	There should be provision for cable manager(Metal Cable Manager) system with necessary cutouts in top surface				
	C.P.U. trolly with castors/roller supports/ Nylon castors.				
	Key board tray with mouse pad made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete				
	Heavy duty <u>telescopic full extension</u> sliding channel of approved make shall be used in all drawers.				
1A	<b>TABLE SIZE: 7'-0" X 3-0" X2'-6" HT. with Laninate finish on Table Top , sides and all other visible surfaces etc complete as follows</b>	1.00	NO		
	Supplying and installation of Table as per the following description : Size 7'-0" X 3-0" X2'-6". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Drawers of size of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Ready made metal Key board with mouse pad of approved make shall be provided. Exposed surfaces of darwers shall have laminate. All internal surface will have 0.60 mm thick balacing laminate				
	<b>Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing</b>				
	<b>Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.</b>				

ESTIMATED BILL OF QUANTITIES					
	Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laquer polished etc complete as directed.				
	Table shall have stand for keeping CPU and metallic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges & corners				
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	<b>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete.</b>				
	All the surface without laminate / balancing laminate shall be lacquered polished of approved shade				
	<b>As per drawing and instruction of Architect/Bank work to be Completed (FOR DETAILS REFER DRG. NO- )</b>				
2	<b>SIDE CREDENZA (SIDE TABLE)</b>				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				
	2) Front Apron & Sides: Frosty White Laminate				
	<b>Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 1.00 mm thick Laminate finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. ( For BM &amp; Officer's) Rate for length Less then 3'-3"</b>	0.81	SQ.MT		
	Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				

ESTIMATED BILL OF QUANTITIES					
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate ( FOR DETAILS REFER DRG. NO- )				
3	<b>FULL HEIGHT PARTITION WORK</b>				
	<b>REMOVING, RECONDITIONING EXISTING PARTITION AND PROVIDING AND FIXING NEW WOODEN PARTITION INCLUDING DOOR</b>	120.00	SQMT		
	Removing ,reconditioning existing partition and providing and fixing new partly glazed both side laminated wooden partition including door as per given layout. Item includes changing of 1mm thick laminate on both sides of existing 1.22 mt. height partition and wooden door also.item also includes erecting new partly glazed wooden partition above 1.22mt. height and upto existing false ceiling with 1.5mm thick aluminium sections of required size for matching thickness of existing partition in a maximum grid of 600mmx600mm, 6/8mm thick plywood and 1.00m thick laminate on both sides and 8mm thick glass. Item also includes providing and fixing new and reconditioning of existing partly glazed wooden door with matching laminate on both sides providing new lock and required necessary all accessories matching beading patties,polishing, cleaning etc. complete. (Existing partition and new partition including door, the combined furnished visible actual area as per layout will be considered for payment) <b>(Note: Contractor should visit the site and check maximum existing partition area to be utilised and the rest area will be provided for neew partition as per given layout).</b>				
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.				
	<b>FALSE CEILING WORK</b>				
4	<b>REPAIRING OF EXISTING FALSE CEILING</b>	30.00	SMT		
	reconditioning ,providing and fixing required gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of <b>Gypsteel ULTRA ( Gypsteel Ultra shall be used)</b> supporting system in line and level. Finishing the surface and <b>applying 3 coats of Plastic emulsion paint</b> as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	<b>After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.</b>				
	<b>Note : (1) Rate includes dismantalling of existing GYPSUM/ AMF/ POP false ceiling including stacking of servicable materials &amp; disposal of unserviable materials &amp; making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment.</b>				

ESTIMATED BILL OF QUANTITIES					
5	Reconditioning of existing grid frames, levelling and providing and Fixing of Armstrong Mineral Fibre Accoustical FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid in the existing structure of the ceiling.	20.00	Nos.		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. Rate includes removing of existing Mineral fibre grid tiles				
6	Providing and fixing 1.0 mm thick laminate on any existing laminate surfaces of Tables, Side Tables, , cupboards,panelling etc.Rate Including removing existing laminate by Hot Iron. and finishing surface etc complete. <b>Only laminate finished surface area shall be measured for payment</b>	50.00	SMT		
7	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)	25	SMT		
	Providing and applying (with rollers only) Acrylic emulsion paint of required shed and approved make on new/old work in two or more coats to give an even shed including the preparation of surface for painting, applying FULL primer and putty, at all heights complete as per manufacturer's specification and as directed.				
8	P/A SYNTHETIC ENAMEL PAINT	10	SMT		
	Providing and applying synthetic enamel paint, at all heights of required shade and approved make on old work including the scrapping/cleaning and preparation of surfaces for painting, applying primer and putty, with two or more coats of approved first quality enamel.				
9	Providing and fixing door closer of approved make.	7	NO.		
	<b>TOTAL COST</b>				
<b>Note:</b>					
[a]	In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabelling and No extra amount shall be paid for this.				
[b]	All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balacing laminate of aproved make & shade in the all S.W Counters/Tables/ Credenza,Storage Cup Board etc.				