

INDICATIVE PRICE BID FOR INTERIOR FURNISHING WORKS AT SBI RACC NEDUMANGAD AT SIXTH FLOOR, KSHB BUILDING.

| Sl.No | DESCRIPTION OF WORK | Qty | Unit | Rate | Amount |
|-------|--|-----|------|------|--------|
| 1 | <p>LOW HEIGHT PARTITION FOR SINGLE WINDOW SYSTEM:Providing and fixing of Low height partitions for Single window system of 1350 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Clear float glass of 12 mm thick of approved band with etching shall be fixed with SS D Brackets for a height of 500 mm above the solid partition. Partition on rear similar to side partition, but solid partition. One door shutter for each cabin for 680 mm width and 1350 mm height, similar to door shutter item, fitted with Godrej night latch at 500 mm from floor level, openable inside the cubicle shall be provided.</p> | 17 | Sq.M | | |
| 2 | <p>Custom Made Full Height Solid Partition: - Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beadings. Measurement for the partition area shall be considered from floor level to false</p> | 30 | Sq.M | | |
| 3 | <p>Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.</p> | 5 | Sq.M | | |

| | | | | | |
|---|---|----|------|--|--|
| 4 | Gypsum Board False Ceiling Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete. | 77 | Sq.M | | |
| 5 | Providing and fixing Officer's table of size 1500 x 750 X 750 mm high to detail as shown in drg. as per specification in item no.11 above. 12 mm thick glass with polished edges to be provided on table | 8 | No. | | |
| 6 | Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 110 x 45 cm as per specification in item no.12 | 8 | No. | | |
| 7 | Low Level Storage :-Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm 1200 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exp[osed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area. | 15 | Sq.M | | |
| 8 | Providing and fixing wall mounted writing desk of 1200 x 350 mm in 19 mm plywood with 1 mm laminate on all exposed surfaces. Top portion is to be provided with 12 mm clear glass with polished edges, with shelves to keep slip books including frosting of approved design and exposed edges to be fixed with TW beeding with melamine polish. A provision to be made for keeping Banks printed Broachers for public etc. complete. | 1 | No. | | |
| 9 | Providing and Fixing Roller Blinds of approved orequivalent make and colour. | 15 | Sq.M | | |

| | | | | | |
|----|--|-----|------|--|--|
| 10 | Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface. | 45 | Sq.M | | |
| 11 | Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade over a coat of putty including cleaning the surface. | 195 | Sq.M | | |
| 12 | Providing and laying 20 cm thick solid cement concrete block masonry for UPS room in CM 1:6 (1 Cement, 6 Sand) including all labour, conveyance, lead, lift, curing etc. complete. | 6 | CuM | | |
| 13 | Plastering with CM 1:4, 12mm thick (1 cement & 4 sand) 12mm thick one coat floated hard and traveled smooth to walls including all staging work watering, curing etc complete. | 60 | SqM | | |
| 14 | Providing and laying Double charged VITRIFIED FLOOR TILES of size 600x600mm and thickness around 12mm without warpage, of make Kajaria/Johnson/RAK or equivalent with water absorption less than 0.08 % and conforming to I.S. 15622 and colour laid on 20 mm thick cement mortar 1:5 (1 cement: 5 coarse sand), for inside flooring including grouting the joints with white cement and matching pigment etc. complete. Minimum Base rate of tiles should be Rs 650/sqm. | 70 | Sqm | | |
| | TOTAL | | | | |
| | GST | | | | |
| | GRAND TOTAL | | | | |