

SCHEDULE OF QUANTITIES FOR REPAIR WORKS FOR STATE BANK OF INDIA, PRABHAT CROSS HONNAVAR

SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
BRANCH - INTERIOR WORKS					
A					
1	PARTITION				
1.1	<p>FULL HEIGHT PARTITIONS - PARTLY GLAZED: Providing and fixing metal stud dry wall partition with following specifications: Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings. 12mm Exterior Grade MDF (EG-MDF) Board fixed on both sides with 25mm dry wall screws for the entire height of the partition. Partition fixed with 1.0mm laminate sheet on both sides as per the following : Skirting level upto 100 mm from FFL to have 1.0mm laminate of dark blue colour. From 100mm to 300mm level to have 1mm Laminate (aqua blue color) From 300mm level to 1070mm level to have 1mm thick Laminate (white color) From 1070mm level to 2135mm level to have 8mm clear float glass fixed with with 85mm x 15mm around jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete. The glass sizes subject to design drawing etc. From 2250mm level to 2350mm level 1mm thick Laminate (aqua blue color) on both sides as shown in drawing. From 2135mm level to 2235mm level 1mm Laminate (aqua blue color) on both sides as shown in drawing. Partition above 2235mm level to have 1mm Laminate (white color) as shown in drawing. All beech wood members to have minimum two coats of LOW VOC or NO VOC white duco paint finish. All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.</p>	22.00	SQM		
1.3	<p>HALF HEIGHT PARTITIONS This item <u>includes partitions for SWO counters, officer cubicles etc as per the layout plan.</u> Height of the partitions shall be as mentioned in the drawings. Same as full height partition Solid above, but for height of 1220mm from finished floor level, to a neat finish as per drawings and directions etc., complete and including the following: Laminate capping of 75mm on top, 50mm bands of 1mm Laminate on both sides of the partitions horizontally and vertically upto skirting as per drawings and directions etc., complete. From desired(as per Engineer's advise) level to have 8mm clear float glass fixed with with 85mm x 15mm around jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete. The glass sizes subject to design drawing etc. Partition fixed with 1.0mm laminate sheet on both sides as per the following : Skirting level upto 100mm from FFL. From 100mm to 300mm level to have 1mm Laminate (aqua blue color). From 300mm level to 1070mm level to have 1mm Laminate (white color) .From 1070mm level to 1170mm level 1mm Laminate (aqua blue color) From 1170mm level to 1220mm level to have 1mm thick laminate on both sides as shown in drawing.</p>	7.50	SQM		
1.4	DOORS IN PARTITIONS				
1.4.1	<p>32MM DOORS IN PARTITIONS - with glass panel: Providing and fixing 32mm thick solid core flush shutter with 85mm x 35mm beech wood frame with rebate around the jamb and shutter fixed with 1mm Laminate as specified on both sides with glass panel of 8mm clear float glass fixed with 19 x 19mm beading on both sides and glass pasted with 3M privacy film as per design. The rate to include necessary hardware viz., door stopper, door buffer, pair of "H" type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC white duco paint finish for all beech wood members, etc., complete as directed.</p>	4.00	SQM		
1.4.2	<p>WICKET GATE - for SWO Counters Wicket gate specified below may also be used with other low height partitions elsewhere in the branch if required, with height of wicket gate modified suitably. Providing wicket gate made of 32mm solid flush door with around BW/PVC edge lipping and height to match low height partitions. Wicket gate shall be fixed to partition with 85mm x 35mm beech wood frame on sides with SS hinges as required with handles, stoppers, self lock etc complete. Wicket gate shall have self lock from inside fixed at lower height as per instructions and Bank requirement.</p>	1.86	SQM		

SCHEDULE OF QUANTITIES FOR REPAIR WORKS FOR STATE BANK OF INDIA, PRABHAT CROSS HONNAVAR

SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
2	TABLES / COUNTERS				
2.1	OTHER OFFICER'S EXECUTIVE TABLES:	2.00	Each		
	Table : 1500 - 1650mm x 760mm x 760mm				
	Side Runner : 915 - 1050mm x 450mm x 760mm				
	Providing, making and placing in position Executive Table and Side Table with following specifications.				
	The "" L "" shaped table top on the back side along with side table to have 49mm edge allround, which is to be achieved by adding a 75mm piece of 18mm EG-MDF to the table top from bottom.				
	All other members to be with 18mm EG-MDF and all exposed faces of the table to have 1.0mm laminate as specified.				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood lipping /PVC edge banding.				
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.				
	One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF. The unit to have 3 equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1 no internal shelf made with 18mm EG-MDF and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
2.2	SINGLE WINDOW COUNTERS:	3.00	Each.		
	Counter : 1500-1650mm x 900-975mm x 760mm				
	Side Runner : 1050 - 1220mm x 450mm x 760mm.				
	Providing, making and placing in position Single Window Counters along with necessary Half height partitions above (The partitions will be measured and paid as per Half Height Partitions) with following specifications and as per dimensions specified.				
	Table top of main table and side table to be made in 25mm block board with 1mm thick laminate and double thickness at edges allround. The laminate to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.				
	All other members to be with 18mm EG-MDF / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 1mm Laminate as specified in the drawing to be used.				
	Front of SWO Counter to have about 100mm high skirting made of 12mm EG-MDF board fixed at floor level and finished with 1.0mm laminate of dark blue colour				
	All the edges of 18mm EG-MDF to have 20mm x 6mm beech wood /PVC edge banding.				
	One readymade CPU mobile pedestal.				
	One Molded Key Board Tray with channels etc.,				
	One Three Drawer Unit made with 18mm EG-MDF and 12mm EG-MDF . The unit to have 3nos equal drawer and each drawer shall be fixed with self locks. Drawers shall have Cash Denomination Partitions made of 12mm ply laminated. The rate to include all necessary hardware viz., telescopic drawer channels, handles, hinges, etc., and 20mm x 6mm beech wood /PVC edge banding etc.,				
	One Side Table with shutters made with 25mm block board top and 18mm EG-MDF for all other members with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate				
	All the unexposed faces to have 0.8mm Laminate.				
	Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	All wooden members to have minimum two coats of NO VOC or LOW VOC white duco paint finish.				
	Each Single Window Counter to have half height partitions on either sides as per item 1.2 above.				
	Each Single Window Counter to have provision for 12mm thick clear float glass in the front and sides as per relevant item measured separately.				
	The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				

SCHEDULE OF QUANTITIES FOR REPAIR WORKS FOR STATE BANK OF INDIA, PRABHAT CROSS HONNAVAR

SL NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
3	<p>12MM TOUGHENED GLASS FOR FRONT PORTION OF SINGLE WINDOW COUNTERS (TRANSACTION SIDE):(incl 2 nos glass) Providing, making and fixing in position 12mm thick clear float glass in the front side and shall be in 2 nos of separate sizes. Lower part shall be fixed with a glass panel of size 1500-1650 x 380mm with a central cut out of 200mm x 150mm. Uppper part shall be fixed with a glass panel of size 1500-1650 x 450mm. A gap of 50mm shall be maintained between the two glass panels. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " / "L" brackets as required. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.</p>	2.00	Each		
4	<p>12MM TOUGHENED GLASS ON LOW HEIGHT PARTITIONS BETWEEN SINGLE WINDOW COUNTERS: Providing, making and fixing in position 12mm thick toughened clear float glass in sizes as per design with cut out of 200mm x 150mm at position to match Voucher tray. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete. Glass size shall be as per length of low height partiton after leaving about 300mm solid portion at both ends Item includes providing Voucher tray of size 200 x 200, made of 19mm BB-laminated with BW/PVC edge lipping beading etc and fixed onto the low partition with all hardware etc complete</p>	2.20	SQM		
5	<p>All existing loose furnitures, Partitions to be purchased by the contractor on lumpsum basis inclusive of all cost for dismantling and removing the same from the site to a distant location of their choice.</p>	-1.00	LS		
TOTAL FOR BRANCH (excluding GST)					
SIGNATURE OF CONTRACTOR					