

PRICE BID

ESTIMATE FOR INTERIOR REPAIRS & RENOVATION WORKS ON 1ST FLOOR, OFFICERS' ASSOCIATION
IN SBI ADMIN. OFFICE AHMEDABAD AT OLD LHO BUILDING, BHADRA, LAL DARWAZA AHMEDABAD.

<p>Note : Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage & removing of all existing furniture items and relocating the same as per instruction by bank etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills</p>					
SN	Description	Quantity	Unit	Rate	Amount
1	TABLE SIZE: 5'-0" X 2'-6" X 2'-6" HT.	2	Nos.		
	Supplying and installation of Table as per the following description: Size 5'0"x 2'-6". Table top shall be made from 18 mm thick commercial plywood with equal sized 10mm thick back painted toughened glass with polished edges hole cut for cable manager. with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Computer Key board of metal of approved make shall be provided. Exposed surfaces of the CABINET shall have laminate, Foot rest of 1 1/2" x 3" T.W members shall be provided. All internal surface will have 0.80 mm thick balacing laminate				
	Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing				
	Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.				
	Drawer Facia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer polished etc complete as directed.				
	Readymade CPU trolley with caster and metalic cable Manager shall be provided in table. All exposed edges of teak wood shall have polished with smooth edges & corners				
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate of approved shade. Etc. complete.				
	As per drawing and instruction of Architect/Bank work to be Completed				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 18 mm thick commercial plywood with equal sized 10mm thick back painted toughened glass				
	2) Front Apron & Sides : 1.0 mm thick Dark Laminate				
	3) Facing of Drawers : 1.0 mm thick Dark Laminate				
	4) All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate				

FALSE CEILING WORK					
2	REPAIRS & LEVELLING OF EXISTING GYPSUM BOARD FALSE CEILING	125.00	SMT		
	Repairs and levelling of existing Gypsum Board false ceiling and Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level wherever required. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. (1) Rate includes dismantalling of existing GYPSUM/ AMF/ POP false ceiling including stacking of servicable materials & disposal of unservicable materials wherever required & making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMT and paid in SqM (3) Only finished visible surface area shall be measured for payment.				
3	Repairs and levelling of existing grid ceiling and Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid wherever required Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications Rate includes dismantalling of existing Mineral fibre ceiling.	100.00	SMT		
4	Removing of existing laminate and refixing of new laminate as per selection for tables, partitions, Storage cabinate etc as directed	100.00	SMT		
5	Plastic paint on walls	130.00	SMT		
6	Oil painting on windows with Grills	40.00	SMT		
7	Polishing of existing tables beading, partition, cupboards etc.	100.00	RMT		
8	Providing and fixing glass louvers for wash room ventilators	6.00	SMT		
9	Dismantling of existing flooring tiles in Wash room and P&F new ceramic /vitrified tiles of approved shade and make	6.00	SMT		
10	Change of sanitary/plumbing fixtures				
a)	Bib Cocks (Jaguar)	2	Nos.		
b)	Presmatic Cock (Jaguar)	2	Nos.		
c)	Pillar Cock (Jaguar)	2	Nos.		
d)	Bottle Trap (Jaguar)	2	Nos.		
e)	Stop Cock for basin & flush tank (Jaguar)	4	Nos.		
f)	Health faucet with bib cock (Jaguar)	2	Nos.		
g)	Flusing Tank (PVC) (cera)	2	Nos.		
h)	Napkin Ring (Jaguar)	2	Nos.		
i)	Soap Dispensar	2	Nos.		
j)	Nani trap	2	Nos.		
TOTAL					