

BOQ for providing for white wash/painting and other miscilinius repair work on 1st and 2nd floor in SBI LHO building, Sector-17, Chandigarh

Sr.No	Description of work	Unit	Qty	Rate	Amount
1	Roller Blinds: Providing & Fixing BLINDS Vista Make Delux Collection (Elemental) Composition : 100% Polyester ., Finished Width : 300 CM., Weight : 200 GSM., Thickness : 0.35 Mm,Colour Fastness to light: 4-5 Grade with supporting framework etc. of Bshade & colour complete in working order as per manufacturers specifications & drawings & directions of the Architect.	Sq.ft	160		
2	Plastic Emulsion Paint: Painting & finishing the walls, including surface preparation primer and putty ,finished with three or more coats of plstic emulsion paint, so as to achieve smooth and even finish complete in desired shades and colours (as approved by Architect/Engineer-In-Charge).	Sq.ft	23800		
3	Enamel paint: Applying two or more coats of synthetic enamel paint on doors, windows, shutters, steel grills, ventilators, etc. including prepration of base coursew as per directions of the Engineer incharge. (Make:- Asian/Nerolac/Burger)	Sq.ft	1300		
4	Finishign wall with water proofing premium exterior paint apex ultima of required shade on old work two or more coats including preparation of base with Birla white putty filling etc complete in all respect as per directions of the Engineer incharge. (Make:- Asian /Nerolac/Burger)	Sq.ft	280		
5	Sprit polish to existng window & doors/Storage cabinets including rubbing, filling sealer and thinner etc. to give smooth finish and base prepartion as per directions of the Engineer incharge. (Make:- Asian/Nerolac/Burger)	Sq.ft	450		
6	Door closer: Doorset/Godrej make , cam action box type door closer with G-N slide channel arm for pull side fixing. Spring size EN 2-4 as per EN 1154 and CE marked. Silver/Antique finish. For maximum door size of 1100mm	Nos	3		
7	Hinges: DORMA BB 4330, 5 Knuckle, 2 Ball bearing butt hinges size 4" x 3" x 3mm, in SS 304 and in SSS finish. Suitable for door weights upto 120kgs. Template Drilled	Nos.	4		
8	Door Handles Antique Finish: Providing and Fixing 10" Brass Handle of Brassage/Doorset make , selected by the Architects, Clients, for:	Nos.	4		
9	Back and side Storage Cabinet in Teak Finish with 12mm glass top: Providing and fixing 2'-0"deep Wooden Platform with Storage below (ht. 2'-9"). The Shutters shall be finished with approved shade teak ply from outside, including all hardware i.e. lock,handle,hinges etc. and the car case shall be finished with liner laminate from inside. The Top shall be finished with Teak ply and 12mm thk. glass on top with champhered edges of approved shade with adhesives., complete with half round moulding from front side.	Rft	18		
10	Repair of existng table (7'-0"x3'-6") including finish with 3-5 mm thick veneer with polish on top of table, changes of channels, locks and drawer etc	1 job	1		
11	Mineral Fibre Grid ceiling with Black Silhouett Grid: Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm Prima Dune / Sand Supreme, RH 99 & micro log edge with black lining, mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Armstrong exposed grid systems. The framework comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules.Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.	Sq.ft	400		
12	Angle Cock: Providing & Fixing Angle Cock of JAQUAR MAKE	Nos	2		
13	Cp Jali: Providing & Fixing CP JALI of JAQUAR MAKE	Nos	3		
14	Paper Towel Dispenser: Providing & Fixing Paper Towel Dispenser of JAQUAR MAKE	Nos	2		
15	Wall Mounter Foam Soap: Providing & Fixing Wall Mounter Foan Soap Dispensor of JAQUAR MAKE	Nos	1		
16	TOWEL RING: (Jaguar - Cat. No. ACN-1121BN Towel Ring Round with Round Flange or equivalent) Towel Ring with Round Flange of Jaguar or approved equivalent make with all necessary materials viz., arrangement for fixing and placing in position etc., complete as directed.	Nos	1		
17	Providing anf fixiing of sun glass film 0.53-0.56 mm thick on existng glass window panel	Sq.ft	200		

18	Vitrified tiles 600x600: Providing and laying and repair 1st quality Vitrified tiles 600 x600 (as specified in Dado (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: on 20 mm thick cement mortar 1:4(1 cement: 4 coarse) sand), including grouting the joints with white cement and matching pigments etc., complete.Approved makes(Nitco, Johnson, RAK, Kajaria (Note: Work Incl. Rate include Dismantling of existing tiles and disposal of material to contractors own dump.)	Sq.ft	300		
19	Providing and fixing 1st quality wall tiles (Size 600x300) conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete including removing the old tile from wall and dumping the malba at MC authorised place with no cost & risk to the Bank (Make- Johnson, Kajaria, Nitco or Bank approved)	Sq.ft	300		
Total value of quoted amount					

GST will be paid extra as applicable

Signature & Seal of contractor