TENDER FOR ELECTRICAL, DATA, TELPHONE & LIGHTING WORKS AT STATE BANK OF INDIA, SME NURPUR, DISTT. KANGRA (HP)

S.No.	Item / Specifications	Qnty.	Units	Rate	Amount
PART-I: C	OMPUTER POINTS & DISTRIBUTION				
1.1	Supply all material, storing, handling, fixing and laying of 3X2.5 Sq. mm. of PVC insulated PVC sheathed armoured cable of 1100 V (IS 1554, Part 1) and fixing of cable on wall with suitable size of clamps /saddles or laid in floor/recess wall including cutting of wall /floor and making good the damages etc for computer points in suitable size of box fabricated with 16 G MS sheet including providing 3 nos 5 amps 3 pin modular sockets controlled by 1 no 5 A modular type switch, indicator and fuse mounted on 3 mm thick ISI marked hylam sheet and painting of box etc complete as required Note; max. two computer points are to be provided on one circuit.	30	each		
1.2	As per item 1 above but with 1 Nos. 15 A 5 pin socket controlled by 1 no 15 A switch and indicator. (RAW POWER)	25	each		
1.2A	As per item 1 above but with 2 Nos. 15 A 5 pin socket controlled by 1 no 15 A switch and indicator. (for data rack-UPS Power)	2	each		
1.3	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.				
a)	2 X 6 sq. mm + 1 X 2.5 sq. mm earth wire	20	Mtr		
1.4	POINT WIRING:				
	Supply & Installation of points for wiring for lights, exhaust fans with 2x1.5 sqmm +1 sqmm copper conductors from switchboard to outlet or fixture/s, including the modular switches & plates, including cost of 2mm thick PVC counduits & ceiling rose, including wiring from DB to switchboard @ 2x2.5sqmm+2.5sqmm				
	Rate includes 3 x 2.5 sq.mm FRLS copper conductor, single core cable in PVC conduit for circuit/sub main wiring along with earth wire)				
a)	1 no. lights controlled by 1 no. switch	61	no.		
b)	2 no. lights controlled by 1 no. switch	25	no.		
c)	5/6 pin 6amp plug point with 6Amp switch	14	no.		
d)	Primary wall fan point including 5Amp socket, controlled by 5Amp switch	15	no.		
e)	1 no. 15Amp 5 pin socket controlled by 1no. 15Amp switch for Record/Cash/Gold Safe Room, including 3Pin/15Amp top etc., complete as required.	4	no.		
	Note: Lights/fans points to be calculated by numbers of lights and no extra cost shall be paid for dummy switch)				
1.5	Supply installation testing and commissioning of 3 pin 20/25 A 3 pin metal clad industrial type plug and socket arrangement with plug top, cap and chain controlled by 1 no 20/25A SP MCB. (for air -conditioning points - 1.5 TR Acs) Note;	3	each		

	Independent circuit for AC point is to be provided starting from			
	distribution system.			
1.6	Supply installation testing and commissioning of 3 pin 32 A 3 pin metal clad industrial type plug and socket arrangement with plug top, cap and chain controlled by 1 no 32A SP MCB. (for air -conditioning points - 2.0 TR Acs) Note; Independent circuit for AC point is to be provided starting from distribution	6	each	
1.7	system. DISTRIBUTION BOARDS			
1.7				
	Supply, installation testing and commissioning of factory fabricated distribution board rust inhibited powder coated sheet fabricated comprising of incoming and outgoing isolator & MCBs neutral link or neutral bus, top and bottom detachable entry earthing bolts interconnection and grouting bolts etc complete as required as per details below			
a)	8-way SPN MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 63 A DP Isolator and 6 Nos. 6/10 A MCBS etc complete as required.	2	no.	
b)	6 way SPN MCBDB Double door comprising 1 no 40 A Isolator and 4 Nos. 6/10 A MCBS.	2	no.	
c)	4 way SPDB comprising 1 no 63 A Four Pole TPNMCB (for UPS INPUT).	1	no.	
d)	4 way DB comprising of 2 nos 63A DP MCB (UPS OUTPUT)	2	no.	
e)	ACDB: 6 Way TP MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 100 A FP TPN and 9 Nos.32 A DPMCBS etc complete as required. (for Air conditioning only).	2	no.	
f)	LIGHTING DB: 4 WayTP MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 30A ELCB and 12 Nos. 6/10 Amp SPMCBS etc complete as required. (for Light, Fan point, Raw power points).	1	no.	
g)	RAW POWER DB: 4 WayTP MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 63 A FP TPN and 12 Nos. 16/20/25 Amp SPMCBS etc complete as required. (for Raw Power Only)	2	no.	
1.8	Supply installation testing and commissioning of following 3 pin metal clad industrial type plug and socket arrangement with plug top, cap and chain controlled by 1 No MCB			
(a)	20 Amps. with 25 Amp. SP MCB UPS OUTPUT	4	no.	
b)	30 Amps. with 63 Amp. SP MCB UPS INPUT	3	no.	
1.9	Providing and fixing of suitable size MS box fabricated with 16G MS sheet either in recess wall or on surface to accommodate dedicated earth from earth electrode and further distribution of earth to computer points including providing of 5 mm bakelite on base connector strip and painting of box etc as required.	1	job	
1.10	Cost of maintaning & working 24 X 7 from date of commensment of work to date of completion.	1	Job	
	TOTAL OF PART -I			

PART-II:	PANELS & CABLES			
2.1	Providing and fixing of 3 nos 160 Amps Kitkat with 1 no neutral link on suitable size of Bakelite sheet of thickness not less than 25 mm complete as required	1	job	
2.2	MAIN PANEL:			
2.2	Supply at site installation testing and commissioning of wall mounted cubicle type electrical panel comprising MCBs, bus bar, cable alleys etc fabricated with 16 G MS sheet and baked or spray enamel painted complete with rubber gaskets name plate interconnection etc. The panel shall consist of:	1	no.	
	INCOMING			
a)	1 no MCCB Breaking Capacity 25 KA 200Amp 4P , DN Series, L&T make.			
b)	1 no 0-500V Voltmeter with selector switch in separate compartment and Amp meter with selector switch and one set of CTs (3 Nos) with CT Ratio 100/5 A with LED type Indication Lamps with protection fuses in a separate compartment			
c)	250 Amps capacity 4 strips Aluminium bus bars.			
	OUTGOING			
a)	3 nos MCCB Breaking Capacity 25 KA 63Amp 4P with seprate neutral Link, DU Series, L&T make.			
b)	1 nos MCCB Breaking Capacity 25 KA 160Amp 4P with seprate neutral Link, DU Series, L&T make.			
2.3	EMERGENCY PANEL:			
	Supply at site installation testing and commissioning of wall mounted cubicle type electrical panel comprising MCBs, bus bar, cable alleys etc fabricated with 16 G MS sheet and baked or spray enamel painted complete with rubber gaskets name plate interconnection etc. The panel shall consist of:	1	no.	
	INCOMING			
a)	1 no MCCB Breaking Capacity 25 KA 160Amp 4P , DN Series, L&T make.			
b)	1 no 0-500V Voltmeter with selector switch in separate compartment and Amp meter with selector switch and one set of CTs (3 Nos) with CT Ratio 100/5 A with LED type Indication Lamps with protection fuses in a separate compartment			
c)	250 Amps capacity 4 strips Aluminium bus bars.			
<u> </u>	OUTGOING			
a)	5 nos MCCB Breaking Capacity 25 KA 63Amp 4P with seprate neutral Link, DU Series, L&T make.			
2.4	Supply, Installation, testing & commissioning of PVC insulated PVC sheathed armoured cable of 1100 V (IS 1554 Part 1) and fixing of cable on wall with suitable size of clamps /saddles or laid in floor/recess wall including cutting of wall /floor and making good the damages etc complete as required of following sizes (ISI marked)			
a)	3.5X35 sq. mm aluminium conductors with two Nos. 8 SWG GI wire.	30	mtr.	
b)	4x16 sq. mm aluminium conductors with two Nos. 8 SWG GI wire.	40	mtr.	

c)	3.5X25 sq. mm aluminium conductors with two Nos. 8 SWG GI wire.	30	mtr.		
d)	4X10 sq. mm aluminum conductor with one no 8 SWG GI wire.	30	mtr.		
e)	3X6 sq. mm copper conductor armoured .	70	mtr.		
f)	4X2.5 sq. mm copper conductor armoured for ACS	205	mtr.		
2.5	End termination with brass compression glands including				
	providing of lugs/ferrules and making necessary connection				
	etc complete as required of the following sizes:				
a)	3.5X35 sq. mm aluminium conductors	4	no.		
b)	4x16 sq. mm aluminum conductors	8	no.		
c)	3.5X25 sq.mm aluminum conductor	4	no.		
d)	4X10Sq.mm aluminum conductor	6	no.		
e)	3X6 sq. mm copper conductor	8	no.		
f)	3X2.5 sq. mm copper conductor	18	no.		
2.6	Providing and fixing the following switch on suitable size of MS				
	base and angle iron frame of suitable size and strength for				
	installation on wall /floor including grouting of frame & painting				
	etc. complete as required.	1			
	1 no.4 pole 160 Amps capacity change over switch with adaptor box	1	no.		
	duaptor box				
2.7	Providing and fixing 16 G MS sheet adopter box and also base				
	frame for installation of MCB DBs plug and socket				
	arrangements and to cover cables in system room including				
	painting etc complete as required.				
	for UPS input/output distribution	1	no.		
	TOTAL OF PART -II				
	EARTHING				
3.1 (a)	Supply and fix copper plate earth station with 600X600X3mm	1	set		
	copper plate including all accessories such as watering pipe and funnel and providing masonry enclosure at top with cover				
	plate i.e excavation of pit, supplying and filling of salt charcoal,				
	refilling of pit etc complete as required as per IS 3043-1987.				
	The voltage between neutral and earth must be below 1 V.				
(b)	Supply and fix GI plate earth station with 600X600X6mm GI	2	set		
	plate including all accessories such as watering pipe and				
	funnel and providing masonry enclosure at top with cover plate i.e excavation of pit, supplying and filling of salt charcoal,				
	refilling of pit etc complete as required as per IS 3043-1987.				
3.2 (a)	Supply fixing and termination of 20X3 mm copper strip with	3	mtr		
	earth station below ground level etc as required.				
(b)	Supply fixing and termination of 32x6 mm G.I. strip with earth	6	mtr		
	station below ground level etc as required.				
3.3 (a)	Providing and fixing of 8 SWG copper earth wire in the recess	25	mtr.		_
	for loop earthing etc. as required.				
(b)	Providing and fixing of 8 SWG GI earth wire in the recess for	25	mtr.		
	loop earthing etc. as required.			_1	

3.4	Supply and laying following dia 2 mm in thickness PVC pipe under floor or in recessed walls from earth electrode to UPS room for computer dedicated earthing including bends Tees Etc. making good the damages etc. wherever required			
	25 mm diameter	50	mtr.	
	TOTAL OF PART -III			
PART-IV:	AC PROVISIONING (COPPER PIPE, WIRING ETC)			
4.1	Supply, Installation, testing & commissioning of refrigeration pipe including cutting of wall & fixing with suitable saddles or clamps, providing suitable sizes of sleeves for passing refrigerant pipe from indoor to outdoor unit including making neccessary arrangement etc. complete as required.			
a)	Hi Wall Split AC (1.0 & 1.5TR), copper pipe size (1/2" & 1/4")	135	mtr.	
4.2	Cutting of floor / wall for refrigerant /drain pipe including making good the damages complete as required, excluding the area having ceramic floor tiles, where chased floor will be got repaired by the firm executing AC installion work, However, the ceramic tiles will be got fixed by the Bank.	50	mtr	
4.3	Supply & laying of 4 core 2.5sq.mm. FRLS copper flexible cable for HWS / Cassette AC, Make - FINOLEX / POLYCAB / HAVELLS / PYEMEN / ECKO	170	mtr	
4.4	SITC of 25mm PVC drain pipe including all accessories, such as bend, tee,cutting chaes and making good damange, leak proof joints, avoid seepage in wall, floor etc complete as required.	40	mtr	
	TOTAL OF PART - IV			
	TELEPHONE			
5.1	Wiring for telephone points with 0.6 mm dia 2 pair insulated annealed tinned electrolatic copper conductor in 2 mm thick 25 mm dia ISI marked PVC conduit complete with accessories such as bends, junction boxes etc. with suitable size of G.I. box modular plate and cover in front on surface or in recess including providing and fixing modular type telephone socket outlet and making necessary connections etc. complete as reqd.	13	no.	
5.2	Supply installation and testing of Tag Block 20 pair for telephone connections	1	no.	
5.3	Supply and fixing 10 Pair Telephone Cable	40	mtr	
	TOTAL OF PART - V			
DADT VI	NETWORKING			
	NETWORKING Wiving for computer not working starting from mounting rook	00	N.I.e	
6.1	Wiring for computer net working starting from mounting rack with UTP Cat 6 cable in 2 mm thick 25 mm dia ISI marked PVC conduit pipe with accessories such as bends, junction boxes including providing and fixing I/O plates and SMB complete with all networking accessories etc complete as required	23	No	
6.2	Supply & Installation testing and commissioning of 24 port Patch Panel, complete in all respects.	1	No	

6.3	Supply & Installation testing and commissioning of mounting rack 9 U high made of powder coated MS sheet complete.	1	No		
6.4	Supply Fixing and commissioning of Patch cable cat 6 of complete with 2 nos of connectors etc complete as required.(
	factory manufactured)				
	(a) 1 meter long	23	No		
	(b) 2 meter long	20	No		
	TOTAL OF PART - VI				
	TOTAL OF PART - VI				
PART-VII	: SITC OF FANS & FIXTURES				
7.1	SITC of 2"x2" Celing grid 33-36 watt LED panel fixtures with	37	no.		
	essential driver in false ceiling including making necessary				
	arrangement for mounting the fixtures and connection with 2 x				
	1.5 sq.mm insulated copper cable from adjacent point in PVC				
	flexible pipe etc Complete as regd. Make Philips cat. RC 380 B-				
	LED-30-6500PSE OD WH or equivalent of Wipro / Bajaj /				
	Crompton.				
7.2	SITC of 15 watt recess mounted LED down light with assembly	30	no.		
	complete with including making necessary connections etc.				
	Complete as reqd. (M/s Crompton Cat No. Or equivalent of				
	Philips/Wipro/ Bajaj)				
7.3	SITC of 9watt RECESS MOUNTED LED down light with	7	no.		
,.0	assembly complete with including making necessary	,	1101		
	connections etc. Complete as reqd. (M/s Crompton Cat No.				
	Or equivalent of Philips/Wipro/ Bajaj) in PASSAGE				
7.4	SITC of 450 mm sweep metal body wall fan complete as	10	no.		
	reqd.(M/s Crompton Metal frame or equivalent of Khaitan /		1101		
	Bajaj				
7.5	SITC of Exhaust Fan 250mm dia, metal body of CROMPTON /	5	no.		
	BAJAJ/KHAITAN				
7.6	SITC of 200 mm exhaust fans complete with self opening	0	no.		
	louvers / shutters including necessary frame etc, complete as				
	reqd. (M/s Crompton High Breeze or equivalent of USHA /				
	Bajaj)				
7.7	SITC of 1200 mm CEILING fans complete as reqd. with	3	no.		
	regulator to be provide in the switch board (M/s Crompton High				
	Breeze or equivalent of USHA / Bajaj).				
7.8	Supply of reccess 5/7 watt LED COB spotlight assembly with	11	no.		
	driver complete as reqd. Phillips ASTRASPOT 7W or equivalent				
	of Wipro / Bajaj .				
7.9	Supply Installation, testing & commissioning of 5W LED STRIP	75	mtr		
	light with driver and Accessories complete as required (MS				
	CROMPTON or equivalent of WIPRO , PHILLIPS, BAJAJ etc.				
7.10	SITC of 18/20 watt of T5 LED fixtures directly on ceiling / wall	7	no.	 	
7.10	including making necessary connections with 2x1.5 sq.mm	,	110.		
	insulated copper cable conductor wire etc. complete as reqd				
	Make Phillips /Wipro / Bajaj.				
7.11	SITC of 30 watt LED Street light /Flood light for lighting the front	3	no.	<u> </u>	
7.11	side of the branch(M/s Crompton Cat No. LSTS-30-CDL or	J	110.		
	equivalent of Philips/Wipro.				
	TOTAL OF PART -VII			 	
	TOTAL OF TARE TVII			-	
				<u> </u>	

SUMMARY			
TOTAL OF PART I-VI(A)		Α	
TOTAL OF PART - VII (B)		В	
TOTAL (A+B)		С	
* GST Shall be paid extra as applicable			