

**FINANCIAL BID OF INTERIOR WORK FOR STATE BANK OF INDIA,
JALANDHAR ROAD BRANCH (11894), AMRITSAR.**

(PART-A) - BANK AREA					
S.N.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	WALL PANELING :-				
	Providing and fixing Paneling (ground floor & first floor) over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally.The frame work to be clad with 8.0 mm thick BWP grade ply (make Aica, Greenlam, Century) and 1.0 mm thick laminate (make Aica, Greenlam, Century) as per pattern. The skirting shall be finished with 1mm thk brushed steel finsih lamiante. Also 3" X 1/2" teak wood section shall be provided on exposed surfaces. All ply / wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be melamine polish with matching pigment. The rate shall include for providing groves in laminate & wood. Payments shell be made only for exposed surfaces & actual measurement at site, no payment shell be made for paneling behind furniture such as tables, Credenza, storage etc.	925	Sft.		
2	FULL HEIGHT PARTITION :-				
	Providing and fixing Low Height Partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick BWP grade ply (make Aica, Greenlam, Century) skirting along with 1mm thick laminate of approved make/colour /texture in desired shade, & horizontal/vertical grooves in desired pattern. Rates to include for provision of 35mm thick flush doors covered with 1.00mm thick laminate on both sides, 4nos brass butt hinges heavy on each door, all brass hardware, 6 levers (make Godrej, Hettich, Haffle) lock with decorative steel handles, door stoppers etc. complete with melamine polish on 2nd class teakwood beeding /moulding in desired shade. The cost of doors with necessary hardware locks etc. complete is to be included and measured in this item. Skirting & intermediate bands will be of 1mm thick metallic shade laminate.All ply / wood to be treated with wood preservatives of approved ISI quality.	310	Sft.		
3	LOW HEIGHT PARTITION :-				
	Providing and fixing Low Height Partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections @ 16" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level with rawl plugs / steel lugs / screw. The frame work to be clad with 8.0 mm thick BWP grade ply(make Aica, Greenlam, Century) and 1.0 mm thick laminate(make Aica, Greenlam, Century) as per pattern with 12 mm thick toughened glass on top with 2nd class C.P. teak wood moulding on free end/top of low height partition complete with melamine polish.The skirting shall be finished with 1mm thk brushed steel finsih lamiante. Also 3" X 1/2" teak wood section shall be provided on exposed surfaces. All ply / wood to be treated with wood preservatives of approved ISI quality.	115	Sft.		
4	GYP SUM BOARD FALSE CEILING :-				

	<p>Providing & fixing Gyp Board False Ceiling, in steps, with 12.5mm gyp bord (make Saint Gobbin, India Gypsum/ Gyproc) fixed on cold rolled galvanized steel section frame as per detailed manufacturer's specifications. The grid consists of a perimeter channel (MF6a of dimensions 20mm x 27mm x 37mm x 3.5M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gypboard. The intermediate channel (MF7) of dimensions 15mm x 45mm x 0.9mm x 3.6M) at 1200mm c/c in the one direction and the ceiling section (MF5 of dimensions 80mm x 26mm x 0.5mm x 3.6M) at 450mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25mm x 0.5mm) at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners. Required cutting for fixtures will be provided. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. Inspection doors for AC units will be of phenol bonded ISI marked 12 mm comm. Ply (make Aica, Greenlam, Century) with 1.0 mm laminate. . Ceiling will be finished with tape and jointing compound and primer & coat of plastic emulsion paint, complete in all respect.</p>	1150	Sft.		
5	ARMSTRONG FALSE CEILING :-				
	<p>Providing & fixing Armstrong false ceiling with 600x600x16 mm Fine Fissured Beveled Tegular Edge RH-99 Armstrong false ceiling laid in Armstrong Silhouette (Black) grid system. The frame work comprises of main runner spaced at 1200 mm centres securely fixed to structural soffit by approved hangers at 1200 mm maximum centres. Hangers (G.I. wires 4.0 mm dia) to be fixed by approved roof plug, level adjuster, screws etc. The last runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200mm long cross tee(with double stitching) to be inter locked between main runners at 600mm centres to form 1200x600mm module. Cut cross tees longer than 600mm to be supported independently. 600x600mm module to be formed by fitting 600 mm long flush fitting cross tee centrally between 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to wall @ 450 mm maximum centres. The rates include making opening for electric fixtures, A.C units etc.</p>	330	Sft.		
6	FRONT LINE COUNTERS (S.W.O.) :-				
	<p>Providing and fixing at site SWO counters each upto 5'0" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick bwp grade ply (Make: century-sainik, green ply-ecotech, Euro) with 1.0 mm thick laminate(make Aica, Greenlam, Century,) on all outer visible surfaces (except the bottom half of front modesty panel , which shall be finished with 4 mm thick lacquered glass), with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. comm. ply and finished with 6mm thk. flexi ply as base for laminate sheet as/design with provision for Installation of Lights in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 with both side laminated board with back support, of EBCO make fixed on channels. Three drawers with autolock on top drawer, running on Telescopic channels of EBCO make, made of 19 mm thick BWP grade ply with 1 mm thick laminate on front face. The sides of the drawers shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood. Non visible/Inside surface i.e. inside leg-space of table, inside drawers shall be finished with 1mm thk. white/off white laminate. All exposed Teak wood edges / teak wood lipping /MDF beading shall be Spray painted Satin Enamel paint or spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also includes foot rest. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), complete in all respects. The provision of swapping machine of green channel size 9"x 6" with lid shall be provided at right side of each counter while facing from front. the cost of corian acrylic surface and lacquered glass is to be paid extra.</p>	18	R.ft.		

7	TABLE (B.M. Cabin):-				
	Branch Manager Table made of 19 mm thk. BWP grade ply (Make: century-sainik, green ply-ecotech) with 1.0 mm thick laminate (make Aica, Greenlam, Century) 12mm thick Corain on all sides for table Front& Top, on all outer visible surfaces (except the bottom half of front modesty panel , which shall be finished with 4 mm thick lacquered glass), with 40 mm X 12 mm thick teak wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. Teak wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of (Ebco, Harison, Godrej) make fixed on channels. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, which will be made of 19mm thick BWP grade ply finished with laminate 1mm thk, 8 mm thick glass with its edges duly bevelled (25 x 3 mm) & PENCIL grinded on all sides, for table tops. (Corain & Lacqered glass is to be paid extra)				
	Three lockable drawer running on side mounting drawer slides (channels) of (Ebco, Harison, Godrej) make made of 19 mm thick BWP grade ply with 1mm thick laminate on front face, handle / knob shall be provided. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Non-Visible/inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Spirit polished or Spray Painted as required.				
	B.M. Table: 6'-0"x 3'-0"x2'-6" as per drawing	1	No.		
8	CLERICAL TABLE :-				
	Clerical Table made of 19 mm thk. BWP grade ply (Make: century-sainik, green ply-ecotech) with 1.0 mm thick laminate (make Aica, Greenlam, Century) with its eon all sides for table top, on all outer visible surfaces (except the bottom half of front modesty panel , which shall be finished with 1 mm thick laminate), with 40 mm X 12 mm thick teak wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. Teak wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of (Ebco, Harison, Godrej) make fixed on channels. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, which will be made of 19mm thick BWP grade ply finished with laminate 1mm thk, 8 mm thick glass with its edges duly bevelled (25 x 3 mm) & PENCIL grinded on all sides, for table tops.				
(i)	Credit Card & Messenger Table: 4'-0"x 2'-3"x2'-6" as per drawing	2	No.		
9	SIDE CREDENZA :-				
	Providing & fixing Side Credenza (1'-3" deep x 2'-6" high) made of 19 mm thick BWP grade ply(make Aica, Greenlam, Century) and 6 mm thick plywood on back side & 1mm thick laminate(make Aica, Greenlam, Century) of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontally running on side mounting drawer slides (channels) of EBCO make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers all non visible/inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.				
(i)	3'-6" x 1'-3" x 2'-6"	1	No.		
10	BACK CREDENZA :-				

	Providing & fixing Back Credenza (1'-6" deep x 2'-6" high) , made of 19 mm thick BWP grade ply (make Aica, Greenlam, Century, Euro) and 6 mm thick BWP grade plywood on back side & 1mm thk laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer 4"high, horizontally running on side mounting drawer slides (channels) of (Ebco, Harison, Godrej) make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle / knob and magnetic catcher shall be provided beneath the drawers and non-visible/inside surfaces should be finished in 1mm thk. laminate of white/off white shade and teak wood edges / lipping / beading shall be Melamine polished with matching pigment	85	Sft.		
11	LOCKER ROOM MIRROR PANELING:-				
	Providing & fixing 5 mm thick looking Mirror with beveled edges paneling of approved quality & grade including making of ground of 12mm thick ply (Green Ecotech/or Century Sainik) as per design, with 4mm wide vertical or horizontal grooves as per the drawing provided by the Architect.	10	Sft.		
12	DRESSING CABINET:-				
	Providing & fixing dressing cabinet in ply & laminate of size (4'-0" x 1'-6" x1'-6") with drawers on both sides & squire puffi (1'-6" x 1'6") in center with leather on top compete in all respects as per the drawing provided by the Architects.	6	Sft.		
13	12 MM TOUGHEND GLASS DOOR :-				
	Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass (Saint gobain, Asahi, Modigaurd) doors, single leaf glazed Toughned door of size approximately, 1200 to 700mm X 2100 mm all sides edge grained, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include necessary etching film / logo all inclusive, complete NOTE: Rates include Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring machine (Ozone, Godrej), 2'-0" SS door handle, 304 grade (both sides) in door - pair, etc. all complete in all respect.	95	Sft.		
14	12 MM TOUGHEND GLASS PARTITIONS :-				
	Providing & fixing frameless fully glazed 12 mm thk. toughend float glass (Saint gobain, Asahi, Modigaurd) partition of size - as per site all sides edge grained, polished to be fixed with necessary patch fittings (Ozone, Dorma, Godrej) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall be include necessarydecorative film / logo all inclusive, complete. Glass partition will be fixed at bottom & top with patch fittings(as required) , SS U-channel of 12x25mm to be grouted with floor.	160	Sft.		
15	8 MM GLASS TABLE TOP :-				
	providing and supplying 8 mm thick toughend glass with its edges duly bevelled (25 x 3 mm) & PENCIL grinded on all sides , for table tops.	40	Sft.		
16	LACQUERED GLASS :-				
	Providing and fixing 4 mm thick lacquered glass of aqua blue colour (Saint gobain, Asahi, Modigaurd) using recommended adhesive over pre existing front modesty panel,complete job to the satisfaction of the architect/bank's engineer.	50	Sft.		
17	ALUMINIUM PARTITION FOR ELECTRICAL PANEL :-				

	Providing and fixing at site aluminium partition for the electrical panel as per the design and drawing. The carcass frame shall be made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections , and cladded with cemented board (Bision, Zykrone, Everest) 6 mm thick on one side. All stiles and rails for the openable shutters shall be made of 83 mm X 40 mm X 16 Gauge aluminium extruded sections and cladded with cemented board 6 mm thick .The shutters shall be mounted on the hinges .The cabinet shall be complete with all necessary hardwares like locks, handles, catchers, tower bolts etc. The cemented board shall be finished with 2 coats of primer putty filling to desired smoothness and finished with two coats of plastic paint of desired shade and colour on all internal surface. All the outer visible surface shall be finished with 1.0 mm thick laminate of approved color and shade using the recommended adhesive.	95	Sft.		
18	CORIAN (Solid Surface) :-				
	Providing and fixing 12mm thick bendable Corian (Make Rehau, LG, Dupont) sheet as per manufactures specifications on top of SWO counters (transaction counters) the work shall including bending the sheet in curvilinear shape and rounding of edges, complete job including recommended adhesive and as per manufacturers specifications. Note: the area is to be measured only in square foot and no quantity in rft shall be measured for billing purpose)	100	Sft.		
19	PIN UP BOARD				
	providing and fixing 12 mm thick soft board over 12 mm thick ply fixed in wooden frame made out of commercial champ wood out of size 2.5 "x 1.5" (duly polished). The work shall be completed by covering the soft board with fabric/tapestry of approved color and shade.	60	Sft.		
20	FIRE DOOR :-				
	Door to System room - Fire rated steel door (make Godrej, Aditya, Rawji) including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC. a). Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm / sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) all-round the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer – in charge (including Dash fasteners). b). Shutter - Providing and fixing Metal Door Shutter 46 mm thk. made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer – in – charge, with suitable mounting on door frame, the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make, provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge. The work includes providing and fixing following hardware for fixing to above door Hinges 4X3X3 (Min. 3Nos), Pull Handle 19 X 250mm -Pair, Dead Lock, (Godrej Night Latch Lock) Fasteners Hilti 10 X 92mm (Min - 10Nos.)	45	Sft.		
21	FLUSH DOOR (WOODEN) :-				
	Providing and fixing wooden Choukhat & Flush Doors made of Partal Wood inside & 1 mm laminate on both the surfaces , with necessary vertical or horizontle grooves 6mm thick, including steel handle, hinges & hudraulic door closer etc.complete in all respect,as/drgs provided by the Architect.including acsory	5	No.		
22	VOUCHER STAND :-				

	Providing and fixing Voucher Stand of size 4'-0" X 1'-6" X 3'-6" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick BWP grade ply (make Aica, Greenlam, Century) with 1.0 mm thick laminate to be fixed and 3/4" x 1/4" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.	1	No.		
23	BATHROOM MIRROR :-				
	Providing & fixing 600x450 mm or as directed, beveled edge mirror 5.5 mm superior glass (Saint gobain, Asahi, Modigaard) complete with 6 mm thick hard board ground fixed to wooden cleats & CP brass screws, washers & clips etc. complete.	10	Sft.		
24	TEXTURE PAINT :-				
	Providing & applying a coat of RUSTIC textured finish in white color (Asian, Nerolac, Berger) on walls and columns. The rate shall include scrapping, leveling & preparing the surface with (Jk, Asain, Birla white) putty. Applying 1 coat of texture over a coat of primer & applying 2 or more coats of plastic emulsion paint of approved shade to give even & uniform surface, including cleaning of floor, surface etc. complete.	465	Sft.		
25	BACK LIT 12mm thick JALI ON COLUMNS :-				
	Providing and fixing on the partitions/paneling 12mm thick MDF jali as per design duly deco painted in desired colour sandwiched between two transparent acrylic sheets each 3mm thick fixed with stainless steel studs and screws complete.provision for led strip light is to be made to litup the jali work. led strip is to be provided by the electrical contractor	30	Sft.		
26	A.C.P. SHEET WALL PANELING / CLADDING :-				
	Providing and fixing 4.0mm thick pvdf coated exterior grade A.C.P.. sheet paneling over Anodised Aluminium frame work of size1-1/ 2" x 1-1/2" @ 2'-0" c/c bothways. including openable shutter where required.the work shall include the cost of all necessary hardware e.g m.s hinges. magnetic catcher,aluminium tower bolts-6" long long etc.	480	Sft.		
	TOTAL (PART-A)				
	DESCRIPTION OF ITEM (WEALTH HUB PART-B)				
1	WALL/ COLUMN PANELING WITH LAMINATE FINISH.				

	<p>Wall paneling made from 25 x 25 x 1.00 mm thick hollow aluminum sections, over which BWR grade ply of 10 mm shall be fixed and additional 6-8mm ply in layers to create grooves as per the design in the drawing or as directed by Architect, with decorative molding patty on the edges.</p> <p>Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under:-</p> <p>(i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.</p> <p>(ii) Panel Finishing:- Providing & fixing 9 mm thick approved make BWR plywood and additional 6-8mm ply in layers to create grooves as per the design to Aluminum framework finished with 1.00 mm thick approved quality and shade laminate, using approved adhesive, in approved pattern & design, including providing grooves, decorative moldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge.</p> <p>(iii) Providing approved quality, seasoned, full length, Teak Wood molding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as directed by the Engineer-in-charge at site.</p> <p>(iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p> <p>(v) Applying 2 or more coats of melamine polish to exposed edges of paneling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete.</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank.</p> <p>(c) Laminate:- Dorby Mica, Greenlam/Century/Archid / Aerolam or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p> <p>Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear paneling area available below false ceiling shall only be measured</p>	220	Sft.		
2	FULLY GLAZED DOOR				
	<p>Providing and fixing position 12 mm fully glazed toughened glass door, single/ double shutter, of approx. size 900/ 1500 x 2100/2400 mm</p> <p>Providing and fixing in position frameless glass door shutter made using 12mm thick toughened glass fixed to the partition (glazed / solid / gypsum partitions) using heavy duty floor spring with pivot of approved make including necessary cutting of floor and making the surface good to its original position including all necessary Patch fittings of approved make and fixtures & hardwares.</p> <p>Approved make: DORMA Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Handle - TG DIH600 - 600mm length) or equivalent brand fittings from Hettich / Hafele / as per sample approved by the Bank. Rate should also include providing film as per design/ instructions of Bank.</p> <p>Mode of Measurement: Door opening size shall be measured.</p>	25	Sft.		
3	FULL HEIGHT FULLY GLAZED PARTITION WITH 12MM TOUGHENED GLASS UPTO 7' LEVEL WITH SOLID PARTITION ABOVE 7' LEVEL				

	<p>Providing & fixing full height glazed partition with 12mm Toughened glass of approved make up to 7' level height with solid partition above 7'-0" level up to false ceiling bottom.</p> <p>The glazed panels shall be fixed to the existing floor and false ceiling with all necessary SS brackets (D, C or U type)</p> <p>Vertical joints between the glass panels shall be sealed with suitable transparent sealant.</p> <p>The solid partition above 7'-0" level shall be made with aluminium framework of size 63mm X38.10mm X1.47 mm (0.780Kg /mtr) box section. The spacing of the Horizontal and Vertical members are approximately 600mm c/c (maximum) and the top of the frame shall be fixed to the RCC slab bottom. The exposed surfaces on both sides of framework are covered with 6mm BWR ply finished with 1.0mm thick laminate as per direction.</p> <p>Providing, placing in position & erecting full height partition in desired shape, framework shall be of 50 x 50 x 1.5 mm thick aluminum square section placed at 500 mm c/c both ways or as directed.</p>	25	Sft.		
4	FULL HEIGHT SOLID WOODEN PARTITION WITH BOTH SIDES LAMINATE				
	<p>Providing & fixing in position 70mm thick +/- 2mm full height solid/opaque wooden partitions finished with laminate on both sides comprising as under:-</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) both ways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling.</p> <p>(ii) Plywood skin:- Providing & fixing 12 mm thick MDF boards on both sides of the framework.</p> <p>(iii) Finishing:- Providing 1.00 mm thick, approved quality and shade laminate, on both sides of partitions in approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approved quality adhesive complete.</p> <p>(iv) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p> <p>(v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full-length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site.</p> <p>(vi) The door shall be provided with approved make lock, heavy duty door closer, 4 nos. of 5" brass oxidized hinges, SS Brush finish H handle of 9" etc. complete.</p> <p>(vii) Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door openings, cutouts etc. complete.</p> <p>(viii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) MDF Board:- Greenply, Century, Samrat or equivalent approved by the Bank.</p> <p>(c) Laminate:- Greenlam/Century/Archid or equivalent approved by the Bank.</p>	190	Sft.		
5	GYPBOARD FALSE CEILING				

	<p>Providing and fixing false ceiling with cove at all height including providing and fixing of frame work made galvanized M.S. sections as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval.</p> <p>Fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of Engineer in charge including cost of painting the false ceiling with two coats of acrylic emulsion paint over a cost of putty</p> <p>12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) to be used.</p> <p>Same as Gypsum false ceiling but providing, making, and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen etc.</p>	80	Sft.		
6	MINERAL FIBRE GRID TILE CEILING:				
	<p>Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc.</p>	80	Sft.		
	<p>Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. GI Metal Ceiling Lay in perforated Tegular edge global white colour tiles of size 595x595 mm and 0.5 mm thick with 8 mm drop; made of GI sheet having galvanizing of 100 gms/sqm (both sides inclusive) and 20% perforation area with 1.8 mm dia holes and having NRC (Noise Reduction Coefficient) of 0.5, electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending and perforation, and backed with a black Glass fibre acoustical fleece.</p>				
7	CENTER TABLE (3'-0" X 2'-0" Oval / Rectangular)				

	Providing and supplying in position oval or rectangular centre table to be made out of 2" X 2" teakwood frame including 12mm thk clear glass top with bevelled edges including bottom glass shelf with etching etc complete. The rate shall also include SS lining design to the teakwood frames including all the necessary hardware, fittings, fixtures as per manufacturers specifications complete.	2	No.		
8	BACK PAINTED GLASS + LOGO				
	Back painted glass (Lacquer Glass) paneling: Providing and fixing in position wooden paneling to column / walls finished with Back painted (Lacquer Glass) comprising as under:- (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed upto 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb. (ii) Panel Finishing:- Providing & fixing 9 mm thick approved make BWR plywood to Aluminum framework finished with 8 mm thick approved quality and make back painted Lacquer Glass panels of required size, rigidly fixed using 3M adhesive / double side self-adhesive tape complete as directed by the Engineer-in-charge. (iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards etc., including providing necessary wooden/aluminum section members support at cutouts, providing scaffolding for execution of work at all heights, complete as per drawings and as directed by the Engineer-in-charge at site.	49	Sft.		
b.	Logo:- Providing and fixing in position with SS studs or as directed laser cut Logo as per design made from 18 mm MDF board (exterior grade) and and 10 inch -12 inch high and finished with PU metallic paint as directed complete.	1	No.		
9	WOODEN FLOORING + SKIRTING				
	Providing and placing in position wooden laminate flooring with planks of size not less than 1200 mm X 190 mm (with unlinck panels / tongue-groove locking arrangement) having a 0.2 mm thick top abrasive layer followed by decorative layer upon HDF (high density fiberboard) substrate core over raisin saturated backing layer installed using tongue-groove system over 2 mm thick underlayer of polyurethane foam on 250-micron polythene sheet over a smooth, flat, hard and free from moisture floor surface complete in all respect with required accessories like end profile, transition profile, reducer 'T' profile etc. and preparation of base including all other incidental works as per direction & satisfaction of Architect in charge. Cost of Laminate Floor Accessories, Skirting, End edge, T- molding, Reducer shall have to be added in the cost, wherever required. Grade :- AC4	125	Sft.		
10	POLYESTER FILM OVER GLAZED PARTITIONS				
	Providing and fixing in position high impact resistant Polyester Films of approved design & pattern, which once installed on glass, give additional strength to glass, reduce glare & prevent glass from splintering on impact. thickness not less than 4 Mil (100 mic.) or 7 Mil (175 mic.)	45	Sft.		
	TOTAL				
	TOTAL (PART A+B)				
	LESS SALVAGE VALUE FOR OLD ITEMS (As per site conditions)				
1	WOODEN PARTITION	85	Sft.		
2	ALUMINUM PARTITION	435	Sft.		
3	COUNTERS	35	R.ft.		
4	TABLES	7	Each		
	LESS TOTAL				
Note	(Bank reserves the right not to dispose of above items as per salvage value)				
	TOTAL INTERIOR WORK				
	G.S.T as applicable will be paid extra by the bank				