

**FINANCIAL BID OF CIVIL WORK FOR STATE BANK OF INDIA,  
NEW AMRITSAR BRANCH (11896), AMRITSAR.**

SN.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
<b>1</b>	<b>VITRIFIED TILES FLOORING:-</b>				
	Providing and laying double charged Vitrified tiles 600mm x600mm ( <b>Marble series- Johnson, Kajaria, Nitco</b> ) with water absorption less than 0.08% and conforming to IS:15622, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm. Including dismantling of existing floor tiles if any and disposing of malba from site at appropriate place. Cutting wooden/ aluminum doors to match new floor level. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.	2375	Sq.ft		
<b>2</b>	<b>PANTRY &amp; TOILET WALL &amp; FLOOR TILE:-</b>				
	Providing and laying Ceramic wall tiles 300mm x 450mm & Anti skid floor tiles 300mm x 300mm ( <b>Johnson, Kajaria, Nitco</b> ) 8mm of 1st quality conforming to IS:15622 of approved make in colours such as White, Ivory,Grey,Fume Red Brown. laid on 12 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) pointing the joints with white cement and matching pigment etc., including dismantling of existing floor & wall tiles if any & disposal of malba at appropriate place.				
	Ceramic Tiles For Wall : ( 12" x 18" )	595	Sq.ft		
	Anti Skid Tiles For Floor : ( 24" x 24" )	115	Sq.ft		
<b>3</b>	<b>GRANITE :-</b>				
	Providing and laying 18mm thick Lopatto / Flamed Finish Granite on main entrance steps with 1.5" moulding over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and directed by the Architect.	665	Sq.ft		
<b>4</b>	<b>PANTRY R.C.C. SLAB WITH GRANITE &amp; STAINLESS STEEL SINK :-</b>				
	Providing and laying 18mm thick Black/Grey lopatto/flamed finish Granite on R.C.C. slab 3" thick (6'-6" X 2'-0) as per the drawings provided by the architect with (2'-0"X1'-6") stainless steel sink make (Neelkanth/ Jaina/Everest) complete in all respect.	1	Lumsum		
<b>5</b>	<b>S.S. RAILING :-</b>				

	Providing and fixing stainless steel Grade 304 railing (Jindal, Hindalco, Bharat) made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per the drawings provided by the Architect, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	25	Rn.ft		
<b>6</b>	<b>PLASTIC EMNULSION PAINT:-</b>				
	Applying three or more coats of Plastic Emulsion Paint ( <b>Asian, Nerolac, Berger</b> ) of approved shade including making of ground, rubbing, filling of putty base preparation etc. In case where the surface has been white/color washed, the old white/color wash shall be entirely removed and surface broomed/scrapped down before the newPaint is applied. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	6750	Sq.ft		
<b>7</b>	<b>PLASTER &amp; FINISHINGS :-</b>				
	Repairs to plaster 1:4 (1 cement : 4 fine sand) of thickness 12 mm to 18 mm in patches of area 2.5 sq.meters including removing the old plaster wherever required and cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	275	Sq.ft		
<b>8</b>	<b>BRICK WORK :-</b>				
	Providing & laying 4.5" Thick brick wall with brick class designated 75 in cement mortar 1:4 (1 cement: 4 coarse sand), including all types of leads/ lift, scaffolding, pads, racking joints, curing, chipping/ cutting concrete floor before starting work, complete in all respect. In case of half brick wall, MS reinforcement as per CPWD specifications to be provided, i.e. 2 nos. 6mm dia TOR steel bars will be provided at every third course, for which no extra payment will be made.	100	Cu.ft		
<b>9</b>	<b>INTERLOCKING TILES :-</b>				
	Providing & fixing 65 mm thick interlocking tiles on floor including sand underneath & all types of leads/lift scaffoldings, pads, curing ,e.t.c complete in all respect.	235	Sq.ft		
<b>10</b>	<b>ROLLING SHUTTER :-</b>				

	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for	260	Sq.ft		
<b>11</b>	<b>COLLAPSIBLE/KANCHI GATE :-</b>				
	Providing & fixing in position collapsible steel shutters with vertical channels 20x10x2 mm & braced with flat iron diagonals 20x5 mm size, with top & bottom rail of T-iron 40x40x6 mm, with 40mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer:-	115	Sq.ft		
<b>12</b>	<b>ENAMEL PAINT:-</b>				
	Applying 2 or more coats of enamel paint ( <b>Asian, Nerolac, Berger</b> ) on Collapsible m.s. kanchi gate & m.s.windows to give even & uniform surface.	1015	Sq.ft		
<b>13</b>	<b>EUROPEAN WATER CLOSET:-</b>				
	Providing & fixing 1st quality vitreous china white colored Floor mounted European water closet ( <b>Hindware- Universal Cat 20012</b> ) with 10 ltr. Vitreous china white colored cistern ( Hindware ) with seat cover & lid, C.p bend, including connecting with existing C.I pipe with CI/PVC,pipe, cutting & making good floor/walls wherever required, complete in all respect.	3	Nos.		
<b>14</b>	<b>WASH BASIN:-</b>				
	Providing & fixing 1st quality vitreous china white colored washbasin 56x41cm size ( <b>Hindware- Opal Cat no. 10082</b> ) size 67x51 cm, with pedestal ( <b>Hindware</b> ) , I no. C.P Pillar cock ( Jaquare – Presmetic ) , C.P waste , P.V.C drain pipe, fixing wash basin with M.S bracket, cutting & making good floor walls, wherever required, complete in all respect.	3	Nos.		
<b>15</b>	<b>URINAL:-</b>				
	Providing & fixing 1st quality vitreous chine white colored urinal ( <b>Hindware – cat mo. 600002</b> ) with matching 5 litre vitreous china white colored auto cistern ( <b>Hindware</b> ) connecting C.P brass pipes/speaders, removing & stacking existing fixtures, cutting & making good floor/walls, wherever required, complete in all respect.	2	Nos.		
<b>16</b>	Providing & fixing 15mm dia CP short body Bibcock (JAQUAR CONTINENTAL- Cat no. 037 ), with CP wall flange, complete.	13	Nos.		
<b>17</b>	Providing & fixing 15mm dia CP Angle valve (JAQUAR - Cat no. 053), with CP wall flange	13	Nos.		
<b>18</b>	Providing & fixing 15mm dia CP Water jet for WC with connecting CP pipe.	3	Nos.		

19	Providing & fixing CP jali (heavy duty) with CP outer ring.	9	Nos.		
20	Providing & fixing CP Towel rack heavy duty rod with wall hanging rail for towel.	3	Nos.		
21	Providing & fixing CP liquid soap container (JAQUAR make or its equivalent.)	3	Nos.		
22	Providing & fixing 15mm dia GI pipe, medium class conforming to IS-1239 (JINDAL/ TATA), including necessary fittings like nipples, tee, socket, union (SNW/ UNIQUE make) etc., complete. Rates to include cutting/ chasing walls, floor, fixing pipe & making good the damages with cement mortar, complete in all respect.	75	R.ft		
22	Providing & fixing GI Reducer (SNW/ UNIQUE make) for floor drain, 75x50mm size ,including chasing walls, floor, fixing pipe & making good the damages with cement mortar, complete in all respect.	13	Nos.		
24	Providing & fixing 75/ 100mm Floor trap, complete in all respect.	13	Nos.		
25	Providing and laying in position 4" heavy duty Supreme/Finolex 6kg/cm2 pipe (DIPLAST- ISI marked), including excavating earth, dismantling cement concrete floor, laying pipe, including bend, collar etc., encasing pipe in concrete 1:2:4 (1 cement: 2 coarse sand: 4 coarse aggregate 20mm & down), connecting with existing pipe, including providing collar & jointing with adhesive, re-filling earth, repairing concrete flooring & disposal of malba from site, complete.	30	R.ft		
26	<b>DISMANTLING :-</b>				
	Dismantling of Slab/brick wall/ Stone wall/ concrete flooring & disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including the loading/unloading/carrying of material from 3rd floor to ground floor, transporting, unloading to approved municipal dumping ground.	1	Lumsum		
	<b>TOTAL</b>				
	G.S.T as applicable will be paid extra by the bank				
	Seal & Signature Of Vendor				