PRICE BID OF FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR
STATE BANK OF INDIA - SIPCOT BRANCH

Note: Rate should be inclusive of material/labour,tools, machinery, scaffolding, final disposal of debris, cleaning, curing wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.

Sln	Description	Qty.	Unit	Rate in (Rupees)	Rate in (paise)	Amount
1	**TABLE OF SALES AND SERVICE MANAGER**	2.00	NOS			
	Same as above item No-1 but size 5'-0" x 2'-6" with storage unit 4 Nos Drawer in table Elevation as follows:					
	Table Top: Backlit with Textured Matte Laminate.					
	Apron (Modesty Panel) made from 18mm thick ply wood with 1mm thick laminate finish on exposed surface shall be provided in a pattern as per drawing approved. Ready made Foot rest CPU stand trolly with castor and and metallic cable manager shall be provided in table top.					
	Table side made from 18mm thick ply wood with 1mm thick frosty white laminate shall be provided in a pattern as per drawing approved.					
	All other surface without lamination shall have polished/ synthetic enamel paint of approved shade. As per drawing and instruction of Architect/Bank Complete.					
	FINISHING DETAILS IN NUTSHELL:-					
	1) Table Top :- Dark Laminate & Burma Teak beading on Edges with Veneer					
	2) Colour Apron & Sides:- Frosty White Laminate					
	3) Finish of Drawer:- Frosty White Laminate					
2	**SIDE CREDENZA**	2.00	SMT			
	Supplying and providing side cabinet for keeping computer and printer size 1'-4" width 2'-6" height and 2'-0'10'-0" length. Openable shutter with 1.0mm thick laminate finish on Top, front side shutter and 35 mm x 6mm thick Burma Teak beading on Edges. Cabinet shall be made from 18mm thick provided only on visible surface etc complete as follows. Having openable shutters as directed. Cabinet shall be made from 18mm thick commercial ply wood with 1.0mm thick laminate Finish. Back shall be made from 6mm in commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch, . Rate includes all necessary provisions for installing computers.All the surface without laminate shall be polished / synthetic enamel paint					
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. As per drawing and instruction of Architect/Bank Complete.					
	FINISHING DETAILS IN NUTSHELL:-					
	1) Table Top :- Dark Laminate & Burma Teak beading on Edges with Veneer					
	2) Front Apron & Sides:- Dark Laminate					
3	**CROCK WARE KITCHEN UNIT (MODULAR)**	3.10	SMT			
	Supplying and providing storage cabinate with 1.0mm laminate on Top, Front Shutter & 35mm x 6mm thick Burma Teak beading on Edges with polish. Laminate to be provided only on visible surface.					
	Size 2'-0" x 2'-0" to 2'-0" Ht. having openable shutter as directed. Storage Cabinet shall be made from 18mm thick commercial ply wood for Top with 1mm laminate finish and 18mm thick ply wood for vertical, shelves, shutters and 6mm commercial plywood for backing with 1mm laminate on all exposed surface and polishing/ synthetic enamel paint on all Openable shutters in 18mm thick commercial ply wood with all S.S. hinges, towers bolts, powder coated handle, ball catches, S.S approved make (group lock) multi purpose lock complete. Edges to be finished with teak wood lipping etc. Including all internal surface to be polished/painted etc. complete. Laminate to be provided only on over visible surface.Front surface area shall be measured for payment purpose.					
	FINISHING DETAILS IN NUTSHELL:-					
	1) Table Top :- Dark Laminate & Burma Teak beading on Edges with Veneer					
	2) Front Apron & Sides:- Dark Laminate					
4	**CLOCKWISE FOR BANER**	2.00	SMT			
	Providing and fixing Electric cupboard using 18mm thick Plywood with 1.0mm thick laminate finish on exposed surface of 50 x 25 x 1.25mm thick with 6mm thick brown panel on both side for shutter with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface, shutter with approved make lock handle, hinges,bolt and catches etc. Size 2'-0" x 2'-0" to 2'-0" x 2'-0" Ht. Front shutter etc.complete as directed, depth of cup board 0'-9' Shutter height up to 7'-0" and above fixed Type up to false ceiling bottom.					
5	**SHUTTER FOR UNDER PANTRY PLATFORM**	1.00	SMT			
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" T.W members for frame, 18mm Ply plywood with 1.0mm laminate for shutters. Providing 1/2" ply back panel, Providing and fixing Stainless steel Cup handles, stoppers and magnetic catch as directed. All the surface shall be polished synthetic enamel paint as directed complete.Providing and fixing 0.80mm thick balance/cig laminate on internal shutter surface					
6	**CLEAR/FROST PARTITION WITH 12X 6TL TAPE EL**	0.50	SMT			
	Providing and fixing low height partition using 50mm x50mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12mm thick MDF Board exterior grade of approved brand on both side of aluminium skeleton and fixing 1.0mm thick laminate finish on exposed surface of board. Fixing laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12mm th free clear float glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface.					
7	**SOLID PARTS FLASHED FULL HEIGHT PARTITION**	28.00	SMT			
	Providing and fixing both sides laminated full height panty glazed partition using 50mm x 25mm x 1.5mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade of approved brand on both side of aluminium skeleton and fixing 1.0mm thick laminate finish on exposed surface of board. Fixing laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12mm th free clear float glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface.					
8	**SOLID PARTS FLASHED FULL HEIGHT PARTITION**	13.00	SMT			
	FULLY GLAZED PARTITION With Patch Fitting for cabin. 12 mm thick Toughened glass with the help of top patch & bottom patch fittings. The door will have patch lock, plunger Handles, Hinges & Screws. The glass edges shall be polish on all sides.					
9	**12MM THICK TOUGHENED GLASS DAPHARM FOR SEMI-ARTIST, THEN NOT SEMI ELI PATCH**	5.00	SMT			
	Providing and fixing 12mm thick Toughened glass Dapharm Fabric complete as directed. Glass edges shall be round insulated and polish as per direction complete.Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured for paid)					
10	**ISOLATED FLUSH DOOR SHUTTER (Partly Glazed and Partly Laminate) WITH FRAME**	4.00	SMT			
	Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 32mm thick flush door with 6mm thick clear float glass vision panel secured with 12mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, 1mm thick laminate finish on exposed surface, aluminium stopper patti on frame including 2 Nos 5" long S.S. hinges with countersunk S.S screws, Approved make Dred Lock, S.S Handles, 150mm long Door stoppers, doorstop of approved make etc. all exposed surface edges not laminated be finished with lacquer polish. As per drawing and instruction of Architect/Bank Complete.					
11	**ISOLATED FLUSH DOOR SHUTTER (Partly Glazed and Partly Laminate) WITH GI AND UPVC WITH**	2.00	SMT			
	Providing and fixing aluminium frame of 45mm x 38mm x 1.5 mm thick and door shutter made out of 32x25x1.5mm thick framing at maximum 1'-6" C/C both way with 6mm thick Alluminium sheet on both side of shutter including 6mm thick clear float glass, vision panel secured with 12mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, aluminium stoper patti on frame including 2 Nos 5" long S/S hinges with countersunk S.S screws, Approved make Dred Lock, S.S Handles, 150mm long Door stoppers, doorstop of approved make etc. complete as per drawing & instructions.					
12	**FULLY GLAZED DOOR WITH PATCH FITTINGS FOR MAIN ENTRANCE DOOR AND A LEDGET DOOR**	7.00	SMT			
	Providing & Fixing fully glazed door. The item includes fixing of 12mm thick Toughened glass with the help of top patch & bottom patch fittings. The door will have patch lock, plunger Handles, Hinges & Screws. Providing and fixing (Approved Make) fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish signage for pull & push.					
	The patch fittings (Approved make) shall be of stainless steel. The door shall be erected in complete line & level. The door will have S.S brush finish signage for pull & push.					
	The door shall be erected in complete line & level. The door will have S.S brush finish signage for pull & push.					
13	**PANELING WITH ALUMINIUM FRAMING (FINISH**	3.10	SMT			
	Providing and laying panelling on walls & pillars having 12mm thick MDF Board exterior grade and 1.0mm th laminate fixed on wall and pillar including Aluminium Framing of 25mm x 1.25mm thick at maximum 2'-0" c/c battenage on wall and pillar etc complete as directed. panelling as per design and instruction of Architect					
14	**WALL PANELING (FINISH LAMINATE)**	11.70	SMT			
	Providing and laying panelling on walls & pillars having 12mm thick MDF Board exterior grade with 1.0mm th laminate fixed on wall & pillars on wall and pillar etc complete as directed. panelling as per design and instruction of Architect.					
15	**WALL PANELING WITH WATERPROOF LAMINATE**	4.00	SMT			
	Providing and laying panelling on walls & pillars having 12mm thick MDF Board exterior grade with 1.0mm th laminate fixed on wall & pillars on wall and pillar etc complete as directed. panelling as per design and instruction of Architect.					
16	**FIBER GLASS PANELING WITH ENGRAVING WITH PLY FRAMING**	7.00	SQMT			
	Providing and fixing 9mm thick MDF Board exterior grade with jali work with high gloss PU coating paint over central column. Fixing laminate in a shape as directed shall be fixed on all with aluminium framing of 25mm x25mm x 1.25mm thick at maximum 2'-0" c/c battenay as per drawing and direction with all labour and material etc. complete (Rate shall be including CNC cutting, jali work and 3mm thick blue glass laminate behind design jali work as directed).					
17	**PANELING FOR DISPLAY WALL WITH 3M VINYL FILM**	3.00	SMT			
	Providing and laying panelling on wall having 9mm thick MDF Board exterior grade with 3M vinyl film with printed design and lamination fixed on wall with Aluminium. Framing of 25mm x 1.25mm thick at maximum 2'-0" c/c battenay etc. complete as directed. panelling as per design and instruction of Architect. Only Finished visible surface area shall be measured for payment (MDF board with 0.80 mm thick laminate) Front surface area shall be measured for payment purpose					
	Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width.					
18	**PANELING FOR DIGITAL WALL WITH BLUEMINTE HIGH GLOSS PU COATING**	5.20	SMT			
	Providing and laying panelling on wall having 9mm thick MDF Board exterior grade with PU coating fixed on wall with Aluminium. Framing of 25mm x 1.25mm thick at maximum 2'-0" c/c battenay etc. complete as directed. panelling as per design and instruction of Architect. Only Finished visible surface area shall be measured for payment.					
19	**ACM SHEET BANER WORK**	19.00	SMT			
	Supplying and fixing 4 mm thick aluminium composite panel of "Reel Bond" Euro Bond with 0.21 mm foil with 2' x 2' x 1.20 mm thick aluminium hollow section tray system with minimum 35 mm bending with silicon Dow Corning of GE seal proof ACP of approved indian make complete as per selection and direction of architect/client. Cutting of ACP sheet and bending will be carried out as per manufacturer specifications. Rate also including trap door shutter including hinges stoppers etc complete as directed. Design as per Bank standard Drawing and Architects instruction etc complete.					
20	**WALL BANER**	4.00	SMT			
	Providing and applying Wall paper approved by Architect / Bank's Engineer, wall paper basic price of Rs. 300/-(Rs Fifty Rupees)					
21	**ROLL LEDGE BLINDS**	14.00	SMT			
	Supplying and fixing Roller Blind Blackout of approved make and selected fabric of approved design and shed. (Basic price of Rs 150/-(Rs. Sixty)					
22	**FROSTED GLASS FILM**	13.00	SMT			
	Providing and Fixing Frosted polyester film of 3M (Scotchcal 7725 - 30) or equivalent make over glass surfaces as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification.					
23	**GRID FALSE CEILING**	85.00	SMT			
	Providing and Fixing of Armstrong Mineral Fibre Acoustical Suspended ceiling system with FINE FISSURED (MICRO LOOK) EDGE TILES With Armstrong Silhouette Exposed Grid					
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose.					
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per Rate specification					
24	**CHEMICAL BATHER FOR SEC FOR 3 MTS**	Unit 50	SMT			
	Providing and fixing Gypsum board 9.5mm thick false ceiling in Chemical Bather Room using Original Indian Gypsum board with original 24 sheet section of Gypsum UltraTEK Gypsum Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gypsum India.					
	After completion of work to certificate from Saint Gobin Gypsum Company shall be submitted along with bill stating that work is satisfactorily completed as per their specifications.					
	Note : (1) Rate includes making necessary cutouts for lighting fixtures, Grills, Diffusers etc. (2) Only Finished visible surface area not in RR and paint in SqM. (3) Only finished visible surface area shall be measured for payment.					
25	**STRIP OF BLUE HIGH GLOSS PU COATING OVER SMC TABLE**	4.00	SMT			
	Providing and Fixing of 9 mm thick MDF board strip with Blue Hilade High gloss Pu Coatings Instead of Gypsum Board for item No-1 over Transaction Area etc complete as per design and instruction. Only finished surface area shall be measured for payment.					
26	**CENTER TIMPOY**	2.00	NOS			

PRICE BID OF FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR

STATE BANK OF INDIA - SPSB BRANCH

Note: Rate should be inclusive of material,labour,tools, machinery, re-shifting, final disposal of debris, cleaning, cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.

Sln	Description	Qty.	Unit	Rate in Rupees	Rate in words	Amount
	Providing and making open box structure type Teapoy made out of 28 mm (25kg) thick plywood with all over 1.0 mm thick laminate finish provided with beveled & diamond polished edges 12mm thick glass top supported on SS stainlessle complete as directed. **(TEAPOY SIZE: 2'-0" x 1'-6"x 1'-0")**					
27	Removing and refixing of old tables (approx. 13 nos.) partitions (approx.25 SMT), storage cabinanes(approx. 15 SMT), Sole racks Chairs, Sofas, tendom Chairs, False ceiling, Grid Tiles including Grids available at our existing premises at Ground floor of SBI Ahmedabad and Local office premises situated infront (approx.200 feet) of the existing SPB Branch Ambawadi including all charges like transportation, lead - Lift etc complete.	1.00	Job			
28	Removing of existing laminate and refixing of new laminate as per selection for tables, partitions, Storage cabinnes	46.00	SMT			
	TOTAL COST "A"		**RS.**			