

N.O.W. - FURNISHING OF STATE BANK OF INDIA**MALERKOTLA MOTI BAZAAR BRANCH****PRICE BID FOR THE INTERIOR WORKS**

S.No.	DSR REF.	Item	Quantity	Units	Rate	Amount
		PANELING/PARTITON				
		Note: For the Paneling, Full height partitions and low height partitons the work measuremnt for costing shall be only of the plain visible surface, no extra cost for extrusions or extra frame work required as per drawing will be made. The work done above ceiling, below floor finish level or not directly visible shall not be measured.				
1		<u>WALL PANELING</u>				
		Providing and fixing panelling on column/wall. Framing shall consist of Heavy duty Aluminium Box Sections 50mmx25 mm with maximum spacing of @ 600mm c/c Both ways horizontally and vertically on the column/wall. This framing would be covered by 8mm thk. ISI Marked Ply finished in approved 1.0mm Th. Laminate of desired shade, design and gloss. Wooden molding, lipping etc. shall be provided wherever required as per drawing and deco painted in desired shade. The paneling shall have skirting and intermediate bands finished with laminate of desired shade, design and gloss. The work shall also include the cost of making cut-outs for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/telephone/Data cabling etc.	107.50	SQ.M		
		The work shall include making provisions for the shutters for the existing niches with 18mm thick ply finished with 1mm thick mica of desired shade/texture/finish with modular hinges, lock, magnet stopper and handle complete including painting/polishing the edges as per the direction of the enginee-in-charge.				
		MAKES:				
		ALUMINIUM: JINDAL, HINDALCO, NALCO OR EQUIVALENT				
		PLY: CENTURY/GREEN/DURO OR EQUIVALENT				

		MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
		ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
2		<u>FULL HEIGHT PARTITIONS:</u>				
		Providing and fixing wooden full height partition with following specifications:	96.91	SQ.M		
		(a) Supporting system comprising of aluminium 50mm x 50mm square sections @ max. 600mm c/c both horizontally and vertically. The frame shall be fixed rigidly at floor level and ceiling level wherever possible. The rate should also include necessary strengthening with additional members at doors and other openings.				
		(b) The partition shall have 8mm Plywood fixed on both sides with screws for the entire height of the partition and finished with approved 1.0mm Th. Laminate of desired shade, design and gloss on both sides. Wooden molding, lipping etc. as directed by Bank / architect shall be provided wherever required. The partition shall have skirting and intermediate bands finished with metallic laminate of desired shade, design and gloss.				
		(c) The full height partition shall be WITH OR WITHOUT 8mm clear float glass with etching fixed as per drawing with 75mm x 12mm Teak wood jamb/chaowkhat around glass opening and 12mm x 12mm teak wood beading for fixing of glass on both sides. As per the direction of Engineer-in-charge and design.				

	(d) The work to include providing and fixing of partly glazed wooden door shutters using 35mm readymade ISI flush door shutter with 1.0mm thick laminate of desired shade/textures and gloss as per drawing with teak wood frame of 75mm x 40mm. The door shall have 6mm thick teak wood lipping all around the edges. The door shall have vision panels with 8mm thick clear float glass with etching fixed with double 14mmx25mm thick teak wood moulding as per design. The exposed surface of wood shall be deco painted in desired shade. The door shall be complete in all respect with hardware handles, godrej 6-lever lock/night latch lock, door stoppers, 8" tower bolts, hinges etc all in brass.				
	MAKES:				
	ALUMINIUM: JINDAL, HINDALCO, NALCO OR EQUIVALENT				
	PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
	MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
	ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
	GLASS: SAIN GOBAIN/MODI GLASS/ASAHI FLOAT GLASS				
	LIPPING/MOULDING: CP TEAK FIRST CLASS				
	HARDWARE: OZONE/DORMA/GODREJ				
3	<u>LOW HEIGHT PARTITONS:</u>				
	Providing and fixing wooden low height partition with following specifications:	35.76	SQ.M		
	(a) Supporting system comprising of aluminium 50mm x 50mm square sections @ max. 600mm c/c both horizontally and vertically. The frame shall be fixed rigidly at floor level and ceiling level wherever possible. The rate should also include necessary strengthening with additional members at doors and other openings.				

		(b) The partition shall have 8mm Plywood fixed on both sides with screws for the entire height of the partition and finished with approved 1.0mm Th. Laminate of desired shade, design and gloss on both sides. Wooden molding, lipping etc. as directed by Bank / architect shall be provided wherever required. The partition shall have skirting and intermediate bands finished with metallic laminate of desired shade, design and gloss.				
		(c) The low height partition shall have 12 mm thick glass with etching as per design fixed with stainless steel heavy duty D-Profile 75mm in width of Ebco/godrej/Dorma/Ozone make at bottom and sides with top surface and other side free. All the edges of the 12mm glass shall be duly grinded/bevelled and polished.				
		e)The work to include providing and fixing of partly glazed wooden flap door shutters using 35mm readymade ISI flush door shutter with 1.0mm thick laminate of desired shade/textures and gloss as per drawing with teak wood frame of 75mm x 40mm. The door shall have 6mm thick teak wood lipping all around the edges. The door shall have vision panels with 8mm thick clear float glass with etching fixed with double 14mmx25mm thick teak wood moulding as per design. The exposed surface of wood shall be deco painted in desired shade. The door shall be complete in all respect with hardware handles, door stoppers, 8" tower bolts, hinges etc all in brass except for the door lock which shall be extra.				
		Note: The measurement for the costing of the ceiling will be done for the plain surface and no extra cost shall be paid for the steps or cope lighting. No extra cost shall be made for cutting the board for fixing of lights/airconditioner diffusers or return air grills/provision for conduits for cabling/ adjustment of the suspended grid as per the layout of the air-conditioners/ air-conditioning ducts or other fittings.				
		MAKES:				
		ALUMINIUM: JINDAL, HINDALCO, NALCO OR EQUIVALENT				

		PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
		MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
		ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
		GLASS: SAIN GOBAIN/MODI GLASS/ASAHI FLOAT GLASS				
		LIPPING/MOULDING: CP TEAK FIRST CLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
4		<u>GYPSUM BOARD FALSE CEILING WITH STEPS:</u>				
		Providing and fixing suspended false ceiling including steps and provision of cope lighting as per design with 12.5mm tapered edge Gypboard / 12mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consisting of a perimeter channel fixed round the perimeter. The intermediate channel at 1200mm c/c in the one direction and the ceiling section at 450mm c/c in the other direction to be connected by a connecting clip. The grid to be suspended with an adjustable strap hanger.	235.97	SQ.M		
		The grid to be suspended with an adjustable strap hanger at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts to be used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers to be screwed to the M/F ceiling sections with gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge including 2-3 coats of oil bound distemper , over a coat of primer.				
		MAKES:				
		GYPSUM BOARD: SAINT GOBAIN/USG BORAL/GYPSUM INDIA				
		CEILING SECTIONS: SAINT GOBAIN/USG BORAL/GYPSUM INDIA				

5		GRID FALSE CEILING:				
		Silhouette Grid False Ceiling:- Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries. The suspension system shall be the Armstrong Trulok Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions.	62.45	SQ.M		
		Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched at every 1200mm c/c maximum and 1200mm cross tee at every 600mm c/c maximum and 600mm cross tee at every 1200mm c/c maximum and wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of premier mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as per manufacturer's specifications.				
		MAKES:				
		GRID CEILING: ARMSTRONG/THAKKAR INDIA/UNIDUS INDIA				
		CEILING SECTIONS: ARMSTRONG/THAKKAR INDIA/UNIDUS INDIA				
6		<u>SWO COUNTERS: (AS PER NEW DESIGN AND SPECIFICATIONS)</u>				

	<p>(a) Providing and fixing at site SWO counters as per the new design and drawings. SWO counters to be made of 18mm thick commercial ply with 1mm thick laminate of desired shade, design and gloss on outer visible surfaces; single color on horizontal surface & two colors on vertical surfaces. The counter shall have a curved front made with flexible 18mm ply and provision of kobe lighting as per the drawings. Provision for 3" dia. Round /3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the counter. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have wooden keyboard rest of size 600mmx 270mm fixed on sliding telescopic channels of ebco/hettich/godrej. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.</p>	<p>9.15</p>	<p>M</p>		
	<p>(b) The counters shall have three self lockable drawers running on side mounting drawer slides (channels) of EBCO/godrej/Hettich make, made of 18mm thick ply with 1mm thick laminate of desired shade, design and gloss on front face & 3 nos. self locking drawer locks be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 18mm thick ply. All other surfaces i.e. inside / legsapce of table, inside of drawer/Cupboard shall be provided with 0.8mm thick laminate of desired shade, design and gloss, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The drawers shall have partitions for keeping currency notes as per drawing, complete in all respects including the required stainless steel hardware like handles, hinges etc. The counter shall have a CPU ledge made of 18mm thick commercial ply board on one side, complete as per drawing.</p>				

		Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost.				
		MAKES:				
		PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
		MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
		ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
		LIPPING/MOULDING: CP TEAK FIRST CLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
7		<u>GRAHAK MITRA COUNTER: (AS PER NEW DESIGN AND SPECIFICATIONS)</u>				
		(a) Providing and fixing at site GRAHAK MITRA counter 9'6" X 2'6" X 2'6" as per the new design and drawings. counter to be made of 19mm thick commercial ply with 1mm thick laminate of desired shade, design and gloss on outer visible surfaces; single color on horizontal surface & two colors on vertical surfaces. The counter shall have a curved front made with flexible 19mm ply and provision of kobe lighting as per the drawings. Provision for 3" dia. Round /3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the counter. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers.The counter shall have wooden keyboard rest of size 600mmx 270mm fixed on sliding telescopic channels of ebco/hettich/godrej. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.	1.83	RM		

		(b) The counters shall have three self lockable drawers running on side ON EACH END OF THE TABLE mounting drawer slides (channels) of EBCO/godrej/Hettich make, made of 19mm thick commercial ply with 1mm thick laminate of desired shade, design and gloss on front face & 3 nos. self locking drawer locks be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick ply. All other surfaces i.e. inside / legsapce of table, inside of drawer/Cupboard shall be provided with 0.8mm thick laminate of desired shade, design and gloss, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The drawers shall have partitions for keeping currency notes as per drawing, complete in all respects including the required stainless steel hardware like handles, hinges etc.The counter shall have a CPU ledge made of 19mm thick commercial ply on one side, complete as per drawing.				
		Note: The contractor to get the sample of the counter approved from the Architect before covering it with laminate without any extra cost.				
		MAKES:				
		PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
		MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
		ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
		LIPPING/MOULDING: CP TEAK FIRST CLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
8		OFFICER'S TABLES WITHOUT SIDE CREDENZA				

		(a) Providing and fixing at site Officer's table made of 18mm th. commercial ply with 1mm thick laminate of desired shade, design and gloss on outer visible surfaces; single color on horizontal surface & two color on vertical surfaces. . The front of the table top shall be projected and curved as per drawing. Provision for 3" dia. Round/3" square stainless steel of grade 304 cable manager for computer / electrical cables at appropriate place, will be made in the top surface of the table. Esteem Biege wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers.				
		The counter shall have a wooden keyboard rest of size 600mm x 270mm made with 18mm ply fixed with sliding telescopic channels of ebco/godrej/hettich make. The work shall also include provision of foot rest made with wooden member of section 3" x 5" along the leg space.				
		(b) There shall be provision of one storage cabinet 1'3" wide. The frame shall be made with 18mm thick ply. The cabinet shall have one lockable drawer running on side mounting drawer slides (channels) of EBCO make & one cupboard with shutter beneath the drawer, made of 18mm thick commercial ply board with 1mm thick laminate of desired shade, design and gloss on front face, handle / knob and magnetic catcher shall be provided on one side of the table as per layout. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 18mm thick ply board.				
		All other surfaces i.e. inside / legsapce of table, inside of drawer / cupboard shall be provided with 0.8mm thick laminate of desired shade/design and gloss, and wood lipping / beading shall be PU polished with matching pigment/deco painted in desired colour. The table shall have a CPU ledge made of 18mm thick ply on one side, complete as per drawing.				
		MAKES:				
		PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
		MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				

		ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
		LIPPING/MOULDING: CP TEAK FIRST CLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
a)		3'0" x 6'0" x 2'6"	1.00	no.		
b)		5'-0" x 2'-6" x 3'-6"	4.00	no.		
9		<u>SIDE CREDENZA 1.22 X 0.46 X .76</u>				
		Side credenza made of 18mm thick commercial ply frame and 6mm thick plywood on back side & 1mm thick laminate on top horizontal surface & one vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer compartment 16" wide outer to outer, containing three drawers vertically running on side mounting drawer slides(channels) of EBCO/godrej/hettich make. The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 18mm thick ply board. The remaining part of the credenza will have open cupboard with shutter of 18mm ply finished with 1mm thick mica of approved shade/design/gloss/texture and one shelf. All the internal surfaces shall be finished with 0.8mm thick mica of desired shade, design, gloss and the exposed wood shall be deco painted/malamine polished in desired shade.	1.00	no.		
		MAKES:				
		PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
		MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
		ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
		LIPPING/MOULDING: CP TEAK FIRST CLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
10		<u>SIDE CREDENZA 1.07 X 0.38 X 0.76:</u>				

		Side credenza made of 18mm thick commercial ply frame and 6mm thick plywood on back side & 1mm thick laminate on top horizontal surface & one vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have drawer compartment 14" wide outer to outer, containing three drawers vertically running on side mounting drawer slides(channels) of EBCO/godrej/hettich make.The sides of the drawer shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 18mm thick ply. The remaining part of the credenza will have cupboard with shutters of 18mm thick ply and finished with 1mm thick mica of approved shade/texture/gloss/design and one shelf. All the internal surfaces shall be finished with 0.8mm thick mica of desired shade, design, gloss and the exposed wood shall be deco painted/malamine polished in desired shade.	4.00	no.		
		MAKES:				
		PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
		MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
		ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
		LIPPING/MOULDING: CP TEAK FIRST CLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
11		LOW HEIGHT STORAGE CABINETS/BACK STORAGE: (2'6" HIGH)				

	(a) Providing and fixing storage cabinets of size 2'6" (High) x 16" (Deep) along the walls/partitions, as per interior drawings, using 18mm ply for carcass, shutters, vertical and horizontal partitions, 6mm ply for the back and 1mm High Gloss laminate of approved shade on vertical and horizontal visible surfaces. The shutters shall be overlapped on the carcass and shall be provided with EBCO hinges. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the board shall be provided with wooden lipping 18mm x 3mm, duly PU poished/deco painted in desired shade. The inner surface shall be provided with 0.8mm thick laminate of desired shade, design and gloss. The cabinet shall be complete with handles, knobs, locks and magnet catchers etc. to the satisfaction of the Architect/Engineer.	26.98	RMT		
	MAKES:				
	PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
	MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
	ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
	LIPPING/MOULDING: CP TEAK FIRST CLASS				
	HARDWARE: OZONE/DORMA/GODREJ				
12	12MM TOUGHENED GLASS FOR FRONT AND SIDE OF COUNTERS :	9.34	SQ.M		
	Providing and fixing 12 mm thick, clear plain toughened glass of approved pattern fixed in vertical position at counter front and as curved glass extension of low height partition as per drawing, fixed on wooden partitions with superior quality stainless steel patch fittings of ebco/godrej/ozone. An opening as per the drawing at the bottom for transaction shall be provided in case of glass in front of the transaction counter. All the edges of the glass shall be grinded/bevelled and polished. The glass shall also be etched as per the design. Glass area with maximum height shall be measured for the purpose of payment. The work shall be carried out as per drawings.				
	MAKES:				

		GLASS: SAIN GOBAIN/MODI GLASS/ASAHI FLOAT GLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
13		<u>12MM THICK TOUGHENED GLASS DOORS WITH ETCHING:</u>				
		Providing and fixing in position 12mm clear float toughened Glass for naked glass door. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., Ozone/ebco/godrej or approved equivalent make floor spring with its accessories, top pivot, center lock, 450mm glass door handles etc., along with etching with sand blasting as per design and drawing. The maximum size of each glass shall be as per the drawing or the direction of the Engineer-in-charge. The rate is for a finished item of work etc., complete as directed.	5.20	SQ.M		
		MAKES:				
		GLASS: SAIN GOBAIN/MODI GLASS/ASAHI FLOAT GLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
14		<u>12MM THICK TOUGHENED GLASS PARTITIONS WITH ETCHING:</u>				
		Providing and fixing in position 12mm clear float toughened Glass partition with patch fittings for the full height glass partitions as per the direction of the engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughen the same.	30.76	SQ.M		

		The cost to include all hardware (PATCH FITTINGS etc) required of Ozone/EBCO/GODREJ or approved equivalent make viz., single corner patch, top and bottom corner patch etc. or as per the direction of the engineer-in-charge, along with etching with sand blasting as per design and drawing. The maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm as per the site requirement. The rate is for a finished item of work etc., complete as directed.				
		The cost to include the cost of bevelling and smoothing of the exposed edges of the glass.				
		MAKES:				
		GLASS: SAIN GOBAIN/MODI GLASS/ASAHI FLOAT GLASS				
		HARDWARE: OZONE/DORMA/GODREJ				
15		<u>HDHMR BEVELLED EDGES PANELED PANELING WITH GROVES</u>				
		Providing and fixing 19mm HDHMR board bevelled edge panelled paneling with groves as per the desired design and drawing. The paneling shall be deco painted in desired shade and design. The work shall further include providing and fixing metallica 1mm thick mica in desired shade as highlighter. The work shall be complete including the required sundries and adhesive for fixing the paneling over the wall. furthermore, the work shall also include providing and fixing profile lights in the paneling as per the instruction of the engineer-in-charge.	12.64	SQ.M		
		MAKES:				
		HDHMR BOARD: CENTURY/GREEN/ACTION TESA OR EQUIVALENT				
16		<u>WOODEN BOXING FOR THE ELECTRICAL PANEL</u>				

	Providing and fixing at site wooden boxing for the electrical panel as per the design and drawing. The carcass shall be made of 18mm commercial ply with 1mm thick LAMINATE of desired shade, design and gloss on the outer surface. The carcass shall have intermediate band and skirting of 1mm thick metallic Laminate of desired shade, design and gloss. The shutter shall be mounted on the SS Piano hinges and provided with magnetic catcher, lock and tower bolts as required etc. All the visible edges of board shall be provided with 4mm thick teak wood lipping, duly DECO PAINTED. All interior surfaces and back of shutters shall be provided with 0.8mm thick mica. the cabinet shall be complete with all necessary hardwares like locks, handles, catchers, towerbolts etc.	9.20	SQ.M		
	The cost shall include provision and fitting of the stainless steel Jali of grade 304A for the ventillation of the panel. The cost shall include the cost of cutting of the shutter and fitting with necessary screws as per the drawing.				
	MAKES:				
	PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
	MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
	ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
	LIPPING/MOULDING: CP TEAK FIRST CLASS				
	HARDWARE: OZONE/DORMA/GODREJ				
17	<u>WRITING DESK AND THE VOUCHER STAND</u>				

	Providing and Fixing Writing desk and voucher stand 1.2m wide, 1.05m high and 30cm thick made with the frame of 18mm thick ply. The back shall be made with 6mm thick ply. The desk shall have four open portions for voucher stand 200mm high with top of 12mm thick toughened glass to be used as wiring desk. The lower portion shall have two independent cabins 75cm high provided with 18mm thick shutter with slits for sliding the voucher or the cheques as per the direction of the engineer-in-charge. All the exposed surfaces shall be finished with 1mm thick mica of approved shade/texture/gloss as per the direction of the engineer-in-charge. All the exposed edges shall be provided with 4mm thick lipping. The internal surfaces shall be provided with 0.8mm Mica. The work shall also include all the sundries and material required to fix the same on the wall as per the direction of the Engineer-in-charge.	1.00	no.		
	MAKES:				
	PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
	MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
	ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
	LIPPING/MOULDING: CP TEAK FIRST CLASS				
	HARDWARE: OZONE/DORMA/GODREJ				
18	<u>FALSE CEILING FINISHED WITH LAMINATE</u>				
	Same as Gypsum false ceiling but instead gypsum boards providing, making, and fixing 12 mm thick. BWR Grade ply, and additional 6-8mm ply in layers with molding of approved design shall be fixed as per drawing or as directed by Architect, with decorative molding patty. The plywood should be finished with 1 mm thick. Laminate of approved colour(wooden finish) and quality.	23.93	SQ.M		
	MAKES:				
	PLY: CENTURY/GREEN/DURO OR EQUIVALENT				
	MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT				
	ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT				
	LIPPING/MOULDING: CP TEAK FIRST CLASS				

		HARDWARE: OZONE/DORMA/GODREJ				
19		HYDRAULIC DOOR CLOSER:				
		Providing and fixing silver color (or matching with color scheme as per site) hydraulic door closer Hyper / Everrite ISI marked make, to doors complete in all respects.	13.00	NOS		
		MAKES:				
		HARDWARE: OZONE/DORMA/GODREJ				
20		Dismantling the existing walls/rcc/floor/furniture/wiring etc. complete, providing the required supports in terms of steel girders/rcc beams and making good the surfaces damaged or as per the direction of the engineer-in-charge. The work shall also include removal of the same to an appropriate location as permissible to the local authorities or as per the direction of the Engineer in-charge. (Note: The amount is expected after deduction of amount to be deducted for the buyback of the existing furniture)	1.00	LS		
ESTIMATE FOR THE INTERIOR WORKS FOR THE WEALTH HUB						
1		WALL/ COLUMN PANELING WITH LAMINATE FINISH WEALTH HUB				

	<p>WALL/ COLUMN PANELING WITH LAMINATE FINISH.</p> <p>Wall paneling made from 25 x 25 x 1.00 mm thick hollow aluminum sections, over which BWR grade ply of 10 mm shall be fixed and additional 6-8mm ply in layers to create grooves as per the design in the drawing or as directed by Architect, with decorative molding patty on the edges.</p> <p>Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under:-</p> <p>(i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.</p> <p>(ii) Panel Finishing:- Providing & fixing 9 mm thick approved make BWR plywood and additional 6-8mm ply in layers to create grooves as per the design to Aluminum framework finished with 1.00 mm thick approved quality and shade laminate, using approved adhesive, in approved pattern & design, including providing grooves, decorative moldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge.</p>	<p>20.49</p>	<p>SQ.M</p>		
--	---	---------------------	--------------------	--	--

		<p>(iii) Providing approved quality, seasoned, full length, Teak Wood molding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as directed by the Engineer-in-charge at site.</p> <p>(iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p> <p>(v) Applying 2 or more coats of melamine polish to exposed edges of paneling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete.</p>				
		<p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank.</p> <p>(c) Laminate:- Dorby Mica, Greenlam/Century/Archid / Aerolam or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p> <p>Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear paneling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sqm.</p>				
2		<u>FULL HEIGHT SOLID / PARTLY GLAZED WOODEN PARTITION WITH BOTH SIDES LAMINATE</u>				

	<p>Providing & fixing in position 70mm thick +/- 2mm solid / opaque partly glazed full height wooden partitions with 1200 mm high glass middle panels finished with laminate on both sides comprising as under:-</p> <p>(i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium sections not exceeding 600 mm c/c bothways (horizontal and vertical) except in glazed portion of partition, fixed rigidly on floor, wall / column & ceiling. Spacing of frame members may vary to the nearest possible extent as per site conditions.</p> <p>(ii) Plywood skin:- Providing & fixing 8mm thick PLY and additional 6mm thick HDHMR boards on both sides of the framework to create grooves in align to the paneling.</p> <p>(iii) Finishing:- Providing 1.00 mm thick, approved quality and shade laminate, on both sides of partitions in approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approve quality adhesive complete.</p>	<p>15.89</p>	<p>SQ.M</p>		
--	--	---------------------	--------------------	--	--

	<p>(iv) Providing and fixing 12mm thick approved make 1200 mm high toughened Glass panels in the middle panels of partitions using second class seasoned teak wood moulding of finished sectional size 75mmx12/15 mm all-round, complete as per drawing and as directed at site.</p> <p>(iv) Making suitable cutouts/openings/channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site.</p> <p>(v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full-length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site.</p> <p>(vi) Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door openings, cutouts etc. complete.</p> <p>(vii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.</p>				
	<p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</p> <p>(b) MDF Board:- Greenply, Century, Samrat or equivalent approved by the Bank.</p> <p>(c) Laminate:- Greenlam/Century/Archid or equivalent approved by the Bank.</p> <p>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</p> <p>Mode of measurement:- Though aluminium frame shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sqm</p>				
3	GYPBOARD FALSE CEILING				

	<p>Providing and fixing false ceiling with cove at all height including providing and fixing of frame work made galvanized M.S. sections as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction,</p>	29.74	SQ.M		
	<p>including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval.</p> <p>Fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of Engineer in charge including cost of painting the false ceiling with two coats of acrylic emulsion paint over a cost of putty</p>				

		12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) to be used. Same as Gypsum false ceiling but providing, making, and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.				
4		<u>MINERAL FIBRE GRID TILE CEILING:</u>				
		Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc.	5.95	SQ.M		

		Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. GI Metal Ceiling Lay in perforated Tegular edge global white colour tiles of size 595x595 mm and 0.5 mm thick with 8 mm drop; made of GI sheet having galvanizing of 100 gms/sqm (both sides inclusive) and 20% perforation area with 1.8 mm dia holes and having NRC (Noise Reduction Coefficient) of 0.5, electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending and perforation, and backed with a black Glass fibre acoustical fleece.				
5		<u>FALSE CEILING FINISHED WITH LAMINATE</u>				
		Same as Gypsum false ceiling but instead gypsum boards providing, making, and fixing 12 mm thick. BWR Grade ply, and additional 6-8mm ply in layers with molding of approved design shall be fixed as per drawing or as directed by Architect, with decorative molding patty. The plywood should be finished with 1 mm thick. Laminate of approved colour(wooden finish) and quality.	7.95	SQ.M		
6		<u>OFFICER'S TABLES WITHOUT SIDE CREDENZA WEALTH HUB 5'0" X 2'6" X 2'6"</u>				

	<p>Supplying and installation of Table as per the following description and as designed by the Architect:</p> <p>Table Top: Providing and fixing 19 mm thick IS 303 BWR grade plywood with 4mm thick Teak veneer with melamine finish with necessary intermediate support. Table top shall be supported by 18 mm thick BWR grade ply wood with plywood framing. The top of the table shall be provided with equal sized 12mm thick toughened glass with polished edges. The top level of the glass shall be 750mm. Apron (Modesty Panel) made from 18mm thick BWR grade plywood finished with 1mm laminate.</p> <p>Table sides, back & intermediate panels (at 500mm from each side) made from 18 mm thick MR ply wood finished with 1mm laminate for exposed surfaces (4 faces) and 0.8 mm thick laminate for inner surfaces shall be provided as per drawing.</p>	2.00	no.		
	<p>Drawer / Storage cabinet: Box of 400 X 750 X 720 mm shall be provided using 18 mm thick BWR grade plywood. Each Drawer Fascia made out of 18 mm thick plywood and all sides of drawers be made of 12 mm thick plywood & bottom of drawers shall be of 8 mm thick BWR grade plywood. The drawer unit box and individual drawers to be fixed with 1mm laminate on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles C-type for each drawer. The front ply of the drawers to be overlapping the frame.</p>				

	<p>Computer Keyboard (550 x 375 mm) of metal / PVC of approved make shall be provided. Footrest of 38 x 76 MM T.W members shall be provided. All internal surface will have min. 0.80 mm thick balancing laminate. Table shall have stand of 18 mm ply finish with 1 mm thk. Laminate of size 400 x 375 mm for keeping CPU and PVC cable Manager shall be provided in the cutouts on the tabletop.</p> <p>All edges to be provided & fixed with teak wood lipping patti finished with melamine polish. All the surface without teak veneer / laminate / balancing laminate shall be lacquered polished of approved shade.As per drawing and instruction of Architect/Bank, work to be completed.</p> <p>Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.</p>				
7	<u>CLERICAL TABLE WITHOUT SIDE CREDENZA WEALTH HUB 4'0" X 2'6" X 2'6"</u>				
	<p>Supplying and installation of Table as per the following description: Tabletop shall be made from 19 mm thick IS 303 BWR grade plywood with 4mm thick Teak veneer with melamine polish with necessary intermediate support. Tabletop shall be supported by 19 mm thick BWR grade plywood with wooden framing. The top of the table shall be provided with equal sized 12mm thick toughened glass fixed.Apron (Modesty Panel) made from 19 mm thick BWR grade plywood finished with 1mm laminate & groove pattern as per drawing. Table sides & intermediate panels (at 50cm from each side) made from 19 mm thick BWR grade plywood finished with 1mm thick laminate for all surfaces shall be provided as per drawing.</p>	1.00	no.		
	<p>(Removed drawer cabinet in this version as there will be no space left for a person to sit)</p> <p>Computer Keyboard (550 x 375 mm) of metal / PVC of approved make shall be provided. Footrest of 38 x 76 MM T.W members shall be provided.</p>				

		<p>All internal surface will have min. 0.80 mm thick balancing laminate. Table shall have stand of 18 mm ply finish with 1 mm thk. Laminate of size 400 x 375 mm for keeping CPU and PVC cable Manager shall be provided in table top.</p> <p>All edges to be provided & fixed with teak wood lipping patti finished with melamine polish.As per drawing and instruction of Architect/Bank, work to be Completed.</p> <p>Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.</p>				
8		MEETING ROOM TABLE				
		<p>Providing and placing in position Meeting Room tables of approx. size 1200mm in diameter (size to be considered based on site conditions).</p> <p>Providing & Fixing Conference Table of shape as per design made from 50mm X 40mm T. W. Wood framework 450mm center to center both ways for tabletop covered with 12mm thick BWR ply for bottom, 19mm thick BWR ply for top, table stand and base with necessary 50mm X 40mm vertical supports. All exposed surfaces shall be finish with approved color 1 mm thk. laminate. All internal surfaces to be finished with 0.8mm thick laminate. All edges to be provide with TW lipping patti finished with melamine polish. Rate shall be inclusive of Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, mikes carting away unserviceable materials out of the compound,cleaning the site etc. complete as per the detail drawing and instruction of Engineer.</p> <p>Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.</p>	1.00	no.		
9		SIDE/ REAR CREDENZA WEALTH HUB- For officer and clerical staff table				

	a	Low Height Cupboard with Laminate Finish: Providing & fixing Low Height Storage Cupboard of 750 height and 450mm deep. Outer exposed structure with to be made with 19mm BWR ply as per IS 303 and back side using 8mm BWR grade ply. All shutters to be made from 25 mm thk BWR Ply and shelves to be made with 19 mm thk.BWR ply.The top potion of the side and rear credenza to be finished with approved veneer and finished with melamine polish. All the other internal and external surfaces to	-	no.		
		be finished with 1mm laminate of approved shade and All edges to be provide with TW lipping patti finished with melamine polish. Shutters will have concealed handle with wooden groove finished with approved shade of melamine polish as per drawing, magnetic catchers, self-closing SS hinges, locks (Godrej/ Hettich/Haffele), SS towerbolts etc. All shutters to be made overlapping the frame Only front elevation will be considered for area calculation. As per drawing and instruction of Architect/Bank, work to be Completed Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.				
	b	Same as above- but finished externally with approved quality veneer with melamine polish complete instead of 1mm laminate to match with design of tables.	2.00	no.		
10		<u>STORAGE CUPBOARDS</u>				

	A	<p>Providing and placing in position storage cupboard of 450 mm depth, made out of 18 mm thick BWR grade ply.</p> <p>Full Height Cupboard with Laminate Finish: Providing & fixing full Height Storage Cupboard of 2100mm height and 450mm deep. Outer exposed structure with to be made with 19mm BWR ply as per IS 303 and back side using 8mm BWR grade ply.All shutters and shelves to be made with 19 mm thk. BWR plywood. All internal and external surfaces to be finished with 1mm laminate of approved shade and make.All edges of the cupboard should be edge banded using PVC edge banding tape of approved shade.Shutters to be provided with S.S. 200mm handles, magnetic catchers, self-closing SS hinges, locks (Godrej/ Hettich/Hafele), SS tower bolts etc. All shutters to to be made overlapping the frame. Only front elevation will be considered for area calculation.</p> <p>Plywood Make: Greenply, Century, Duro or equivalent approved by the Bank.</p>	-	no.		
	B	Same as above- but finished externally with approved quality veneer and PU coating finish over melamine polish complete instead of 1mm laminate.	3.35	SQ.M		
11		<u>LOW HEIGHT STORAGE CABINETS/BACK STORAGE WEALTH HUB: (0.90 HIGH)</u>				

		(a) Providing and fixing storage cabinets of size 3'0" (High) x 16" (Deep) along the walls/partitions, as per interior drawings, using 19mm board for carcass, shutters, vertical and horizontal partitions, 6mm ply for the back and 1mm laminate of approved shade on vertical and horizontal visible surfaces except for the top which shall be provided with veneer of approved quality and shade finished with melamine polish with PU Coating as per manufacturer's specifications. The shutters shall be overlapped on the carcass and shall be provided with Hettich /Godrej/Ozonehinges. The width of the shutter shall be between 12" to 15" as per the site conditions. All the exposed edges of the board shall be provided with wooden lipping 19mm x 3mm, duly PU polished/deco painted in desired shade. The inner surface shall be provided with 0.8mm thick laminate of desired shade and design. The cabinet shall be complete with handles, knobs, locks and magnet catchers etc. to the satisfaction of the Architect/Engineer.	5.02	SQ.M		
12		FULLY GLAZED DOOR				

	<p>Providing and fixing position 12 mm fully glazed toughened glass door, single/ double shutter, of approx. size 900/ 1500 x 2100/2400 mm</p> <p>Providing and fixing in position frameless glass door shutter made using 12mm thick toughened glass fixed to the partition (glazed / solid / gypsum partitions) using heavy duty floor spring with pivot of approved make including necessary cutting of floor and making the surface good to its original position including all necessary Patch fittings of approved make and fixtures & hardwares.</p> <p>Approved make: DORMA Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Handle - TG DIH600 - 600mm length) or equivalent brand fittings from Hettich / Hafele / as per sample approved by the Bank. Rate should also include providing film as per design/ instructions of Bank.</p> <p>Mode of Measurement: Door opening size shall be measured.</p>	4.23	SQ.M		
13	<u>FULL HEIGHT FULLY GLAZED PARTITION WITH 12MM TOUGHENED GLASS UPTO 7' LEVEL WITH SOLID PARTITION ABOVE 7' LEVEL</u>				

	<p>Providing & fixing full height glazed partition with 12mm Toughened glass of approved make up to 7' level height with solid partition above 7'-0" level up to false ceiling bottom. The glazed panels shall be fixed to the existing floor and false ceiling with all necessary SS brackets (D, C or U type) Vertical joints between the glass panels shall be sealed with suitable transparent sealant.</p> <p>The solid partition above 7'-0" level shall be made with aluminium framework of size 63mm X38.10mm X1.47 mm (0.780Kg /mtr) box section. The spacing of the Horizontal and Vertical members are approximately 600mm c/c (maximum) and the top of the frame shall be fixed to the RCC slab bottom.</p> <p>The exposed surfaces on both sides of framework are covered with 8mm BWR ply and additional 6mm HDHMR Board to provide grooves aligned with the grooves in the paneling. The exposed surfaces shall be then finished with 1.0mm thick laminate as per direction.</p> <p>Providing, placing in position & erecting full height partition in desired shape, framework shall be of 50 x 50 x 1.5 mm thick aluminum square section placed at 500 mm c/c both ways or as directed.</p>	22.96	SQ.M		
14	<u>MDF FLUTED WOODEN PANELLING</u>				

	<p>Wall paneling made from framework of 25 x 25 x 1.20 mm thick hollow aluminum sections spaced 600mm c/c, over which MDF fluted wooden panel of 10mm +/- 2mm shall be fixed as per the design in the drawing or as directed by Architect.</p> <p>(i) Framework:- Made out of 25 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb.</p> <p>(ii) Panel Finishing:- Providing & fixing 10mm +/- 2mm thick approved MDF Wooden Panelling fixed on the aluminum sections with tongue and groove joints in line and level.</p>	5.86	SQ.M		
	<p>(iii) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p>				
	<p>iv) The Duco paint shall be of approved make and shade. The surface to be painted shall be first prepared smooth by applying proper grade of sandpaper/water-paper and then if any pores are noticed the same shall be filled with approved quality synthetic filler agent. The complete surface shall be then applied an even coat of sealer putty and permitted to dry. The surface shall be again grinded smooth and even using appropriate grade of water-paper. When the surface is properly smooth and leveled without any pores or cracks the same shall be spray painted with approved quality Duco paint. The adjoining surfaces which are not to be painted with this application shall be suitably masked using appropriate masking tape. The paint shall be permitted to dry at room temperature and attain smooth lustrous finish.</p>				

		iv) The Duco paint shall be of approved make and shade. The surface to be painted shall be first prepared smooth by applying proper grade of sandpaper/water-paper and then if any pores are noticed the same shall be filled with approved quality synthetic filler agent. The complete surface shall be then applied an even coat of sealer putty and permitted to dry. The surface shall be again grinded smooth and even using appropriate grade of water-paper. When the surface is properly smooth and leveled without any pores or cracks the same shall be spray painted with approved quality Duco paint. The adjoining surfaces which are not to be painted with this application shall be suitably masked using appropriate masking tape. The paint shall be permitted to dry at room temperature and attain smooth lustrous finish.				
15		<u>CENTER TABLE (3'-0" X 2'-0" Oval / Rectangular)</u>				
		Providing and supplying in position oval or rectangular centre table to be made out of 2" X 2" teakwood frame including 12mm thk clear glass top with bevelled edges including bottom glass shelf with etching etc complete. The rate shall also include SS lining design to the teakwood frames including all the necessary hardware, fittings, fixtures as per manufacturers specifications complete.	1.00	NOS		
16		<u>BACK PAINTED GLASS + LOGO</u>				
		Back painted glass (Lacquer Glass) paneling: Providing and fixing Back painted (Lacquer Glass) over the one side of the wooden partition with required sundries and accessories.	7.25	SQM		
		The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards etc., including providing necessary wooden/aluminum section members support at cutouts, providing scaffolding for execution of work at all heights, complete as per drawings and as directed by the Engineer-in-charge at site.				

17		LOGO:				
		Logo:- Providing and fixing in position with SS studs or as directed laser cut Logo as per design made from 18 mm MDF board (exterior grade) and and 10 inch -12 inch high and finished with PU metallic paint as directed complete. The logo shall read as " SBI EMERALD GOLD" as per the approved font and design.	1.00	NOS		
		WOODEN FLOORING + SKIRTING				
18		Providing and placing in position wooden laminate flooring with planks of size not less than 1200 mm X 190 mm (with unlink panels / tongue-groove locking arrangement) having a 0.2 mm thick top abrasive layer followed by decorative layer upon HDF (high density fiberboard) substrate core over raisin saturated backing layer installed using tongue-groove system over 2 mm thick underlayer of polyurethane foam on 250-micron polythene sheet over a smooth, flat, hard and free from moisture floor surface complete in all respect with required accessories like end profile, transition profile, reducer 'T' profile etc. and preparation of base including all other incidental works as per direction & satisfaction of Architect in charge. Cost of Laminate Floor Accessories, Skirting, End edge, T- molding, Reducer shall have to be added in the cost, wherever required. Grade :- AC4	32.53	SQ.M		
19		POLYESTER FILM OVER GLAZED PARTITIONS:				
		Polyester Film over glazed partitions: Providing and fixing in position high impact resistant Polyester Films of approved design & pattern, which once installed on glass, give additional strength to glass, reduce glare & prevent glass from splintering on impact. thickness not less than 4 Mil (100 mic.) or 7 Mil (175 mic.)	21.15	SQ.M		
20		ROLLER BLINDS				

	<p>Providing, fabricating and fixing vertical roller blinds of approved make preferably of “Vista Levelor” with a woven made acrylic coated fabric of 100% polyester of thickness 0.50 – 0.60 mm (+/- 5% tolerance) with the main properties like resistance to Cracking & Fraying, dust repellence, UV proof and virtually maintenance free along with the Vista accessories of like Head rail , Roller tube Idler, Bottom rail, chain, matching colour installation brackets etc. including all fixtures and fittings of Vista like Rainbow curtain rods with electric resistance welded MS pipe having a corrugated virgin PVC extrusions reinforced to minimize friction, finials and along with standard anchoring arrangements etc. all complete done in workmanlike manner as per the approved design, colour and including necessary scaffolding as directed.</p>	5.95	SQ.M		
	Total Value of Works				
	Note: CONTENGENCIES AND GST as aplicable shall be extra				