## N.O.W. - FURNISHING OF STATE BANK OF INDIA

## **BHUMATI BRANCH**

## PRICE BID FOR THE CIVIL WORKS.

C N:	DCD DEE	PRICE BID FOR THE CIVIL WORKS.	<u>-</u>	11*	D-1	A
S.No.	DSR REF.	Item	Quantity	Units	Rate	Amount
1		VITRIFIED TILE FLOORING 600MM X 1200MM				
1	11.41	Providing and laying vitrified floor tiles in different sizes	96.10	SQM		
		(thickness to be specified by the manufacturer) with water	55.25			
		absorption less than 0.08% and conforming to IS: 15622, of				
		approved make, in all colours and shades, laid on 20mm thick				
		cement mortar 1:4 (1 cement : 4 coarse sand), jointing with				
		grey cement slurry @ 3.3 kg/ sqm with 3mm thick groves all				
		around including grouting the joints with epoxy of matching				
		pigments etc., complete. (Italian Marble Shade Digital Tiles from				
		Johnson and Johnson, Kajaria, Somany etc)				
	11.41.2	Size 600mm x 1200mm				
		NOTE: THE COST SHALL INCLUDE ANY KIND OF REQUIRED				
		ADDITIONAL CONCRETE/CEMENT MORTAR OR FILLING. NO				
		EXTRA COST SHALL BE PAID FOR ANY ADDITIONAL WORKS FOR				
		LEVELING THE SURAFCE FOR NEW TILING WORKS.				
		MAKES:				
		VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT				
		AND EQUIVALENT.				
		CEMENT: ULTRATECH/ACC/AMBUJA				
2		VITRIFIED TILE FLOORING 400MM X 400MM				
-	11.41	Providing and laying vitrified floor tiles in different sizes	13.29	SQM		
		(thickness to be specified by the manufacturer) with water		J		
		absorption less than 0.08% and conforming to IS: 15622, of				
		approved make, in all colours and shades, laid on 20mm thick				
		cement mortar 1:4 (1 cement : 4 coarse sand), jointing with				
ı		grey cement slurry @ 3.3 kg/ sqm including grouting the joints				
		with white cement and matching pigments etc., complete.				
		(PAVER ANTISKID ROUGH TEXTURE 12MM THCIK Tiles from				
		Johnson and Johnson, Kajaria, Somany etc)				
	11.41.2	Size 400mm x 400mm				
		MAKES:				
		VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT				
		AND EQUIVALENT.				
		CEMENT: ULTRATECH/ACC/AMBUJA				
3		EXCAVATION				
	2.6	Earth work in excavation by mechanical means (Hydraulic				
		excavator)/ manual means over areas (exceeding 30 cm in				
		depth, 1.5 m in width as well as 10 sqm on plan) including				
		getting out and disposal of excavated earth lead upto 50 m and				
		lift upto 1.5 m, as directed by Engineer-in charge.				
	2.6.1	All kinds of soil	4.52	CUM		
4		HALF BRICK MASONARY				
-	6.12	Half brick masonry with common burnt clay F.P.S. (non				
		modular) bricks of class designation 7.5 in superstructure :				
	6.12.2	cement mortar 1:4 (1 cement : 4 coarse sand)	33.04	SQ.M		
		MAKES:				
		BRICKS: FIRST CLASS BRICKS				
		CEMENT: ULTRATECH/ACC/AMBUJA	-			
		THE PRICE MACONARY				
5	<i>C A</i>	FULL BRICK MASONARY  Brick work with common burnt clay F.P.S. (non modular) bricks				
	6.4	, , ,				
		of class designation 7.5 in foundations and superstructure				
		above plinth level up to floor V level and in foundations				
		(including the cost of back-filling as required) in all shapes and				
		sizes in :		L		

1		Ta		1 1	1
	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	2.26	cu.m	
		MAKES:			
		BRICKS: FIRST CLASS BRICKS			
		CEMENT: ULTRATECH/ACC/AMBUJA			
6		PLASTERING			
	13.1	12 mm cement plaster of mix :			
	13.1.1	1:4 (1 cement: 4 fine sand)	54.07	SQ.M	
		MAKES:			
		CEMENT: ULTRATECH/ACC/AMBUJA			
7	13.2	15 mm cement plaster on the rough side of single or half brick			
		wall of mix :			
	13.2.1	1:4 (1 cement: 4 fine sand)	54.07	SQ.M	
	13.2.1	MAKES:	34.07	JQ.IVI	
		CEMENT: ULTRATECH/ACC/AMBUJA			
		WALL (FLOOR THES			
8		WALL/FLOOR TILES			
	11.36	Providing and fixing Ist quality ceramic glazed wall tiles	36.20	SQ.M	
		conforming to IS: 15622 (thickness to be specified by the			
		manufacturer), of approved make, in all colours, shades except			
		burgundy, bottle green, black of any size as approved by			
		Engineer- in-Charge, in skirting, risers of steps and dados, over			
		12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse			
		sand) and jointing with grey cement slurry @ 3.3kg per sqm,			
		including pointing in white cement mixed with pigment of			
		matching shade complete. SIZE 1'0" X 2'0"			
		MAKES:			
		VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT			
		AND EQUIVALENT.			
		CEMENT: ULTRATECH/ACC/AMBUJA			
		CEMENT: CETTATECT/ACC/AMBOSA			
9	11.37	Providing and laying Ceramic glazed floor tiles of size 300x300	6.51	SQM	
9	11.57	mm (thickness to be specified by the manufacturer) of 1st	0.51	JQIVI	
		quality conforming to IS: 15622 of approved make in colours			
		such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm			
		thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing			
		with grey cement slurry @ 3.3 kg/sqm including pointing the			
		joints with white cement and matching pigment etc., complete.			
		MAKES:			
		VITRIFIED TILES: KAJARIA, JOHNSON AND JOHNSON, ORIENT			
		AND EQUIVALENT.			
		CEMENT: ULTRATECH/ACC/AMBUJA			
10		PUBLIC HEALTH			
	17.78	Providing and fixing white vitreous china single body (cistern	2.00	NO.	
		and seat attached) with dual flush fitting, of flushing capacity 3			
		litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover,			
		and cistern fittings, nuts, bolts and gasket etc complete.			
		MAKES:			
		WC : KEROVIT/HINDWARE/CERA		1 1	
		KEROVIT KUPA- KS709			1
					1
11	NS	Providing and fixing UPVC pipes 6kg pressure for soil and waste		1	
	INO	water pipes with required specials like bends/tees/union etc.			
		Including making the base and covering the same with cement			
		concrete 1:3:6 as per the direction of the engineer-in-charge.			
			<b>-</b>	+ +	
		75mm dia pipes	9.15	M	+
		NOTE: THE COST SHALL INCLUDE THE COST OF THE			
		EXCAVATION		1	
		MAKES:			
		UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT			

	T				1	
12	NS	100mm dia pipes	12.20	M		
		NOTE: THE COST SHALL INCLUDE THE COST OF THE				
		EXCAVATION				
		MAKES:				
		UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT				
			<u></u>			
13	NS	Providing and fixing viterous china wash basin with pedestal	2.00	EACH		
		including the CP waste complete with required brackets/rawl				
		plugs etc.				
		MAKES:				
		WC : KEROVIT/HINDWARE/CERA				
		KEROVIT CASINO- KS283				
14	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin				
		including PVC. waste fittings complete.				
	17.28.1	Semi rigid pipe				
	17.28.1.1	32 mm dia	3.00	EACH		
	l	1				
15	18.11	Providing & Fixing CPVC pipes complete with fittings and clamps				
		including making good the walls etc. concealed pipe including				
		jointing with the chemical/adhesive, cutting chases and making				
		good the wall:				
	18.11.1	25 mm dia nominal bore	30.49	RM		
		MAKES:		1		
		UPVC PIPES : SUPREME/ASTRAL/PRINCE OR EQUIVALENT		1 1		
16	18.53	Providing and fixing C.P. brass angle valve for basin mixer and				
		geyser points of approved quality conforming to IS:8931				
	18.53.1	15 mm nominal bore	13.00	EACH		
		MAKES:				
		WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT				
		KEROVIT HYDRUS PLUS				
17	NS	Providing and fixing C. P. Brass Center Hole Mixture/ SINK	2.00	EACH		
		MIXTURE of approved quality conforming to IS:8931				
		MAKES:				
		WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT				
		KEROVIT HYDRUS PLUS				
18	NS	Providing and fixing the CP Brass connections for the	13.00	EACH		
		connections from angle valve to the wash basin mixture. The				
		pipe shall have brass ends complete with rubber gaskets etc.				
		, , , , , , , , , , , , , , , , , , , ,		1 1		
19	NS	Providing and fixing 100mm dia. Floor traps complete with the	7.00	EACH		
-		CP. Brass grating both normal grating and grating below the				
		wash basins with and hole for the waste pipe.				
		MAKES:		1 1		
		FLOOR TRAP : SUPREME/ASTRAL/PRINCE OR EQUIVALENT		1 1		
		JALI: 304A STAINLESS STEEL				
20	NS	providing and fixing of complete CP brass accessories set for	2.00	EACH		
-	_	toilets (towel rail, hand towel rail, paper holder, tooth paste				
		stand, soap dishes for wb's and bathing area etc) as per the				
		direction of the Architect.				
				+ +		
21	NS	Providing and fixing the CP brass hand Jet for ablution complete	2.00	EACH		
		with the PVC connection etc.				
		MAKES:				
		WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT		+ +		
		The state of the s		+ +		
22	18.5	Providing and fixing C.P. brass bib cock of approved quality		+ +		
	10.5	conforming to IS standards and weighing not less than 810 gms.				
	18.50.1	15 mm nominal bore	2.00	EACH		
		MAKES:				
		WC : KEROVIT/HINDWARE/JAQUAR OR EQUIVALENT				
	I					

		KEROVIT HYDRUS PLUS				
		RENOVIT III DNOST EOS				
23		Providing and fixing urinal in the Gent's toilet with complete fiitings and hardware. The cost shall include prividing and fixing of one ceramic partition also. (of approved make)	1.00	EACH		
		MAKES:				
		WC : KEROVIT/HINDWARE/CERA KEROVIT ARUSA- KO512W				
		RENOVII AROSA- ROSIZW				
24	NS	Providing and fixing handmade stainless steel sink with sink mixture and all accessories including the cost of cutting of the granite/slab/tiles. Single Bowl 230 mm deep.	1.00	EACH		
		MAKES: SINK: NIRALI, KOHLER, AMERICAN STANDARD				
		NIRALI ELOR SMALL				
25	NS	Providing and fixing Black Granite for the counters/outer verandahs /floorintg/skirting etc including the cost of providing single moulding and polishing the same. The cost shall also include the cost of making the sub-base and fixing the granite with neat cement slurry and filling the joints with grout of desired shade as per the direction of the Engineer-in-charge.	8.46	SQ.M		
26	4.1.5	1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size)	2.02	CU.M		
27	NS	Providing and laying RCC slab with mix 1:1.5:3 (one cement: 1.5 sand: 3 aggregate) for the Kitchen Platform 3" thick including the cost of shuttering AND reinforcement and any other sundries required. The work shall also include keeping the provisions for the sink as per the required size	1.49	SQ.M		
		The steel reinforcement shall be 10mm dia bars @ 5"c/c bothways.				
28	NS	Providing and laying RCC lintel for the doors of 150/230mm x 150mm in RCC with mix 1:1.5:3 (one cement: 1.5 sand: 3 aggregate) including cost of 5-12mm dia bars and rings of 8mm dia placed @ 5"c/c. The work shall include the cost of required shuttering or any other sundries.	5.49	RM		
29	NS	Dismantling the existing walls/rcc/floor/ and other civil items etc. complete, providing the required supports in terms of steel girders/rcc beams and making good the surfaces damaged or as per the direction of the engineer-in-charge. The work shall also include removal of the same to an appropriate location as permissible to the local authorities or as per the direction of the Engineer in-charge. (Note: The amount is expected after deduction of amount to be deducted for the buyback of the existing furniture)	1.00	LS		
30	NS	Plastic Emulsion paint  Providing and applying Plastic Emulsion paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including applying 2 coat of P.O.P to give a smooth surface, complete in all respects (Colour to approval) applicable to old or new.	175.00	SQ.M		
		MAKES:				
		PAINTS : ASIAN/NEROLAC/DULUX/BERGER				
31	NS	External Emulsion paint				
<u> </u>		Providing and applying External Emulsion paint three coats to give an even shade after preparation of surface for painting by scrapping etc. & filling including one primer coat, complete in all respects (Colour to approval) applicable to old or new.	100.00	SQ.M		
		MAKES:				

	PAINTS : ASIAN/NEROLAC/DULUX/BERGER			
32	FLUSH DOORS			
	providing and fixing of partly glazed wooden door shutters	8.78	SQ.M	
	using 32 mm readymade ISI flush door shutter with 1.0mm thick			
	laminate of desired shade/textures and gloss as per drawing			
	with teak wood frame of 150mm x 62.5mm. The door shall have			
	6mm thick teak wood lipping all around the edges. The door			
	shall have vision panels with 8mm thick clear float glass with			
	etching fixed with double 14mmx25mm thick teak wood			
	moulding as per design. The exposed surface of wood shall be			
	deco painted in desired shade. The door shall be complete in			
	all respect with hardware handles, godrej 6-lever lock/night			
	latch lock, door stoppers, 8" tower bolts, hinges etc all in brass.			
	MAKES:			
	FLUSH DOOR: CENTURY/GREEN/DURO OR EQUIVALENT			
	MICA: GREEN/SUNMICA/MARINO OR EQUIVALENT			
	ADHESIVE: FEVICOL SH/ VAMICOL/JIVANJOR OR EQUIVALENT			
	GLASS: SAIN GOBAIN/MODI GLASS/ASAHI FLOAT GLASS			
	LIPPING/MOULDING: CP TEAK FIRST CLASS			
	HARDWARE: OZONE/DORMA/GODREJ			
33	ACP BASE/FRAME LED ACRYLIC SIGNAGE			
	providing and fixing acrylic signage made with router cutting or	4.65	SQ.M	
	moulding of a- cast acrylic in desired colour as per logo design			
	with the thickness of letter or logo atleast 3" thick. The base			
	made with MS sheet powder coated or with ACP sheet and as			
	per requirement special vinyl pasting on the logo. The complete			
	signage with backlit water proof and heavy duty LED lighting including provission for easy repairs after installation complete.			
	MAKES:			
	ACP: ALSTONE/ALUDECOR/EUROBOND OR EQUIVALENT			
34	TEXTURE PAINT:- ( Spectrum Finish )			
	Providing & applying spectrum surface texture finish of	20.00	SQ.M	
	approved shade & colour on walls as per requirement &			
	manufacturers recommendations.			
	MAKES:			
	TEXTURE PAINT: SPECTRUM/ASIAN/ALTEC OR EQUIVALENT			
35	DAMP PROOF COURSE			
	Providing and laying damp-proof course 40mm thick with	3.82	SQM	
	cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III)			
	derived from natural sources : 4 graded stone aggregate			
	12.5mm nominal size derived from natural sources)			
	Total Value of Works			
	NOTE: GST SHALL BE PAID EXTRA			
			1	