	PRICE BID						
	F NICE DID						
SN		DESCRIPTION	UNIT	QTY	RATE	AMOUNT	
1	Supply, Installation, Testing and Commissioning of double skin Air handling Units, with coil section having 6 Rows deep chilled watercooling coil, 50mm thick (EU-4) box type pre filter, imported DIDW centrifugal forward curved fan, drive set with v-belt & motor (EF-2) including duct & fire damper of following specifications AHU's complete in all respects.						
	Outer Sin	0.6 mm Pre-coated GI					
	Inner Skin	0.6 mm plain GI					
	Frame work Thickness of Insulated	Hollow extruded A1 profile  40 mm thick , CFC free PUF injected					
	panels	(Density: 40 kg/cu.m)					
	Material of drain Unit base	20 gauge ss-304 tray duly insulated with 13 mm closed cell nitrile insulation GSS base Channel					
	CHW coil	AHRI certified as per test standard ARI-410 & UL certified for safety					
	Coil Casing	GI					
	Material of tube Tube Dia	copper 12.7 mm/ 1/2" 0.D					
	Thickness of Tube	0.41mm					
	Header Material	copper					
	Thickness & material of Fins	0.15mm plain Aluminium					
	No. of fins per inch (FPI) FILTERS:	11-13 No.					
	Media of Filters	Synthetic (non-woven type)					
	Eficiency of Pre Filters (EU-4)	90% down to micron					
1.1	AHU CAPACITY 14,000 C		No.	1			
1.2	AHU CAPACITY 20,000 C		No.	1			
2	Make:- Edgetech /Zeco/R Supply & Installation of M 25mm Nitrile insulation.						
	Dia- 80mm	piece in an imposed maner (min/official	Rft	60			
	Dia- 100mm		Rft	36			
3	Supply & Installation of 80mm MS Butterfly valves duly insulated with 25mm Nitrile insulation, complete in all respects. Make:- Advance /L&T/Audco						
	Dia- 80mm		No.	4			
4	Dia- 100mm  Supply & Installation of 80mm MS Balancing valve duly insulated with 25mm Nitrile insulation, complete in all respects. Make: Advance /Castle/ Zoloto		No.	2			
	Dia- 80mm		No.	2			
	Dia- 100mm		No.	1			
5	Supply & Installation of MS Y-Strainer duly insulated with 25mm Nitrile insulation, complete in all respects. Make: Advance /L&T/Audco						
	Dia- 80mm		No.	2			
6		ing & Commissioning of GSS square/ icated on Site complete with gaskets, elbows,	No.	1			
	splitters, vanes, supports etc. as per specification and as required for air distribution Make:- SAIL/TATA		Commit	40			
7	Supply Installation Tests	in & Commissioning of 10mm thik	Sqmt	40			
	Supply, Installation, Testin & Commissioning of 10mm thik  Acoustic lining of supply air ducting complete with Aqua sound as per specifications. Make: A-flex/ K-flex		Sqmt	20			
8	Wall Mounted panel complete with incoming status including Star Delta / Dol starter for Air Handling Unit complete as required. Make: L&T/Power Associated		No.	2			
9	Supplying and Laying of Al PVC/XLPE Armoured cables with 2 no. 8 5WG GI wire 16 sq. mm*4 Core Make: Havell/KEI/Polycab		Mtr	30			
10	Civil works including dismantling of wall & door, if required,reconstruction,re-fixing of door,plastering and painting complete as required		Job	1			
	SUB-TOTAL(Rs.)(Sum from 1 to 9)  Buy Back of Old material: Dismantling & Removal of Existing 14000cfm AHU's including the CHW pipes, valves, motors cables, panels etc. and making good the damages done in the process of removal to entire satisfaction of SBI.						
10	Existing 14000cfm AHU's i panels etc. and making go	ood the damages done in the process of removal to	Set	2			
	Existing 14000cfm AHU's i panels etc. and making go	ood the damages done in the process of removal to	Set	2			
	Existing 14000cfm AHU's i panels etc. and making go	ood the damages done in the process of removal to	Set	2			