



STATE BANK OF INDIA
LOCAL HEAD OFFICE PATNA

DATE : __-__-2025

ADMINISTRATIVE OFFICE MUZAFFARPUR

Name of the work:- INTERIOR DECORATION & FURNISHING WORK OF HOME LOAN CENTRE SIWAN UNDER RBO SIWAN

PRICE BID

Sl.No	Description	Unit	QTY	Rate (RS)	Amount
1	BACK CABINET of CM, CABINET BELOW GRANITE COUNTERS IN PANTRY AREA 750MM HT	Sqm	14.50		
	Making and fixing low type storage cabinet with drawer and cupboard with shelf as per the drawing / design all made of 19 mm thick BWR block board of Green/Century /Mayur/aSEAN or equivalent/ Exterior Grade MDF board of Green/Century or equivalent top and front laminated with 0.8 mm thick blue / white high glossive laminate of Green/Marino /century/Durian or equivalent . Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be melamine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per approved materials Colour laminate and specifications. This includes cabinets as per requirement in kitchen. Shutters shall be hinged to the framework and finished with 1.0mm thk. PVC Laminate of approved shade for kitchen cabinets from outside, applied with approved oil paint from the inside and edges of shutters with steam beach lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				
2	Column / Wall Panelling (upto false ceiling ht)				
	Providing and fixing in position panelling made out of GI /BWR PLY frame with intermediate spacing of 600mm c/c horizontally as well as vertically. Frame to be covered with 8mm thick BWR Grade ply/ 12mm thick MR GRADE MDF board (of approved/equivalent make). The surface so prepared shall be pasted with 0.8 mm thick blue / white high glossive/matt finish laminate (of approved or equivalent make). Measurement will be done upto false ceiling only. All work to be completed as per drawing, design, specification and direction of Engineer-in-charge /Bank. All electrical wires, accessories, telephone wires, etc, shall be run in the panelling as per Electrical Drawings and designs. Nothing extra shall be paid for the co-ordination of the same. All items necessary for completing the above mentioned work are deemed to be included in the scope of work, whether or not they are specifically mentioned in the B.O.Q / tender documents / drawings. All complete as per drawings, designs, specifications and directions of Engineer-in-Charge.				
2.1	Wall & column panelling (BM Chamber)	Sq.M	45.00		
	DOOR				
3	FRAMEDGLASS DOOR WITH WOODEN BOTTOM SUPPORT AT MAIN ENTRY/BM CABIN				
3.1	Providing and fixing frameless fully glazed 12mm thk toughened glass fixed with necessary wooden bottom including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS handle over glass. Rate shall include necessary floor springs, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length) & FIXED GLASS WITH WOODEN BOTTOM AND TOP ABOVE OPENING DOOR AND AREA ADJACENT TO DOOR	Sq.M	27.50		
4	FROSTING FILM ON CLEAR GLASS	Sq.M	39.50		
	Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyster film with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.) 3M - CRYSTAL GLASS FINISHES 7725 SE325				
5	LOCKS				
	P/F/F Godrej/link locks and night latches as per requirement.	No.	4		

7	GYPSUM FALSE CEILING				
	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with wedge of 80 mm with tapered flanges of 26 mm each having clips of 10.5 mm at 450 mm centre to centre shall be fixed in a direction perpendicular to G. I. channel with connecting clips made out of 2.64 mm dia x 230 mm long G. I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long.				
	including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge including the cost of putty and painting with specification as below:				
	Plastic Emulsion paint on gyp board false ceiling: Wall/ceiling painting with plastic emulsion paint of approved brand and manufacture to give an even shade in Two or more coats on new work. White cement based putty on false ceiling: Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.				
	Rate includes cutting, adjusting the existing 2'x2' false ceiling alignment etc so that its aesthetic look shall be retained.				
	A 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) For the area where vertical design etc to be done measurement shall be made in running metre for the verticals and shall be payable additional to plan area.	Sq.M	45.50		
8	OFFICER'S TABLE				
	Providing and fixing the Officer's table made out 19mm BWP ply board with 0.8mm laminate as per drawing detail enclosed, storage unit with 3 drawer, and keyboard and pencil drawer on channels, cable manager, and laminated apron to match decor. Drawer unit and verticals made out of 19mm BWP ply board with keyboard drawers, PC stands for PC below worktop and 12mm ply board for footrest. All Drawers to be provided with Godrej lock & SS handle of approved make. The exposed side of front facade, drawer front shall be finished with 0.8mm laminate as per drawing. the inside surface also finished with white/blue colour paint as per approved A/E/I/Bank.				
	a FOs TABLE	Nos	1		
	(5'0"x3'0"x2'6") LXWXH WITH 3'9"x1'6"x2'6" CREDENZA				
	b BM TABLE	Nos	1		
	(6'0"x3'6"x2'6") LXWXH WITH 3'9"x1'6"x2'6" CREDENZA				

9	ROLLER BLINDS				
	a Supply and installation of roller blind of blue color for window of polyester based fabric of Vista make all complete and inclusive the all taxes as per the direction of Architect/E/I/Bank	Sq.M	10.50		
10	DISMANTLING, TRANSPORTATION OF WOODEN, CIVIL,ELECTRICAL AND GLASS ITEMS				
	Dismantling of existing fully glazed/panelled/semiglazed partition (full/low ht), cabinet, glass door, tables etc from old premise/store and shifting it to new premise/place/store and fixing as per requirement and direction of EIC. A lumpsum of 95 sqm dismantling is to be done.	LS	1		
11	REPAIR WORK ON OLD CABINET, TABLE, PARTITIONS, GATE				
	Repair work on old low storage cabinets, partitions, tables , doors etc as per requirement etc. Payment shall be made for repaired area as per actual. (mica pasting and other minor repair work including supply of 0.8mm mica, 3-6mm ply as per requirement. Rate is inclusive of cutting and finishing.	Sq.M	10		
12	FALSE CEILING (GYPSUM TILE GRID)				
	Providing and fixing of Gypsum tile false ceiling tile of size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Prelude XL Hot dipped galva-nized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independent-ly. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-coordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.	SqM.	142.5		
13	ACP PANELLING/PARTITION/COVER BOX				
	Providing and fixing ACP for panelling/partition/shutter box: Providing and fixing of ACP cover for rolling shutter/partition for ATM/branch & its UPS and ACP Panelling in ATM within inner ALuminium box section cover frame work of 50mmx50mm placed at suitable spacinfng not exceeding 600mmc/c. The work is to be finished with 3mm thick exterior grade Aluminium Composite Panel (ACP) cladding of approved make and shade with grooves duly treated with silicon sealant.The work is to include all necessary materials, ac-cessories, labour, tools & tackles.Executed covered area shall be measured for fin-ished work.	SqM.	6		
14	FULL/LOW HEIGHT SEMI/FULLY GLAZED/SOLID PARTITION				

	Providing and fixing double skin partly paneled & partly glazed or solid full /lowheight partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members at maximum intervals of 600 mm x 600 mm with provision of bigger members at skirting, fixing to false ceiling (if provided) fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 6 mm thick MR grade plywood/ of Green/Century/Asean/as per tech specs and .8 mm thick (Greenlam / century /durian/IS certified) blue / white high gloss laminate with grooves / small / panels cut and pasted in the same as per typical design, on both sides so as to form able skin partition to level 900 mm and with 5.50 mm clear float toughen glass of approved make as above at item-1 of Modi float or equivalent above, etched / etching film pasted as per design fixed in wooden frame and with teak wood beading as per detail design, which is to be of 1st quality teakwood (all visible wood to be of 1st quality teakwood) and shall be polished and protected with melamine polish. The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fas-teners so as to form a stable system / partition all	SqM.	45.3		
15	DECORATIVE PANELLING/CEILING				
a	Providing and fixing Charcoal finishing on above specification panelling (SNO. 2)				
	Hall 8 FT X4 FT BASIC PRIZE 8500 /- @PCS	SqM.	6.5		
b	Providing and fixing Louvers plank 4.5"X9" thk 8'-9'6"long finishing on above specification panelling make dexaart/ europateek or equivalent(Basic rate for each plank=1050/-	SqM.	5.35		
c	Providing and fixing 9 mm MR ply on gypsum false ceiling finished by 1.0mm laminate as per approved by Bank Engineers/ architect hanging false ceiling chanel on gypsum board same as above item LAMINATE Basic rate 2250/- per sheet Taxture/Veneer finish laminate in pattern	SqM.	7.5		
15	HYDRAULIC DOOR CLOSER				
	Providing and fixing hydraulic Hardwyn, Everite or approved make equivalent door closures of Hardwyn, Everite or equivalent approved brand and sample – all complete as per instructions of the Bank. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank.	Nos	4		
16	SHOW CASE RACK				
	Supplying and fixing of wall hung award or achievement showcase in BM Chamber of minimum size 5ftx4ftx8"deep of wooden/plyboard with glass shutter , magnet on the elevation area. The front must have glass with arrangement of lock etc.	Nos	1		
TOTAL IN INR EXCL. GST					
Note:-					
1)	Extra members, wherever required for stability / otherwise, to be provided with the required finish without any extra charges.	ALL PLY/MDF MAKE -Green ply /Century/Austin/ACTION TESA/Green panel/ASEAN/Tajpuria/Equivalent/as per technical specs. Use of MDF as per direction of EIC. Vendor shall not be allowed to use the MDF at any place without prior permission by EIC in the layout. Laminate/Mica - Greenlam/Marino/Century/Europateek/Durian/ as per technical specs Hard ware and fitting as mantioned in specification refer technical specs/item description Rate is exclusive of GST GST payable as per Bank rule.			
2)	Any damages caused to the walls, ceilings, floors, etc. shall be made good by the Contractor by refinishing the same in exactly the same manner, so as to leave the surfaces in a good-as-new condition. A final coat of paint on all painted surfaces shall be deemed to be included in the occupation, so as to leave the premises in a suitable condition for occupancy.				
3)	Contractor shall made and get approved shop drawings of all items prior to fabrication / manufacturing of the same.				
4)	In case of partitions / panelling / etc., if any corbellings, cornices, etc. are called for, these shall be done as shown in the drawings, designs, etc., or as per the requirement of the Employer / Architect, and these shall be paid for at the square foot rate quoted by the contractor. Nothing extra over and above the square foot rate shall be payable to the contractor				
5)	The contractor shall extend full co-operation to the other contractors viz. Electrical, Airconditioning, and any others who may be working in the said premises.				
		(Signature) AUTHORIZED SIGNATORY			